Occoquan Forest Sewage Pumping Station and Force Main Replacement

Community Meeting #1 April 29, 2018

SA Project Manager:

Debbie J. Maxwell, P.E., CCM

Design Engineer:

Whitman, Requardt & Associates, LLP





Agenda

- Service Authority (PWCSA) Basics
- Definitions
- Existing Layout & Facility History
- Purpose of the Project
- Proposed System Improvements
 - Pump Station Design
 - Siting
 - Architecture
 - Landscaping
 - Access
 - Force Main Design
 - Alignment
- Site Activities and Notes of Interest
- Anticipated Construction Schedule
- Contacts & Q&A





PWCSA Basics



1.4 Billion Dollars in Assets

22

WATER STORAGE TANKS 10.4 Billion Gallons
of Water Distributed per Year



15 WATER BOOSTER STATIONS

9.2 Billion
Gallons
of Wastewater Treated per Year

59 Wastewater Pump Stations

1,100 Sewer

...... 1,200 Water

338 EMPLOYEES

2,300 MILES OF PIPELINE



Water Capacity
67.9
Million Gallons/Day

Wastewater Treatment Capacity 43.8
Million Gallons/Day





Definitions

Sewage Pumping Station

 A gravity sewer sump with a pump to lift accumulated sewage to a higher elevation

Force Mains


 A pressurized sewer line to convey wastewater from a lift station to another service level and gravity sewer

Gravity Sewer Lines

 Sewer lines constructed to allow the wastewater to flow based on a downward slope



Existing Layout



- ► Well Site
- L36 Existing Sewage Pumping Station
- Shaded area Service Authority owned property



Existing Facility History

History of Sewage Pumping Station and Force Mains

- Constructed in the early 1970s
- The sewage pumping station has reached the end of it's useful life
- The force main is old cast iron piping


History of the Water Treatment Facility and Wells

- Constructed in the early 1970s
- Removed from service December 23, 2015 with the extension of the water main along Davis Ford Road into Occoquan Forest



Existing Facility History

Sewage Pumping Station and Force Mains





Existing Facility History



Sewage Pumping Station







Purpose of the Project

Sewage Pumping Station and Force Mains


- Replace antiquated sewage pumping station and force main
- Provide a more aesthetically pleasing sewage pumping station
- Provide permanent emergency back-up power supply
- Improve safety conditions at the sewage pumping station
- Reduce maintenance
- Demolish existing sewage pumping station
- Extend electrical service to the pavilion
- Provide water access to the pavilion area

Water Treatment Facility and Wells

- Demolish the existing facilities
- Regrade and stabilize the three sites



Proposed Layout of Sewage Pumping Station Site



- L36 New, relocated Sewage Pumping Station
- Existing Sewage Pumping Station is demolished
- Wells are demolished
- Water Treatment Facility is demolished
- Shaded area Service Authority owned property conveyed to the OFOA
- Additional Items:
 - Water service connection near the pavilion area
 - New electrical service to the pavilion
 - Storm inlet replaced at the cul-de-sac
 - Mill and overlay asphalt along access road to replace/repair existing asphalt
 - Install new gravel along access road
 - Additional landscaping near new sewage pumping station

Proposed Layout of Sewage Pumping Station Site



Exterior façade

- Precast, stamped concrete panels
- Dark appearance

Roof

- Pitched
- Brown Shingles

Fencing


 Black vinyl coated chainlink fence

Landscaping

- Evergreen shrubs/trees
- Northeast side to provide some shielding



Proposed Force Main



Force Main

- Approximately 3,733 feet
- 6-inch ductile iron pipe

Gravity Sewer

- Approximately 55 feet
- 10-inch PVC pipe

Roadways

Mill and Overlay



Summary of Proposed System Improvements

Project Summary

- Demolition of treatment facilities,
- Demolition of existing Sewage Pump Station #36,
- Demolition of existing Well #2 and Well #5,
- Construction of a new sewage pumping station and associated yard piping,
- Installation of precast manufactured building,
- Installation of approximately 3,733 feet of 6-inch diameter sewer force main,
- Installation of approximately 55-feet of 10-inch diameter gravity sewer Installation of a water service connection near the pavilion,
- Installation of electrical service to the pavilion,
- Mill and overlay VDOT and Access Road, and
- Installation of additional gravel along Access Road



Site Activities

Activities

- The Contractor will determine the final sequence of construction
- The existing pumping station must stay in operations while the new pumping station is being constructed
- Construction, demolition and restoration may happen concurrently
- The Service Authority is committed to restoring any property affected by the construction to original or better conditions



Notes of Interest

Construction Notes of Interest

- Notifications will be provided by the Service Authority and the Contractor for any anticipated interruptions
- Access will not be interrupted
 - Emergency Services, school buses, trash, mail and other services will not be disrupted
- Temporary parking or staging areas will be coordinated with the OFOA if needed by the Contractor prior to construction
- Daily clean-up by the Contractor is required
- A Service Authority Inspector will cover this project and others close by and will be on site on a daily basis



Anticipated Construction Schedule

- Project Duration (includes 3 projects)
 - 455 days / 15 months
- Anticipated Start Date:
 - Award Contract in September 2018
 - Notice to Proceed in November 2018
 - On-site Construction start anticipated for Winter 2019
- Anticipated End Date:
 - Spring 2020
- Weekday Hours of Operations
 - 7:00 a.m. to 5:00 p.m.



Contacts

- Community Relations & Outreach Liaison
 - Kathy Bentz
 - 703.335.8944

Or

- Email: Occoquan36@pwcsa.org
- Website: www.pwcsa.org
- Project Specific Website: http://www.pwcsa.org/Occoquan36-project



Q & A

Any Questions?

