

## Project Summary

### Heritage Hunt Sewage Pumping Station and Force Main

#### Project Description:

Prince William Water owns and operates the Heritage Hunt Sewage Pumping Station (SPS) in the Little Bull Run Sewer Shed. Prince William Water is upgrading the existing Heritage Hunt SPS to convey up to 7.81 Million Gallons per Day (MGD) to meet sewage demands in the Little Bull Run and Catharpin Creek Sewersheds in conformance with the current Prince William County Comprehensive Plan.

The existing force main (FM) system consists of a 16-inch ductile iron and a 10-inch PVC FM that act in parallel. The existing FMs do not provide sufficient capacity to convey the ultimate flow of 7.81 MGD. An additional 8,200 feet of ductile iron FM will convey wastewater from the Heritage Hunt SPS to the corner of Heathcote Boulevard and Route 29, where it will connect to an existing 24-inch FM previously installed. Ultimately, the wastewater is conveyed to the Upper Occoquan Prince William Water treatment plant.

#### Project Engineer's Function:

Dewberry Engineers, Inc. (Dewberry) is the Engineer of Record for this project. Dewberry prepared the construction documents for the new sewage pump station and for the new 24-inch ductile iron FM and is providing the SA with construction administration services through the construction and close-out phases of the project.

#### Project Representative's Function:

RK&K is the Project Representative for this project, representing Prince William Water during the construction and providing day-to-day construction management.

#### Project Benefits:

- Increase system capability to meet the current and future flows
- Provide a more reliable facility
- Maintain service reliability for all customers
- Update noise and odor control technology

#### Project Timeframe:

- Public Facility Review Process: Completed February 1, 2017
- Design, Permitting, and Advertisement for Bids: July 2020 through January 2022
- Bid Opening: Held February 15, 2022
- Approval to Award Construction Contract: Board of Directors Meeting on April 14, 2022
- Contract Notice to Proceed: June 22, 2022
- Final Completion of Construction: August 2024

**Project Website:** <https://www.princewilliamwater.org/heritage-hunt-project>

**Project Email Address:** [heritagehunt@princewilliamwater.org](mailto:heritagehunt@princewilliamwater.org)