

# SCADA DESIGN & CONFIGURATION STANDARDS

July 2025

Version 3.03

# **Document History and Version Control**

Document history and version control are used to record detail of minor and major amendments (reviews) to this document over time. It allows anyone accessing the document to know if it is the most current version; when it was last amended; what was changed from the previous version; and who made the change(s).

Version Number	Section	Date	Ву	Description
0.01	All	May 22, 2015	CDM Smith	Draft Version
0.02	All	June 19, 2015	CDM Smith	Pre-Final Version (Incorporates Draft Comments)
1.00	All	July 14, 2015	CDM Smith	Final Version (Incorporates Pre-Final Comments) – Issued for Use
2.00	All	March 2018	IT/SCADA	Document renamed. Overall document review and updates.
2.01	All	April 2018	IT/SCADA	Product updates. Overall document review and updates.
2.02	All	November 2018	IT/SCADA	Product Updates and adding new product for Generator Fuel Level. Edited requirements for PMR. Fixed Appendix J.
2.03	All	November 2020	IT/SCADA	Product part number updates, general updates.
2.04	All	July 2021	IT/SCADA	Product part number updates, general updates.
2.05	All	January 2022	IT/SCADA	Product part number updates, PCSS requirements, general updates.
3.00	All	July 2022	IT/SCADA	Product part number updates, addition of AESS language such that AESS may be provided by SA or GC, decision to be made prior to conformed/final specifications.
3.01	All	January 2023	IT/SCADA	Product part number updates, additional markup of AESS language, modification of Backup Controller type for complex stations.
3.02	All	July 2024	IT/SCADA	Product part number updates, language regarding remote access and wireless technologies. Updated PWCSA to PWW and changed logo. Updates/changes highlighted in YELLOW.
3.03	All	July 2025	IT/SCADA	Updated Service Authority with Prince William Water. Product part number updates highlighted.

# Contents

Docu	ment History and Version Control	i
101	Standards Overview	1
101	101.01 Introduction	
	101.02 Purpose	
	101.03 System Description	
	101.04 Compatibility of Products	
	101.05 Compliance	
	101.06 Document Organization	
	101.07 List of Acronyms and Abbreviations	
110	Tagging Conventions	6
	110.01 Introduction	6
	110.02 Instrument and Equipment Tagging	
	110.02.01. XXXX – Mechanical Equipment Abbreviations	
	110.02.02. XXXX – ISA Instrumentation Tag Identifiers	
	110.02.03. LLL – Loop Numbers	
	110.02.04. S – Optional Suffix	
	110.03 Process Pipe Tagging	
120	Required Design Documents	10
120	120.01 Introduction	
	120.02 References and Applicable Standards	
	120.03 Drawings	
	120.03.01. Drawing Coordination	
	120.03.02. Legend Sheets	
	120.03.03. Control System/Network Architecture Drawings	
	120.03.04. Facility Plan and Equipment/Device Location Drawings	
	120.03.05. Process and Instrumentation Drawings	
	120.03.06. Panel Layouts	
	120.03.07. Vendor-Furnished/OEM Control Panels	
	120.03.08. Installation Details	
	120.04 Specifications	
	120.05 Other Design Documents	
	120.06 Coordination Meetings and Schedule	
400		
130	Contracting	
	130.01 Introduction	
	130.02 PCSS Qualifications Criteria	
	130.03 Applications Engineering	
140	Control Hierarchy	
	140.01 Introduction	
	140.02 Local Control	
	140.03 Remote Control	
	140.04 Backup Control	
	140.04.01. Wastewater Lift Stations	
	140.04.02. Water Booster Pump Stations	21
150	Site Specific Design Requirements	23

	150.01 Introduction	23
	150.02 Wastewater Lift Stations	23
	150.03 Fresh Water Booster Stations	24
	150.04 Elevated Water Storage Tanks	24
	150.05 Fresh Water Metering Stations	
	150.06 Alarm Identification and Prioritization	
	150.06.01. Alarm Configuration	25
160	Programmable Logic Controllers	26
	160.01 Introduction	
	160.02 General Requirements	
	160.03 Standard Components	
	160.04 Programming Software	27
170	Operator Interface Terminals	
	170.01 Introduction	
	170.02 General Requirements	
	170.03 Non-Controlled Sites	
	170.04 Controlled Sites	
	170.05 Programming Software	29
180	Control Panels	
	180.01 Introduction	
	180.02 Communications Panel	
	180.03 PLC Panel	
	180.03.01. General	
	180.03.02. Materials and Construction	
190	System Testing	
	190.01 Introduction	
200	Backup Power and Miscellaneous Monitoring	36
	200.01 Introduction	
	200.02 Uninterruptible Power Supply	
	200.03 Emergency Site Power	
	200.04 Power Monitoring	
	200.04.02. Elevated Storage Tanks, Metering Stations, and Other Non-Pump Stations	
	200.04.02. Elevated Storage Tanks, Metering Stations, and Other Non-Pump Stations	
210	Field Instrumentation	
210	210.01 Introduction	
	210.02 Level	
	210.02.01. Wet Well Level Measurement	
	210.02.02. Water Storage Tank Level Measurement	
	210.02.03. Level Switch	
	210.03 Differential Pressure	
	210.04 Flow	
	210.05 Miscellaneous	
	210.05.01. Ambient Temperature	
	210.05.02. Smoke Detection	42
220	Access Control, Operational Video, and Lighting Controls	43

	220.01 Introduction       43         220.02 Access Control       43         220.03 Operational Video       44         220.04 Lighting Requirements       45
230	Telemetry, Networking, and Cyber Security       46         230.01 Introduction       46         230.02 Telemetry       46         230.03 Networking       47         230.04 Cyber Security       48
Tabl	es
Table Table Table	2 110-1. ISA Instrument Tag Identifiers
A B C D E F	Standard Components Example P&IDs Example General and Design Drawings Example Equipment & Instrument and I/O Lists Alarms, Alerts, and Logging Configuration PCSS/AESS Qualification Requirements
G H I J	Acceptance Testing Remote Site Network Configuration Requirements Sample Schedule Design Review Approximate Sequence and Duration

## 101 Standards Overview

#### 101.01 Introduction

The Supervisory Control and Data Acquisition (SCADA) Design and Configuration Standards (Standards) is Prince William Water's (PWW) design and configuration technical requirements for automation, instrumentation, and process control design and configuration throughout the distribution and collection (D&C) system.

These Standards apply to all new construction. PWW reserves the right to modify any of the requirements for existing facilities that are being upgraded.

## 101.02 Purpose

The purpose of this document is to establish uniformity and consistency by any party providing design and configuration services and/or providing SCADA related equipment for PWW. These standards provide a minimum baseline for all projects involving new construction or the upgrading of existing D&C facilities. Consult PWW before deviating from these Standards, or if the Project Design Engineer (PDE) determines that the Standards do not cover a unique situation.

The PDE must obtain approval in writing to deviate from the standards and requirements presented in this manual. Unless written approval of a deviation is provided by PWW, no deviations are permitted. It is not acceptable to assume Prince William Water design reviewers will pick up on deviations included in the detailed design or electrical schematics. Contact PWW for clarifications, if needed.

The Standards describe acceptable implementation practices and standards that are in accordance with Prince William Water required practices. All users are expected to exercise good professional judgment and apply appropriate industry standards for all projects.

Although the SCADA Standards Design and Configuration Standards dictate much of the automation design for projects, the manual does not contain actual specifications which can be used directly within contract specifications. It is the PDE's responsibility to develop specifications and drawings that incorporate PWW's standards and are acceptable to PWW.

## 101.03 System Description

The top-end system at PWW's Operations Control Center is comprised of a fault-tolerant, open architecture SCADA network consisting of servers hosting various applications including a real-time data historian. Prince William Water operations staff interact with the SCADA system using workstations residing in the control room or remotely through a secure connection to the SCADA system. Programmable Logic Controllers (PLCs) provide all monitoring and control functions at each remote site and interface with the existing and input/output (I/O) data points. All site automatic control logic exists within the remote site. For local monitoring and back-up control at each remote site, a backup touch screen operator interface terminal (OIT) panel and I/O for critical controls is located at the control panel. In more complex process control situations, a second PLC with minimal I/O may be used rather than a backup OIT. In this situation, the Main OIT would be the display for that backup process. This PLC shall be comprised of parts from Appendix A.

## 101.04 Compatibility of Products

Throughout this document, equipment may be described by function, features, or other characteristic. All equipment that has received prior approval by PWW is listed in Appendix A – Standard Components. For purposes of compatibility with the system architecture or key system components, some items are shown as **No "or equal" or substitutions.** Where this constraint is not shown, PWW's preferred manufacturer and model is provided. If a substitution is proposed for any of this equipment, the substitute product must have identical features, capabilities, warranties, and MTBF characteristics, and must be manufactured of equal or better materials.

Refer to Appendix A – Standard Components for information on submitting proposed substitute products for consideration by PWW.

## 101.05 Compliance

PWW's Infrastructure SCADA System is planned around standardized equipment, configuration, and programming in order to minimize maintenance and maximize the efficient operation of the Distribution and Collection system. Any variation from the Standards described in this document and the SCADA Programming Standards document can be expected to extend the time needed for review and acceptance of designs or constructed systems, and may result in the rejection of the design or constructed system.

In order to assist in understanding the requirements of the Standards, the steps typically necessary to complete the process of submitting designs for review all the way through testing and acceptance are summarized below:

Sequence of Control System Submittals, Reviews, and Testing:

- 1. Panel Layout Drawings and Preliminary Test Plan Submittal
- 2. Panel Layout Drawings Submittal Review and Approval Period
  - a. Panel Layout Drawings Re-Submittal Review and Approval Period if Required
- 3. Submittal Review Coordination Meeting
- 4. PCSS Test Plan & Programming Submittal Review and Approval Period
  - a. PCSS Test Plan & Programming Re-Submittal Review and Approval Period if Required
- 5. AESS Programming Submittal
- 6. PCSS Unwitnessed Factory Test (UFT) w/Recorded Results
- 7. PCSS Witnessed Factory Test (WFT) w/Recorded Results
  - a. PWW may, at its discretion, waive the WFT
- 8. Joint on-site AESS / PCSS Operational Readiness Test (AESS/PCSS-ORT)
  - a. This shall include PWW SCADA Personnel to program and test various devices (e.g. Cameras, Badge Readers, etc.) as well as the GeoSCADA integration.
  - b. Separate AESS Operational Readiness Test (AESS-ORT) Only if needed
- 9. Site Acceptance Test (SAT) for SCADA

Each project may be unique, and different design and submittal steps may be necessary to achieve an approved design. Contact PWW as needed to understand and comply with the applicable requirements.

## 101.06 Document Organization

The Standards are divided into 14 sections (plus appendices). Each section has its own numbering sequence and is divided into sub-sections as necessary. The 14 sections and appendices are defined as follows:

Section 101: Standards Overview

Section 110: Tagging Conventions

Section 120: Required Design Documents

Section 130: Contracting

Section 140: Control Hierarchy

Section 150: Site Specific Design Requirement

Section 160: Programmable Logic Controllers

Section 170: Operator Interface Terminals

Section 180: Control Panels

Section 190: System Testing

Section 200: Backup Power and Miscellaneous Monitoring

Section 210: Field Instrumentation

Section 220: Access Control, Operational Video, and Lighting Controls

Section 230: Telemetry, Networking, and Cyber Security

Appendix A: Standard Components

Appendix B: Sample P&IDs

Appendix C: Example General and Design Drawings

Appendix D: Example Equipment & Instrument and I/O Lists

Appendix E: Alarms, Alerts, and Logging Configuration

Appendix F: PCSS Qualification Requirements

Appendix G: Acceptance Testing

Appendix H: Remote Site Network Configuration Requirements

Appendix I: Sample Schedule

## 101.07 List of Acronyms and Abbreviations

The following acronyms and abbreviations are used throughout the SCADA Design Standards Manual:

AE Applications Engineering

AESS Applications Engineering System Supplier

AI analog input

ANSI American National Standards Institute

AO analog output

ATS automatic transfer switch

AWG American Wire Gauge CPU central processing unit

CSI **Construction Standards Institute** 

FRP fiber-reinforced plastic

D&C distribution and collection

DΙ digital input

DNP3 Distributed Network Protocol 3

DO digital output

GC **General Contractor** 

**Human Machine Interface** HMI

HOR Hand-Off-Remote

I&C instrumentation and controls

I/0 input/output

ISA **International Society of Automation** 

LAN local area network MCC motor control center MTW machine tool wire

**NEMA** National Electrical Manufacturers Association

NFPA **National Fire Protection Agency** 

OIT operator interface terminal ORT operational readiness test

P&ID process and instrumentation drawing

**PCSS Process Control System Supplier** 

PDE Project Design Engineer

PLC Programmable Logic Controller

PoE Power over Ethernet PQM power quality meter Prince William Water **PWW** 

REX Request to Exit

RTU remote telemetry unit

**RVSS** reduced voltage soft starter

SAT site acceptance test

**SCADA** Supervisory Control and Data Acquisition

Service Authority Prince William County Service Authority SIT system integration test

Standards SCADA Design and Configuration Standards

SNMP Simple Network Management Protocol

TCP/IP Transmission Control Protocol/Internet Protocol

UFT unwitnessed factory test

UL Underwriters Laboratories

UPS uninterruptible power supply

USB universal serial bus

VAC voltage alternating current

VDC voltage direct current

VFD variable frequency drive

VLAN virtual local area network

WAN wide area network

WFT witnessed factory test

# 110 Tagging Conventions

#### 110.01 Introduction

This section includes the requirements for instrument and equipment tagging including loop assignment on all design projects.

## 110.02 Instrument and Equipment Tagging

Equipment tagging shall be used to identify drawing objects such as instruments, valves, pumps, tanks, and other devices. Pieces of equipment and instrumentation through the plant will be given a tag that can be referenced between mechanical and electrical equipment. No piece of equipment or instrument shall have an identical tag to any other piece of equipment at the same site. Submit the tagging plan to PWW for approval before developing design documents.

The format for all equipment tags shall be as follows: XXXX-LLLS

#### Where:

- XXXX 1 to 4 letter identifier; International Society of Automation (ISA) instrumentation tag identifiers code (for instruments) or, mechanical equipment abbreviation
- LLL 3-digit loop number
- S 1-digit letter optional suffix (A, B, C...)

#### 110.02.01. XXXX - Mechanical Equipment Abbreviations

All equipment, motors, pumps, mixers, etc. abbreviations shall consist of up to 4 letters to describe the type of equipment. Some mechanical equipment abbreviations are shown as follows.

- AC Air Compressor
- ATS Automatic Transfer Switch
- G Grinder
- GEN Generator
- HPU Hydraulic Power Unit
- P Pump
- VFD Variable Frequency Drive

Additional device codes and abbreviations will be jointly developed and approved by PWW.

#### 110.02.02. XXXX - ISA Instrumentation Tag Identifiers

Instrument tagging will follow ISA standards as established in the ISA Standards Book, Library for Measurement and Control: Volume I.

TABLE 110-1, ISA INSTRUMENT TAG IDENTIFIERS

	First Letter(s)		Succeeding Letters		
Letter	Measured or Initiating Variable	Variable Modifier	Readout or Passive Function	Output or Active Function	Function Modifier
A	Analysis		Alarm		
В	Burner, Combustion		Users Choice	Users Choice	Users Choice
С	Conductivity			Control	Closed
D	Density	Differential			Deviation
E	Voltage		Primary Element		
F	Flow, Flow Rate	Ratio			
G	Gauge		Glass		
Н	Hand (Manual)				High
I	Current		Indicate		
J	Power		Scan		
K	Time, Schedule	Rate of Change		Control Station	
L	Level		Light (Pilot)		Low
M	Moisture				Middle
N	Users Choice		Users Choice	Users Choice	Users Choice
0	Users Choice		Orifice		Open
P	Pressure		Point (Test Connection)		
Q	Quantity		Integrate, Totalize		
R	Radiation		Record or Print		Run
S	Speed, Frequency	Safety		Switch	Stop
T	Temperature			Transmit	
U	Multivariable		Multifunction	Multifunction	Multifunction
V	Vibration			Valve or Damper	
W	Weight, Force		Well		
X	Unclassified		Unclassified	Unclassified	Unclassified
Y	Event, State, Presence			Relay or Compute	
Z	Position			Drive, Actuate, or Unclassified Final Control Element	

#### 110.02.03. LLL - Loop Numbers

On every design project, identification numbers for equipment and instruments must be assigned. Project loop numbering shall follow the ISA loop numbering format defined by the ISA standard ISA-5.1, paragraph 4.3.

There are no specific ISA guidelines for assigning loop numbers; however, PWW has standardized on loop number ranges based on the relative location of the process or area grouping. The following are the loop number ranges, by site type, that shall be adhered to on all design projects:

TABLE 110-2.	INNP	NUMBERING	BY CITE TVDE
IADLE IIU-Z.	LUUP	NUMBERING	DISHELIPE

Loop Number Range Process / Area			
	PUMP STATIONS		
100-199	Station Influent / Suction		
200-299	Pumping		
300-399	Station Effluent / Discharge		
400-499	Station Power / Electrical Systems		
500-599	Supplemental Systems / Miscellaneous		
600-699	Water Quality Monitoring / Chemical Addition		
700-799	Building Management		
800-899	Security / Access Control		
900-999	Backup Control		
ELEVATED STORAGE TANKS			
100-199	Primary Piping including Level Measurement		
200-299	Pumping (If Present at Site)		
300-399	Station Outlet / Discharge (If Present at Site)		
400-499	Station Power / Electrical Systems		
500-599	Supplemental Systems / Miscellaneous		
600-699	Water Quality Monitoring / Chemical Addition		
700-799	Building Management		
800-899	Security / Access Control		
900-999	Backup Control		
METERIN	NG / PRESSURE REDUCING STATIONS		
100-199	Pre-Metering / Pre-Pressure Reducing		
200-299	Metering / Pressure Reducing		
300-399	Post-Metering / Post-Pressure Reducing		
400-499	Station Power / Electrical Systems		
500-599	Supplemental Systems / Miscellaneous		
600-699	Water Quality Monitoring / Chemical Addition		
700-799	Building Management		

#### TABLE 110-2. LOOP NUMBERING BY SITE TYPE

Loop Number Range	Process / Area
800-899	Security / Access Control
900-999	Backup Control

#### 110.02.04. S - Optional Suffix

Only used when a given loop has more than one instrument with the same functional identification.

## 110.03 Process Pipe Tagging

Included on process and instrumentation drawings (P&IDs), identification of process piping is an important activity for improved process understanding. All major or minor process piping shall be tagged as follows:

"Size - Service - Spec"

#### Where:

Size Pipe diameter in inches

Service Process service abbreviation

Spec Pipe material abbreviation

# 120 Required Design Documents

## 120.01 Introduction

The Designer shall submit two types of deliverables for SCADA design projects: drawings (plans) and specifications. This section provides an overview of the referenced industry standards, different types of drawings that can be developed as well as an overview of each specification section and when to use it.

This section is presented in general terms to guide the PDE in developing documents that meet PWW's requirements, while allowing some latitude in meeting specific project requirements. The Designer shall submit an outline of the proposed design documents to PWW for approval prior to beginning development of a detailed design.

## 120.02 References and Applicable Standards

The following automation codes and standards shall apply to the D&C SCADA control systems in addition to the Standards. The current revision shall be the standard upheld to.

#### **International Society of Automation (ISA)**

- ISA S5.2, Binary Logic Diagrams for Process Operations.
- ISA S5.3, Graphic Symbols for Distributed Control/Shared Display Instrumentation Logic and Computer Systems.
- ISA S5.4, Instrument Loop Diagrams.
- ISA S20, Specification Forms for Process Measurement and Control Instruments, Primary Elements and Control Valves.
- ISA RP60.3, Human Engineering for Control Centers.
- ISA RP60.6, Nameplates, Labels, and Tags for Control Centers.
- ISA-99, Industrial Automation and Control Systems Security.

#### National Electrical Manufacturers Association (NEMA)

#### National Fire Protection Agency (NFPA)

- NFPA 70, National Electrical Code (NEC).
- NFPA 79, Industrial Control Equipment.

#### **Area Classification**

• PDE to establish classification per codes, Prince William Water, and AHJ.

#### **Project Specifications**

- PDE shall use the reference specifications, modified as required for the project and Approved by PWW, for the project construction documents.
- The reference specifications are available from PWW in electronic format upon request.

#### Underwriters Laboratories, Inc. (UL)

• UL 508 - Industrial Control Equipment - for custom fabricated equipment.

A nationally recognized testing laboratory, as approved by both the Authority having
jurisdiction and PWW (when PWW is not the AHJ), may substitute for UL listing on commercial
off the shelf products.

## 120.03 Drawings

The PDE shall present instrumentation and controls (I&C) design drawings in a logical manner using the following sequence for types of drawings:

- Legend Sheets
- Control System/Network Architecture Drawings
- Facility Plan and Equipment/Device Location Drawings
- P&IDs
- Panel Layouts
- Installation Details
- Demolition Details
- Other drawings as necessary to clearly describe the project

Refer to Appendix B – Example P&IDs and Appendix C – Example General and Design Drawings. These examples are for general arrangement and content only, and are not to be copied or reused for design or submittal purposes. Appendix B and C both include a **REQUIRED BORDER STYLE** for the Panel Drawings and the P&I Drawings.

#### 120.03.01. Drawing Coordination

The physical location of instruments shall be shown on all relevant drawings. With Prince William Water approval of the PDE's Design Document Outline, drawings for different disciplines may be combined for small projects as appropriate. Locate equipment as indicated below:

- Mechanical
  - Locate all field instruments, show interface to mechanical piping (pipe taps, insertion meters, etc.).
- Electrical
  - o Locate all equipment that requires electrical power supply connection.
  - o Locate all equipment requiring signal or communications interconnection.
- Architectural
  - Locate control panels and enclosures on floor plan layouts.
- Structural
  - o Locate instruments on: flumes, weirs, stilling wells
  - Special equipment access railings, bases, and pads
  - o Antennas including antenna base considering wind-loading factor

Care must be taken to specify or detail the field mounting location of all instruments, remote-mounted controls and indicators or displays so that equipment can be easily maintained and operated. Details or coded notes shall be used to clearly define the location and orientation of controls and indicators so

that they can be safely accessed and read. Indicators or displays should face the operator and be horizontally and vertically located so that they can be easily read.

Controls, switches, and keypads must be readily accessible to and appropriately illuminated for the operator.

#### 120.03.02. Legend Sheets

Legend sheets shall be provided to clearly define all of the symbology, nomenclature, equipment and line types shown on the design drawings. Each discipline shall have their own legend sheets for their drawings. Where appropriate, ensure that, on black and white prints and copies, symbology and line types clearly delineate between new and existing equipment, construction and demolition, and other changes to an existing facility.

#### 120.03.03. Control System/Network Architecture Drawings

For all D&C projects, a control system/network architecture drawing(s) shall be provided that quantifies and locates all of the major equipment in the system. The drawings shall show the major components of the network (e.g., communication medium, communication panels and components, and UPS systems), connecting cables and types, all control panels that have controllers connected to the network, and the operator interface devices such as OITs. Any of these components powered by the UPS shall be noted on this drawing.

### 120.03.04. Facility Plan and Equipment/Device Location Drawings

The Facility Plan Drawings shall show the overall site with the location of all planned or visible structures, facilities, driveways, and visible utility lines on the project site.

The Equipment/Device Location Drawings shall show the location of all equipment, whether SCADA-related or not, on the interior and exterior of the facility. Dimensions shall be included to show clearances, heights, and other features to clearly indicate the installed locations. If demolition is required at existing facilities, the equipment to be removed shall be clearly identified on a separate drawing.

#### 120.03.05. Process and Instrumentation Drawings

P&IDs shall show all of the major mechanical equipment and instrumentation for the process, as well as I/O signals to/from the PLC. Refer to the example drawings in Appendix B – Example P&IDs for the acceptable layout of this information. Other information to be shown on a P&IDs is discussed in this section. Loop numbers are used to create a unique tag for each instrument and piece of equipment on the P&IDs. The PDE shall use the loop numbering convention described in Section 2.

The following items shall be shown on P&IDs:

- Power Sources Instruments and vendor control panels shall be shown with the appropriate
  power source as defined by the symbology on the legend sheets. Types of power sources could
  include but are not limited to a UPS system, a power feed from a control panel, a dedicated
  power supply, or a power feed from an electrical power distribution panel.
- Remote vs. Integrally Mounted Displays and Controls P&IDs shall clearly indicate which instruments and valves have their displays and controls locally mounted at the device versus a remote location. The location of each instrument and valve shall be such that all displays and controls are accessible to an operator and technician. Placing displays and controls at inaccessible locations or areas that are difficult to access will be unacceptable.
- Types of Wiring Some instruments are provided with their own power and communication cables while others need to be wired by the electrician. The P&IDs shall clearly indicate these

differences on the P&IDs with different line type symbology to clearly indicate how each instrument is wired.

- Vendor Control Panels In addition to the control system designed by the PDE, there may be other control panels provided with the major mechanical equipment. These are referred to as vendor control panels. If these panels are connected to the SCADA system, they shall be shown on the P&IDs. Vendor control panels shall be differentiated with either a different line type or note that states which Division # (i.e., "discipline") is providing it. Any vendor panels shown on the P&IDs need to be coordinated with the appropriate specification section to ensure that the signals to the control system, communication medium, and panel devices are all properly coordinated.
- Failsafe Wiring Each digital input (DI) to the control system shall be designated with notation to indicate failsafe wiring (i.e., contact opens on alarm or status indication).

#### 120.03.06. Panel Layouts

PWW has developed standard SCADA system control panel layouts and component lists with which the PDE and control panel fabricator shall comply. Any deviation from the standard panel layout and components must be approved in writing by PWW prior to beginning fabrication. Any unapproved modifications cannot be included in any Request for Payment.

Panel layout drawings define the minimum and maximum size requirements for non-standard and/or vendor-supplied control panels. The control panel layout must establish that all of the components will fit within the panel, can be readily accessed for maintenance and/or replacement, and have the required manufacturer's clearances for ventilation.

The panel templates can be found in Appendix C – Example General and Design Drawings. The layout of all SCADA panels shall match the configuration shown on the drawings.

#### 120.03.07. Vendor-Furnished/OEM Control Panels

Vendor provided control panels included as part of packaged systems must generally comply with requirements of these Standards, including brands and models of components described in Appendix A – Standard Components. It is not the intent of this specification that standard or stock control panels be redesigned per the workmanship and material sections defined in this Section. This section does, however, set minimum quality standards that must be met or exceeded. The control panel submittals shall clearly identify exceptions to these specifications.

- Power Supplies Unless otherwise noted, power is provided to the OEM control panels from a single source as listed in the specifications or shown on the Drawings.
  - Power and distribution devices including, control power transformers, power supplies, fuses, circuit breakers, power distribution blocks, terminations and other required components shall be provided to generate all required voltages used by the control panel.
  - Panels including VFDs or motor starters shall be provided with an externally accessible main disconnect.
- Large and Networked PLCs
  - Where OEM panels are provided with PLC components tied to the Plant PCS over a control network, the components shall match the equipment provided by the PCSS for the units provided as part of Division 17.
  - Coordinate with the PCSS to verify that the equipment has been properly selected and that network addresses, data types and register addresses are properly identified.

- Small PLCs Standard or stock OEM panels that are not networked and have I/O requirements totaling less than one full I/O rack, shall be provided with the vendor standard PLC.
- Owner Maintenance
  - All tools, information and equipment required to fully maintain or modify the provided OEM panels shall be provided. Tools and equipment shall include, but not be limited to:
    - Documented PLC/HMI source code and configuration files.
    - Licensed PLC/HMI development software.
    - Connecting cables.
    - Network interface devices.
    - One spare of each type of PLC card provided.
  - Where the PLC source code contains verifiable copyrighted material, the Vendor may request that distribution of the source code be limited outside of PWW's managers and users.

#### 120.03.08. Installation Details

Installation details show the physical requirements for each installation in order for that instrument to be properly installed by the contractor. The details are not meant to replace the manufacturer's installation details and instructions but instead provide the contractor with general requirements specific to the design.

## 120.04 Specifications

The PDE shall prepare specifications in accordance with this SCADA Design and Configuration Standard. Any variation from the requirement of the Standard must be approved in writing by PWW.

The specifications shall be organized per the Construction Standards Institute (CSI). PWW currently uses the 16 division format.

The following is a sample listing of specifications:

**TABLE 120-1. SPECIFICATIONS** 

16	Division Format	50 Division Format	Title
	13300	40 9000	General Provisions
	13302	40 9020	Testing
	13303	40 9030	Training
	13305	40 9645	Control Strategies
	13310	40 9413	Computer Hardware and Software
	13311	40 9443	PLC Hardware
	13320	40 9510	Control and Data Networking Equipment
	13321	40 9553	Fiber Optic Cabling
	13330	40 9513	Control Panels and Panel Mounted Equipment
	13335	40 9514	Uninterruptible Power Supply (UPS) (Single Phase)
	13340	40 9100	Instruments

**TABLE 120-1. SPECIFICATIONS** 

16 Division Format	50 Division Format	Title
13341	40 9141	Flow Devices
13342	40 9142	Level Devices
13343	40 9143	Pressure Devices
13344	40 9144	Temperature Devices
13345	40 9145	Analytical Devices
13346	40 9146	Miscellaneous Devices

## 120.05 Other Design Documents

In addition to drawings and specifications, there are other documents that shall be produced as part of the design. Two required documents are an Instrument List and an I/O List. Each of these lists shall be submitted in both electronic (Excel and pdf) and printed format, and shall follow the templates provided in Appendix D – Sample Equipment & Instrument and I/O lists.

The Instrument List identifies the instruments (and devices, such as limit switches) provided for the project as well as the instrument ranges and initial operational setpoints. The instrument list shall also identify the power requirements, the make and manufacturer of an instrument, and any specific operating or configuration requirements for the device.

An I/O list shows each input and output signal in a list. The preliminary I/O list shall be provided as part of the preliminary design, and the list, along with the control panel design, shall be finalized and approved by PWW prior to beginning fabrication of the control panel. This list shall be organized by I/O card to ensure signals are assigned to the PLC I/O cards to take into account system redundancy. For example, the design shall take signals from multiple pumps for a particular process and spread out the monitoring and control signals for each of those pumps over multiple cards, to prevent the failure of one I/O card from causing all pumps to fail. Spare I/O card points and spare rack slots (spaces) shall be designated in the I/O list.

The I/O list shall also include the SCADA tagname and shall include a space to add the ClearSCADA point ID after the ID has been assigned.

## 120.06 Coordination Meetings and Schedule

Project coordination meetings are mandatory as a part of any project, unless specifically waived by PWW in writing. Where the AESS is performed by or contracted by PWW (covered in Section 130.03), the meetings shall be held at PWW's designated location and shall include attendance by PWW, the PDE, the General Contractor (GC), the Process Control System Supplier's (PCSS's) Project Engineer, and the AESS Project Engineer. The PCSS shall prepare and distribute an agenda before the scheduled meeting date.

A project kickoff coordination meeting shall be held to discuss the PCSS's and AESS's
understanding of the project; discuss the project's submittal requirements; discuss any
proposed substitutions or alternatives; schedule testing and delivery deadline dates; provide a
forum to coordinate hardware related issues; and request any additional information required
from PWW. This meeting should be held prior to the submission of any technical shop
drawings or submittals.

• A submittal review coordination meeting shall be held after the panel drawing submittal package has been reviewed and returned to the PCSS. The purpose of this meeting shall be to review comments made on the submittal package; to refine scheduled deadline dates; coordinate equipment installation activities; and provide a forum for any further required coordination between the PCSS and AESS.

Additional meetings such as factory test coordination and field test coordination may be specified and included at the discretion of either PWW or the PDE. A complete schedule for the project shall be prepared showing all meetings, milestones, deliverables, testing, points of coordination with PWW and/or their contractors, and other significant activities. The schedule shall be updated no less frequently than once a month. All updates shall include a Summary Change document describing the changes that have been incorporated in the update. An example schedule is provided in Appendix I – Sample Schedule.

# 130 Contracting

#### 130.01 Introduction

The entity that furnishes and installs all materials, equipment, labor and services, required to achieve a fully integrated and operational control system is identified as the PCSS. On each construction project, the GC shall procure the services of a PCSS to execute the process control system requirements specified on a given project. In most cases, the AESS services shall also be procured by the GC, however, PWW may choose to perform or hire these services. This decision will be finalized during design and will become part of the project specifications.

## 130.02 PCSS Qualifications Criteria

The PCSS shall be a "systems integrator" regularly engaged in the design and the installation of instrumentation systems and their associated subsystems as they are applied to the municipal water and wastewater industry. The company qualifications and individual resumes of the PCSS are subject to review and acceptance by PWW prior to beginning work on any project. For current PCSS qualification requirements, refer to Appendix F – PCSS Qualification Requirements. The company qualifications and individual resumes of the PCSS are subject to review and acceptance by PWW prior to beginning work on any project.

## 130.03 Applications Engineering

The entity that performs the software development, integration, and commissioning of the control system is identified as the Applications Engineering System Supplier (AESS). On all projects, the AESS scope of work shall include: PLC programming, testing of PLC logic, Main and Backup OIT graphics and control development and testing, and OIT software configuration. In some instances, at the discretion of PWW, the AESS may be required to program, configure, and test the HMI graphics and control and GeoSCADA database development, but typically these activities will be performed by PWW personnel. The cellular router and managed Ethernet switch final configurations, report development, and Access Control and Operational Video devices shall be performed by PWW personnel. Startup/training activities associated with the configured portions of the PLC/HMI/OIT systems shall also be the responsibility of the AESS.

To implement PWW's standard programming blocks, templates, and strategies; all AESS activities shall be performed in accordance with PWW's SCADA Programming Standards. The AESS may be performed by PWW or the Service's Authority's designee. This decision shall be made prior to final/conformed specification documents and shall be clearly noted in those documents whether the AESS activities will be part of the GC's responsibilities to subcontract or if they will be the responsibility of PWW and/or PWW's designee. Where the AESS activities are performed or contracted separately by PWW, the system programming and development shall not be furnished by the PCSS, the PDE, or the GC. The PCSS shall provide all programming required for witnessed factory testing (WFT) and unwitnessed factory testing (UFT), and shall provide one copy of all testing code to PWW in native electronic and printed format.

In the case where PWW provides or procures the AESS services, it is the PDE's responsibility to ensure that the contract documents provides enough time for the AESS to complete all Applications Engineering (AE) activities on the project. Where the AESS services are procured by the GC, it is the GC's responsibilities to ensure proper coordination of events. The following are the minimum time durations that shall be specified on every project where the AESS services are provided or procured by PWW:

- Completion of AESS's Programming A minimum of ninety (90) calendar days are required for PWW or designee to complete the programming necessary prior to the system integration test (SIT). The allotted time period shall not start until panel layout drawings have been submitted and approved. Any additional time required for programming due to changes or errors in the design shall not extend the duration of the contract.
- Completion of AESS's Software Integration Test (if requested) at PCSS's facility Twenty-one (21) calendar days after successful completion and acceptance of the WFT.
- Completion of AESS's Application Software operational readiness tests (ORTs) Twenty-one (21) calendar days after successful completion and acceptance of the PCSS's ORT.

Refer to Section 190 for more information on SCADA system testing.

# 140 Control Hierarchy

#### 140.01 Introduction

PWW utilizes a hierarchical control approach by having layers of control to provide a standard format for monitoring/control of each D&C remote site and configuration of the SCADA servers. At the lowest layer, local control provides the ability to operate the equipment at the device or from a local control panel, independent of the PLC. Remote control provides operations the ability to control the individual equipment or grouping of equipment from either the local OIT or remotely via computer workstations. Remote control shall consist of selecting an operational mode (manual or automatic), and sending control set points and commands to the PLC systems. In turn, each of these commands will activate preprogrammed control algorithms within the PLC software logic. In case of a PLC failure, a backup control system shall be provided to keep the site operational until the PLC can be fixed.

Utilizing this control approach provides operators and maintenance staff a uniform interface which improves their understanding of how to monitor/control the equipment, the control modes the equipment can attain, and how to override the controls when necessary due to failures or when required for routine maintenance. All services provided related to the D&C SCADA System shall support this control approach.

#### 140.02 Local Control

Local controls shall be provided in the close proximity of each piece of equipment. Local controls shall be located on respective equipment motor control center (MCC), VFD or a panel containing motor starter only if the driven equipment can be observed from this location; otherwise, the local controls shall be located next to the equipment. Equipment controls shall be designed such that control is only from one location at a time.

The following are the general requirements for local control:

- Local controls shall be fully independent of the PLC controls and shall only incorporate hardwired interlocks such has high motor temperature, high discharge pressure, low level etc. wired in the motor starter circuit to stop the equipment on detection.
- Local controls shall always take precedence over any remote controls.
- Local controls shall be furnished with LED pilot light indication to display the operating status
  of the equipment.
- A three position Hand-Off-Remote (HOR) switch shall be provided for local controls near the equipment. When the HOR switch is in the "Hand" position, the equipment shall be operated by hardwired logic in the motor starter circuit. While in "Hand" position, any remote control signals from PLC shall be isolated from the motor starter circuit. Any user video display interfaces shall indicate that the equipment is in "Hand".
- When the HOR switch is in the "Remote" position, the equipment operation shall be controlled by the PLC logic. All the hardwired interlocks wired in the motor starter circuit shall still be applicable. Any user video display interfaces shall indicate that the equipment is in "Remote."

## 140.03 Remote Control

Remote control of the remote site and individual equipment shall be performed by the local PLC or the backup control system.

• When the HOR switch is in the "Remote" position, the equipment operation shall be manually or automatically controlled via the PLC logic. All the hardwired interlocks wired in the motor starter circuit shall still be applicable. An equipment "In Remote" status signal from the HOR switch position shall be wired to the PLC system.

While in "Remote "mode, the control system shall have the option of operating the equipment in following two modes.

- Remote-Manual: When Remote-Manual control is active, it means that the equipment is in the "Remote" position in the field and all control decisions shall be initiated by the operator using the software control functions shown on the local SCADA HMI or OIT screen. The operator shall be able to manually start/stop and adjust the speed (if applicable). This is the default mode.
- Remote-Auto: When Remote-Auto control is active, it means that the equipment is in the "Remote" position in the field and the equipment is controlled automatically by the logic programmed in the PLC or by the backup control system. The operator will need to engage "Auto" mode from the SCADA HMI or OIT screen to enable PLC control. The operator shall be able to change the start/stop control function related setpoints when this mode is engaged.

## 140.04 Backup Control

The primary control system for each site consists of a local PLC that interfaces the site's input and output (I/O) signals for monitoring and control of the site's instrumentation and equipment. The PLC will be programmed with custom control logic functions that will automate the operations at each site.

Should the PLC fail for any reason, a backup system consisting of an OIT + PLC combination unit will be used for interim limited automatic control functions. The OIT backup control system consists of a graphical touchscreen panel equipped with logic solving capabilities and integrated I/O for critical system controls. In some instances, as approved by PWW, it may be necessary to use an additional PLC with the Main OIT as a backup control system. Refer to Section 170 for more information on the OIT backup control system.

# The use of hardwired controls as a backup to the PLC in lieu of the backup control system is strictly prohibited.

The backup control system will primarily be used as a traditional OIT system to monitor and control the equipment and instrumentation at each site. The system shall be networked over Ethernet through the wide area network (WAN) to the top-end SCADA system via Modbus Transmission Control Protocol/Internet Protocol (TCP/IP) for communication purposes.

The purpose of the backup control system is to operate the remote sites in a temporary, controlled manner until the primary system is restored. When the backup control system detects a PLC failure or a user initiates a remote command to place the backup controls in service, the system will automatically control the facility based on a pre-programmed logic sequence. A minimal set of I/O required to operate the facility shall be wired to the backup control system. The backup control system shall monitor the health of the PLC through a hardwired connection from the PLC power supply. The power supply is equipped with an alarm relay contact that signifies when the PLC is operating properly. The operating principle of the PLC power supply alarm relay contact is as follows:

- In normal operation, with the PLC in "run" operation, the alarm relay is activated and its contact is closed.
- The relay de-energizes and its associated contact opens whenever the PLC application stops, even partially, due to any of the following:
  - Occurrence of a detected software fault.

- Incorrect rack output voltages
- Loss of supply voltage

Backup operations apply to the following types of remote sites:

- Wastewater Lift Stations
- Fresh Water Booster Pump Stations

#### 140.04.01. Wastewater Lift Stations

For wastewater lift stations, the backup control system shall control the station's lift pumps to pump the sewage out of one or more wet wells. The backup control system will operate the pumps based on the measured wet well level. All wet wells shall be equipped with redundant level instruments. Signals from all instruments shall be connected to the PLC.

The following field signals shall also be interfaced to the backup control system:

- Wet well levels (4-20 mA analog inputs (AI))
- High-High float switch (DI)
- Start / Stop Commands to each lift pump (digital outputs (DOs))
- Any additional I/O as determined by the process control description and PDE in consultation
  with PWW during design required to operate the station in a controlled manner until the
  primary system is repaired.

The backup control system shall operate the lift pumps in response to the selected wet well level. Start and stop level setpoints shall be provided for each pump. The backup control system shall provide options for "Fixed" and "Alternating" pump sequences. For duplex pump configurations, the backup control system shall provide Lead / Lag & Duty / Standby options. For triplex pump configurations, the backup control system shall provide Lead / Lag 1 / Lag 2 and Lead / Lag / Standby options.

For VFD pumps, when the PLC fails, the 4-20 mA speed reference signal will drop to zero. To control the pumps independent of the speed signal, the VFDs must be configured by the PCSS to a default speed when the reference signal fails. The default VFD speed shall be determined on a case-by-case basis in consultation with PWW.

## 140.04.02. Water Booster Pump Stations

Normal operation of the water booster pumps is to control the booster pumps in response to a remote water storage tank level. The remote tank levels are normally transmitted to the local PLC at the pump station; however, if the PLC fails, the pump station may no longer be able to operate to maintain tank level depending on the specific communications configuration. Coordinate with PWW on this configuration.

The following field signals shall be interfaced to the backup control system:

- Station Discharge Pressure (4-20 mA AI)
- Start / Stop Commands to each booster pump (DOs)
- Any additional I/O as determined by the process control description and PDE in consultation with PWW during design required to operate the station in a controlled manner until the primary system is repaired.

The backup control system shall operate the booster pumps in response to the discharge pressure. Start and stop pressure setpoints shall be provided for each pump. The backup control system shall provide options for "Fixed" and "Alternating" pump sequences. For duplex pump configurations, the

backup control system shall provide Lead / Lag & Duty / Standby options. For triplex pump configurations, the backup control system shall provide Lead / Lag 1 / Lag 2 and Lead / Lag / Standby options.

For VFD pumps, when the PLC fails, the 4-20 mA speed reference signal will drop to zero. To control the pumps independent of the speed signal, the VFDs must be configured by the PCSS to a default speed when the reference signal fails. The default VFD speed shall be determined on a case-by-case basis in consultation with PWW.

# 150 Site Specific Design Requirements

### 150.01 Introduction

This section includes Prince William Water requirements regarding the design of various remote sites. Site types included in this section include:

- Wastewater Lift Stations
- Fresh Water Booster Stations
- Elevated Water Storage Tanks
- Fresh Water Metering Stations

It is the responsibility of the PDE to incorporate the following minimum requirements, including alarm management planning, into their contract documents.

### 150.02 Wastewater Lift Stations

Wastewater lift pump stations are generally comprised of a receiving well (wet well), often equipped with a screen or grinder to remove coarse materials; pumps and piping with associated valves; and a discharge flow measurement. In most cases, an emergency generator is provided for emergency site power.

The primary and backup control system at each wastewater lift station shall conform to the requirements of Section 140 of these Standards.

The following are primary requirements for lift station automation design:

- A high level float switch in the influent channel to notify operations if the bar rack (or screening system) is apparently blocked. The switch is wired to the PLC for alarm purposes.
- PLC control of the influent grinder is not required. This equipment will be operated in hand at all times when the lift station is online. The grinder running status and motor overload/failure shall be monitored.
- The primary method of level measurement in the wet well is hydrostatic pressure using submersible level transducers. PWW no longer uses nor allows bubbler systems for continuous level measurement.
- Redundant level measurement shall be provided and connected to the PLC and backup controller, utilizing signal conditioners and isolators.
- Floats shall be provided for alarming and backup control; however, control must be through the PLC (and backup control system if required). The use of hardwired controls (for primary or backup) is not permitted. Hardwired controls may be used as safety interlocks for the equipment. One High-High level float is required per wetwell.
- Pumps should be controlled based on operator enterable setpoints against the continuous wet
  well level. For VFD driven pumps, the speed will be adjusted to maintain an operator
  adjustable wet well level setpoint,
- All process control I/O for pumps shall be interfaced to the PLC by hard wired I/O and not by networked communications. Networked communication for data not used for control purposes is encouraged to take advantage of additional data monitoring opportunities. If networked, devices shall natively support and use Modbus TCP/IP Ethernet communication protocol.

Requests to use non-native protocol converters under special circumstances shall be made in writing to PWW, whose approval or disapproval shall be final. All available process data for networked devices must be accessible by the PLC.

• Other design considerations such as backup control, power monitoring, access control, and emergency generator integration shall be designed in accordance with this document.

#### 150.03 Fresh Water Booster Stations

Fresh water booster stations are generally comprised of one (1) or more booster pumps, suction and discharge pressure, flow, and power instrumentation. In most cases, an emergency generator is provided for emergency site power.

The primary control system at each water booster station shall be a PLC that interfaces with the I/O signals for monitoring and control. Should the PLC fail for any reason, the backup control system shall be used for interim automatic control functions.

The following are general guidelines and preferences for automation design:

- The pumps should be controlled based one or more remote elevated storage tank levels. In most cases, pumps are constant speed and are controlled based on operator enterable setpoints.
- If all remote tank levels are unavailable, any operating pumps will continue to run and the pump will be stopped on high discharge pressure.
- All process control I/O for pumps shall be interfaced to the PLC by hard wired I/O and not by networked communications. Provide networked communication for data only, and enable supplemental data monitoring opportunities. Networked data communications shall use, Modbus TCP/IP Ethernet communication protocol. Networked connections to devices shall not be used for control or to replace hardwired requirements for alarms.
- Other design considerations such as backup control, power monitoring, access control, and emergency generator integration shall be designed in accordance with this document.
- All pressure transmitters for discharge pressure shall be Rosemont smart transmitters with a display.

## 150.04 Elevated Water Storage Tanks

Fresh water storage tanks shall be equipped with level instrumentation, a chlorine analyzer, and an altitude valve. In some instances, emergency generators and tank mixers are also required.

The primary control system at each elevated storage tank shall be a PLC that interfaces with the I/O signals for monitoring and control. Each PLC is equipped with an OIT for local monitoring of the PLC. Unless specifically required by PWW, backup control is not required for these sites.

The following are general guidelines and preferences for automation design:

- Redundant tank levels shall be provided for each tank.
- Tank level measurement shall be provided by pressure transmitters located in the tanks' valve vault or in the base of the tank (depending on the tank style).
- All pressure transmitters for tank level shall be Rosemont smart transmitters with a display.
- A chlorine residual analyzer shall be provided to measure and report water quality.
- PWW requires full control and monitoring of altitude valves.

- Each vault shall be monitored for unauthorized intrusions. Limit switches on hatches, doors, or other access points shall be used in conjunction with the access control system design.
- Other design considerations such as power monitoring, access control, and emergency generator integration shall be designed in accordance with this document.

## 150.05 Fresh Water Metering Stations

Fresh water metering stations are comprised of one (1) or more flow meters and pressure instrumentation. Where determined to be necessary by PWW, these site may also include control valves and/or chlorine analyzers, which must be included in the SCADA system.

The following are general guidelines and preferences for automation design:

- Flow meters shall be interfaced to the PLC for calculating the total flow. The use of a high-speed counting PLC module may be required.
- Each vault shall be monitored for unauthorized intrusions. Limit switches shall be used in conjunction with the access control system design.
- Valve monitoring is not required unless otherwise required by PWW.
- Other design considerations such as power monitoring and access control shall be designed in accordance with this document.
- Unless specifically required by PWW, backup control is not required for these sites.

#### 150.06 Alarm Identification and Prioritization

The primary function of the alarm system is to alert the operator to deviations from normal operating conditions, i.e. abnormal operating situations. The ultimate objective is to prevent, or at least minimize, physical and economic loss through operator intervention in response to the condition that was alarmed. The secondary function of the alarm system is to serve as an alarm and event log so operations staff can analyze the events that have led to current or past incidents. The log can also be used for analysis to optimize D&C system operations.

## 150.06.01. Alarm Configuration

For each design package, the PDE shall ensure that the alarms to be generated by the SCADA system meets PWW's requirements. PWW has defined what conditions are to be configured as alarms, and what conditions are alerts or log entries.

Refer to Appendix E – Alarms, Alerts, and Logging Configuration for general configuration requirements. All equipment shall be provided with the appropriate relays, contacts, or outputs required to provide the indicated alarm or alert information. The PCSS shall configure any required communications, alarms, or alerts in manufacturer-furnished control panel. The PDE shall submit for approval a completed I/O list with the configuration of all alarms, alerts, or logging settings clearly identified. The submittal shall follow the template included in Appendix D – Example Equipment & Instrument and I/O Lists

# 160 Programmable Logic Controllers

### 160.01 Introduction

This section includes the PLCs for control of process instrumentation and equipment at the D&C remote sites. PWW has standardized on the Modicon M340 PLC platform from Schneider Electric. It is the responsibility of the PDE to incorporate the following requirements into their contract documents.

## 160.02 General Requirements

The following are the general requirements for all PLCs (minimum requirements for all parameters are specified in Appendix A – Standard Components):

- Provide PLC equipment with the required memory and functional capacity to perform the specified sequence of operation with the scheduled input and output points.
- Each PLC system shall include a processor, power supply, I/O modules, and communication modules as required to meet system requirements.
- The PLC shall be capable of stand-alone operation in the event of failure of the communication link to the supervisory HMI subsystem.
- The PLCs shall communicate between the OIT; motor starters, VFDs, and other networked components; and field-mounted transducers, switches, controllers, and process actuators. The communication protocol shall be completely transparent to operators at the HMI or OIT.
- VFD status (Run Command, Run Status, Fault, Speed Command and Speed Feedback) signals shall be hardwired to the PLC. All other data is communicated via the network connection.
- Reduced voltage soft starters (RVSS) shall be configured to allow SCADA control when the RVSS is in bypass mode.
- Each I/O drop or I/O location shall include at least 25 percent spare points of each type used (AI, AO, DI, and DO) for future use. The spares shall be the same type of I/O modules supplied. Unpopulated modules may be required to meet this requirement.
- Regardless of the spare requirement, all installed unused points on all I/O modules shall be wired to terminal blocks in the same manner and order that they occur on the I/O modules, including conditioners, filters, fuses, and similar. Unwired spares are not acceptable.
- Where multiple sets of mechanical equipment and instruments are provided for process redundancy, arrange their field connections to I/O modules so that the failure of a single I/O module will not disable the redundant system. This applies to all I/O types. The acceptability of the I/O arrangement shall be at the discretion of PWW.
- The PLC chassis shall be sized to accommodate the number of modules required based on the I/O schedule plus the required spare slots. A minimum of 2 spare slots shall be provided for future expansion.
- The PLC shall have chassis mounted power supplies to power the chassis backplane, and provide power for the processor and applicable modules. Power supply for the PLC shall accept 120 voltage alternating current (VAC) as input voltage.
- Each PLC (**including all I/O**) shall be powered from a UPS power conditioning system installed within the Communications Enclosure.

- DI modules shall be rated for 120 VAC.
- DO modules shall be relay type
- AI and analog output (AO) modules shall be 4-20 mA; isolated type.
- PLC Ethernet network communications (local network only) shall be via Modbus TCP network protocol. The PLC Modbus TCP module shall always be installed in chassis slot 1. If local Ethernet network communications are not required, leave the slot open for future installation.
- Each PLC shall be equipped with a remote telemetry unit (RTU) module to provide Distributed Network Protocol 3 (DNP3) /IP network communications back to the HMI subsystem. This module shall always be installed in chassis slot 2.

## 160.03 Standard Components

Refer to Appendix A – Standard Components for the current list of standard components that are already approved for use in the SCADA system by PWW. Any proposed substitution of manufacturer or model shall be submitted for review and approval by PWW. All submittals must include purchase, installation, and maintenance cost comparison information for the approved and proposed component, as well as availability/source for each.

## 160.04 Programming Software

PLC configuration and application development software (including licenses) shall not be provided on any project. The AESS shall supply and use their own licensed software. The AESS shall program all PLCs in the same version that PWW uses, and this must be discussed and agreed on prior to any programming.

All PLC, HMI, and OIT configuration and testing files and programs developed by the PCSS for the WFT and UFT shall be provided to PWW in native format, along with one printed copy at the conclusion of the testing.

# 170 Operator Interface Terminals

## 170.01 Introduction

This section includes the OITs for local process monitoring and backup control at the D&C remote sites. PWW has standardized on two devices, depending on the control requirements at each remote SCADA site. It is the responsibility of the PDE to incorporate the following requirements into their contract documents.

## 170.02 General Requirements

There are two standard local OITs which apply to the types of sites:

- Non-Controlled Sites For water storage tanks, the OIT is only required for monitoring purposes.
- Controlled Sites For water booster and wastewater lift stations, two OITs are used the Main OIT and the Backup Controller OIT. Refer to the Standard Components table for information on the currently approved equipment.
- Non-Controlled Non-OIT Sites

Some sites do not require an OIT, and are identified as "Non-OIT" sites. These sites have communications and monitoring equipment, but do not have a graphic user interface. Except as required by PWW, sites that only include meters or pressure reducing valves will be Non-OIT sites.

The following are the general requirements for all OITs:

- OITs shall be mounted on the front of the PLC control panel and maintain the rating of the control panel.
- OITs shall be powered from the UPS system.
- The Main OIT shall communicate to the PLC via the Ethernet connection at the managed Ethernet switch.
- The Main OIT and the Backup Controller OIT communicate via the Communications Cabinet WAN connection at the managed Ethernet switch for remote monitoring and programming.
- All OITs shall be mounted no more than 5.5 feet or less than 4.5 feet from the horizontal centerline of the OIT to the floor.

## 170.03 Non-Controlled Sites

The following are the requirements for OITs at non-controlled sites:

• The communication between the OIT and the PLC shall be via the Ethernet connection.

## 170.04 Controlled Sites

At remote SCADA sites with control, the backup OIT is part of a solution which serves as a backup control system. The backup control system shall consist of the following components.

1. Main OIT – Shall communicate with the PLC via Modbus protocol via the OIT's Ethernet connection.

- 2. Backup Controller OIT Mounts directly to the face of the panel and contains backup controller logic. The Backup Controller OIT is connected to Backup Controller I/O in the control cabinet.
- 3. Backup Controller OIT I/O Provides the I/O interface for the Backup Controller for critical controls.
- 4. Interconnected Cabling Provides connectivity between the OIT Controller and its Distributed I/O system. The cable is a manufacture's optional part with various lengths, but PWW requires the use of this part such that the Backup OIT display is mounted on the door while the I/O portion is mounted on DIN Rail on the cabinet back panel.

## 170.05 Programming Software

Programming and configuration software (including licenses) for the components noted in this Section shall not be provided on any project. The AESS shall supply and use their own licensed software. The AESS shall program all OITs in the same version that PWW uses and this must be discussed and agreed on prior to any programming.

All PLC, HMI, and OIT configuration and testing files and programs developed by the PCSS for the WFT and UFT shall be provided to PWW in native format, along with one printed copy at the conclusion of the testing.

## 180 Control Panels

#### 180.01 Introduction

This section includes the requirements for the SCADA system control panels at all D&C remote SCADA sites. Each SCADA site shall be supplied with the following two control panels:

- Communications Panel
- PLC Panel

It is the responsibility of the PDE to incorporate the following requirements into the contract documents.

#### 180.02 Communications Panel

The Communications Panel installed at each site serves as the communications hub for communicating site information back to PWW's Operations Control Center. Each panel includes a router with a cellular interface, and support for an alternate communication media for redundant communication. The panel also includes a Managed Ethernet Switch that manages several virtual local area networks (VLAN) including SCADA, Access Control, and Operational Video. Integrated Power over Ethernet (PoE) allows PoE enabled devices like cameras and access card readers to connect to the managed Ethernet switch or Router. The SCADA UPS system is also housed within this panel. All panel components (except terminal blocks and breakers) shall be rack mounted within a standard 19-inch rack frame.

The following are the requirements / features for all Communications Panels:

- Wall-mount style suitable for mounting standard 19-in. rack-mounted equipment.
- NEMA type 1 for indoor applications and NEMA type 3R for outdoor applications.
- Front and rear access to 19-in. rack equipment provided by three part design: door, center section and wall section.
- Integral top solar/drip shield
- Perforated, vented base with internal, expanded metal, serviceable filter.
- Seamless, foam-in-place gasket to prevent contaminants from entering the panel.
- Locking kit with keys for access control.
- Intrusion switch wired to the PLC.
- 1U Shelf
- Thermostatically-controlled fans to provide airflow to cool current and future internal equipment.

Communication panel layout templates are included within Appendix C – Example General and Design Drawings.

## 180.03 PLC Panel

The control panel at each site is a typical PLC arrangement provided at water and wastewater facilities based on Prince William Water configuration templates. Major components within the panel include the PLC, backup control system, and an OIT.

The following are the requirements for all control panels:

#### 180.03.01. General

- These requirements apply to all control panels fabricated based on PWW's layout templates and custom-designed and approved panels.
- Panel shall be sized and arranged per the templates to accommodate all required equipment for a fully integrated and operational system.
- Each panel shall bear the UL label. Provide ground fault protective devices, isolation transformers, fuses and any other equipment necessary to achieve compliance with UL 508 requirement.
- All panel doors shall have a hasp and staple for padlocking.
- Panels shall be equipped with an intrusion switch wired to the PLC.
- The devices designated for rear-of-panel mounting shall be arranged per the templates. Any variations from the layout template must be approved in writing by PWW. Approvals for variations from the template should not be expected.
- The panels shall be completely fabricated, instruments and devices installed and wired at the PCSS's facility.
- All components shall be mounted in a manner that shall permit servicing, adjustment, testing, and removal without disconnecting, moving, or removing any other component.
- Components mounted on the inside of panels shall be mounted on removable plates and not directly to the enclosure. Mounting shall be rigid and stable unless shock mounting is required otherwise by the manufacturer to protect equipment from vibration.
- All exterior panel mounted equipment shall be installed with suitable gaskets, faceplates, etc. required to maintain the NEMA rating of the panel.
- Refer to ISA Recommended Practice RP60.3 for layout and arrangement of panels and panel mounted components if a variation from the templates is approved.
- The internal components shall be identified with suitable plastic or metal engraved nametags mounted adjacent to (not on) each component identifying the component.
- All panels shall be supplied with suitable nameplates, which identify the panel and individual devices as required.
  - o Front panel shall be labeled using Black 3-ply, laminated engraving stock nameplates with white lettering.
  - Subpanels shall be labeled using White 3-ply, laminated engraving stock nameplates with black lettering

#### 180.03.02. Materials and Construction

- All panels shall be rated (NEMA) according to the installed environment.
- Panels shall be of continuous welded-steel construction. Provide angle stiffeners as required
  on the back of the panel face to prevent panel deflection under loading or operation. Internally
  the panels shall be supplied with a structural framework for instrument support purposes and
  panel bracing. The internal framework shall permit panel lifting without racking or distortion.
  Provide removable lifting rings designed to facilitate simple, safe rigging, and lifting of the
  control panels during installation.

- Each panel shall be provided with full height, fully gasketed access doors. Front access doors with mounted devices shall be of sufficient width to permit door opening without interference from flush mounted instruments.
- The panels, including component parts, shall be free from sharp edges and welding flaws. Wiring shall be free from kinks and sharp bends and shall be routed for easy access to other components for maintenance and inspection purposes.
- The panel shall be suitable for top and bottom conduit entry as required. For top mounted conduit entry, the panel top shall be provided with nominal one-foot square removable access plates, which may be drilled to accommodate conduit and cable penetrations. All conduit and cable penetrations shall be provided with ground bushings, hubs, gasketed locknuts, and other accessories as required to maintain the NEMA rating of the panel and electrical rating of the conduit system.
- All sections shall be descaled, degreased, filled, ground and finished. The enclosure when fabricated of steel shall be finished with two rust resistant phosphate prime coats and two coats of enamel, polyurethane, or lacquer finish which shall be applied by either the hot air spray or conventional cold spray methods. Brushed anodized aluminum, stainless steel, and fiber-reinforced plastic (FRP) panels will not require a paint finish.
- All panels shall be provided with louvers, sun shields, heat sinks, forced air ventilation, or air
  conditioning units and thermostatic controllers as required to prevent temperature buildup
  inside of panel. Panel cooling or heating equipment shall not compromise the NEMA rating of
  the panel.
- All panels shall be provided with thermostatically-controlled fans to provide airflow to cool current and future internal equipment.
- The finish exterior colors shall be American National Standards Institute (ANSI) 61 gray with a textured finish.
- Print storage pockets shall be provided on the inside of each panel. The storage pockets shall be steel, welded on to the door, and finished to match the interior panel color. The storage pocket shall be sufficient to hold all of the prints required to service the equipment, and to accommodate 8.5 inch by 11 inch documents without folding.
- A folding shelf/desktop shall be mounted on the door inside the panel. PWW shall approve the submittal for this shelf/table.

#### 180.03.03. Internal Construction

- All interconnecting wiring shall be stranded, type machine tool wire (MTW), and shall have 600 volt insulation and be rated for not less than 90 degrees Celsius. Wiring for systems operating at voltages in excess of 120 VAC shall be segregated from other panel wiring either in a separate section of a multi-section panel or behind a removable Plexiglas or similar dielectric barrier. Panel layout shall be developed such that technicians shall have complete access to 120 VAC and lower voltage wiring systems without direct exposure to higher voltages.
- Power distribution wiring on the line side of fuses or breakers shall be 12 American Wire Gauge (AWG) minimum. Control wiring on the secondary side of fuses shall be 16 AWG minimum. Electronic analog circuits shall utilize 18 AWG shielded, twisted pair, cable insulated for not less than 600 volts.
- Power and low voltage DC wiring systems shall be routed in separate wireways. Crossing of different system wires shall be at right angles. Different system wires routed parallel to each

other shall be separated by at least 6-inches. Different wiring systems shall terminate on separate terminal blocks. Wiring troughs shall not be filled to more than 60 percent of the cross-sectional area of the trough.

#### Terminations

- All wiring shall terminate onto single tier terminal blocks, where each terminal is uniquely and sequentially numbered. Direct wiring between field equipment and panel components is not acceptable.
- o Multi-level terminal blocks or strips shall not be used.
- Terminal blocks shall be arranged in vertical rows and separated into groups (power, AC control, DC signal). Each group of terminal blocks shall have a minimum of 25 percent spares.
- Discrete inputs and outputs (DI and DO) shall have two terminals per point with adjacent terminal assignments. All active and spare PLC and controller points shall be wired to terminal blocks.
- AI /AO shall have three terminals per shielded pair connection with adjacent terminal
  assignments for each point. The third terminal is for shielded ground connection for cable
  pairs. Ground the shielded signal cable at the PLC panel. All active and spare PLC and
  controller points shall be wired to terminal blocks.
- o Wire and tube markers shall be the sleeve type with heat impressed letters and numbers.
- Only one side of a terminal block row shall be used for internal wiring. The field wiring side
  of the terminal shall not be within 6-inches of the side panel or adjacent terminal or within
  8-inches of the bottom of free standing panels, or within 3-inches of stanchion mounted
  panels, or 3-inches of adjacent wireway.
- Circuit power from the PLC panel out to field devices (switches, dry contacts etc.) that are used as discrete inputs to the PLC input cards shall be isolated with an isolating breaker switch terminal block with an LED blown fuse indicator. (Phoenix Contact TCP type resettable Thermal Device circuit breaker Example: 2 amp version is Phoenix Contact part number 0712217, include base that provides LED for blown fuse indication). Each circuit must be sized accordingly.
- All PLC discrete outputs to the field shall be isolated with an isolating breaker switch terminal block with an LED blown fuse indicator. (Phoenix Contact TCP type resettable Thermal Device circuit breaker Example: 2 amp version is Phoenix Contact part number 0712217, include base that provides LED for blown fuse indication). Each circuit must be sized accordingly.
- All wiring shall be clearly tagged and color coded. All power wiring, control wiring, grounding, and DC wiring shall utilize different color insulation for each wiring system used. The color coding scheme shall be:

#### **TABLE 180-1. WIRE COLOR CODING SCHEME**

Wiring System	Wire Color		
120 VAC Hot Incoming	Black		
120 VAC Hot Wiring downstream of panel circuit breaker	Red		
120 VAC Hot Wiring derived from UPS system	Red with Black Stripe		
Three Phase Power	Brown		

#### TABLE 180-1. WIRE COLOR CODING SCHEME

Wiring System	Wire Color		
120 VAC Neutral	White		
Ground	Green		
DC Power or Control Wiring	Blue		
DC Common	White/Blue		
DC Analog Signal Wiring	Black (+) / White (-)		
Foreign Voltage	Yellow		

- Surge protection shall be provided on all incoming power supply lines of the panel.
- Each field instrument deriving input power from the control panel(s) shall have a separate power distribution circuit with a circuit breaker and blown fuse indication (Phoenix Contact TCP type resettable Thermal Device circuit breaker Example: 2 amp version is Phoenix Contact part number 0712217, include base that provides LED for blown fuse indication). Each circuit must be sized accordingly.
- Provide redundant 24 volt direct current (VDC) power supplies and redundancy module to power field instruments and panel devices.
- Wiring trough for supporting internal wiring shall be plastic type with snap-on covers. The side
  walls shall be open top type to permit wire changing without disconnecting. Trough shall be
  supported to the subpanel by stainless steel screws. Trough shall not be bonded to the panel
  with glue or adhesives.
- Each panel shall be equipped with a LED enclosure light that turns on via door switch when the door is open.
- Each panel shall have a specification grade duplex convenience receptacle with ground fault interrupter, and minimum 2-port, 2.4A per port USB power outlet, mounted internally within a stamped steel device box with appropriate cover.
- Each panel shall be provided with an isolated copper grounding bus for all signal and shield ground connections.
- Each panel shall be provided with a circuit breaker to interrupt incoming power.

Example PLC panel layouts are included within Appendix C – Example General and Design Drawings.

# 190 System Testing

# 190.01 Introduction

It is the responsibility of the PCSS to provide a functional process control system. Confirmation of an operational SCADA / control system is dependent upon results derived from formal test procedures.

The PCSS shall test the system so that PWW can verify all the points in the SCADA system. The PCSS shall coordinate all testing with PWW. Copies of signed off test procedures, forms and checklists constitutes the required test documentation.

Each test shall be in the cause and effect format. The person conducting the test shall initiate an input (cause), and if the system or subsystem produces the correct result (effect), the specific test requirement will have been satisfied. In general, the following tests shall be performed and documented by the PCSS on a project:

- Factory Testing
  - o UFT
  - o WFT
  - o SIT
- Field Testing
  - o ORT
  - Site Acceptance Test (SAT)

All tests shall be conducted and documented in accordance with approved test procedures, forms and checklists. Tests may not commence without an approved test procedure and approved programming.

Specific requirements for control and SCADA system testing are provided in Appendix G – Acceptance Testing.

# 200 Backup Power and Miscellaneous Monitoring

## 200.01 Introduction

This section includes the requirements for backup power and miscellaneous monitoring including power and vibration. It is the responsibility of the PDE to incorporate the following requirements into their contract documents.

# 200.02 Uninterruptible Power Supply

An inline UPS shall be provided to condition the incoming power and to provide continuous power to all critical SCADA equipment at the site when power is lost. The following are the general requirements for all UPS systems:

- Critical SCADA Equipment includes:
  - Control Panel
  - Communications
  - Network
  - Access Control
  - o Camera
- The UPS shall be mounted in the Communications Panel and power all critical loads shown within the Communication and PLC panels.
- The UPS shall include a maintenance bypass switch for bypass capability to service the UPS system. The bypass switch shall be rack mounted within the Communications Panel.
- The PDE shall size the UPS system to provide a minimum of 20 minutes of battery runtime at 150% of the calculated load at each site for the SCADA system. Provide extended battery modules as needed to provide the required backup runtime duration. The extended battery module shall also be rack mounted.
- The UPS components shall be located at the bottom of the Communications Panel.
- The UPS shall be furnished with a Modbus monitoring card for monitoring by the PLC. The card shall also support Simple Network Management Protocol (SNMP) for remote monitoring over the Ethernet WAN.
- The UPS shall be furnished with a relay output I/O common alarm and hard-wired to the PLC to provide notification in the event of a UPS failure.

# 200.03 Emergency Site Power

PWW may require the D&C remote site to be equipped with backup emergency power generators to keep the remote site operation during periods of semi-extended power outages. Sites with generators will include an ATS to transfer essential loads from one power source to another. At minimum, the ATS status for Commercial Power Available, Commercial Power Connected, Generator Available, and Generator Connected shall be transmitted to the PLC.

The SCADA system shall be able to monitor the following hard-wired I/O signals from the emergency power system:

- Generator Run Status (DI)
- Generator Failed Status (DI)
- Generator Fuel Tank Level (4-20 mA AI)
- Normal Source Power Available Status (DI)
- Normal Source Power Connected Status (DI)
- Generator Source Power Available Status (DI)
- Generator Source Power Connected Status (DI)
- ATS Fault Status (DI) (If available)

The ATS shall start the generator on loss of normal power and transfer the load from normal source power to generator source power. The emergency power system shall be provided with a hardwired "Remote Test" function from the PLC that allows the SCADA system to exercise the generator remotely.

When the "Remote Test" signal is sent from the PLC, the ATS shall start the generator, and shall transfer the pump station load to the generator. On removal of the signal, the ATS shall transfer the equipment load from generator source power to normal source power, if applicable.

The ATS shall be networked over Modbus TCP/IP to the PLC. The network data shall not replace the required hard-wired signals to the PLC.

# 200.04 Power Monitoring

Power monitoring shall be provided to measure the power availability, quality and consumption at each pump station site. Power monitoring shall be provided from PQMs and Power Monitoring Relays (PMR). PQMs shall support an external power source, and shall be powered by the UPS. The use of the PQMs and PMRs are largely dependent on the site type and equipment. The PDE shall confirm PWW's requirements on a site-by-site basis. A PMR may be omitted where an Automatic Transfer Switch is being installed since the Normal and Emergency Source Available statuses will be monitored by the PLC and provide the required power availability monitoring.

# 200.04.01. Pump Stations (Wastewater and Fresh Water)

- Site Power availability shall be monitored by a PMR.
- The PMR I/O shall be hard-wired to the PLC.
- Site power quality and consumption shall be monitored by a PQM.
- The PQM shall be networked to the PLC via Modbus Ethernet.
- The PQM shall be powered from the UPS to allow communication with the PLC during a loss of phase or power outage.
- All PQMs shall be mounted no more than 5.5 feet or less than 4.5 feet from the horizontal centerline of the display to the floor.
- Motor current for pumps shall be monitored using CT's on each power leg. The CTs shall provide a proportional 4-20mA analog signal to the PLC.
- If the pump has a VFD or soft starter equipped with power monitoring via network interface, this interface may be used to provide data with Prince William Water approval

# 200.04.02. Elevated Storage Tanks, Metering Stations, and Other Non-Pump Stations

- Site Power availability shall be monitored by a PMR.
- The PMR I/O shall be hard-wired to the PLC.

# 200.05 Vibration and Temperature Monitoring

Vibration and temperature monitoring shall be provided for large motors (100 HP and above). The PDE should follow the motor manufacturer's recommendations for monitoring and protection; however, the minimum following signals are required for SCADA system monitoring. The motor supplier shall factory install the sensors.

- Vibration (x, y, z)
- Motor winding temperature for each phase (3 RTDs in total)
- Each bearing RTDs

A signal conditioning device shall be provided for all vibration and RTD signals. An analog 4-20 mA signal for each of the vibration signal and RTD signal shall be wired to PLC system, alternatively, with Prince William Water approval, an Ethernet Modbus TCP communication link shall be established between the signal conditioner and PLC to allow continuous monitoring by PLC. The signal conditioner shall also provide two relay output dry contacts alarms, one for vibration and other for temperature

(common) to trip the motor on high vibration or high temperature. Vibration and temperature alarms shall also be wired to the PLC system.

# 210 Field Instrumentation

## 210.01 Introduction

This section includes PWW's requirements regarding field instrumentation at D&C remote sites. It is the responsibility of the PDE to incorporate the following requirements into their contract documents. The PDE shall be responsible to include additional instruments as necessary for the proper operation of the remote site.

Refer to Appendix A – Standard Components for approved manufacturers and models. Some components do not allow "or equal" or substitutions due to system compatibility requirements.

## 210.02 Level

#### 210.02.01. Wet Well Level Measurement

Water level in each wastewater wet well shall be measured using two submersible type level transducers. The level signal from the transducer shall be wired to PLC system for continuous monitoring.

The following are the minimum guidelines and requirements for the level transducer selection and installation. The PDE shall coordinate with the civil and structural engineers to select the appropriate installation location and the electrical engineer for the signal wiring.

- The transducer shall be hung in the wet well within a stilling well supported by a steel rope with a weight attached to the bottom to stay away from the direct inflow and outflow in the wet well.
- Stilling wells and their mounting details shall be properly engineered for support in the wet well(s). Stilling Well detailed drawings must be included in the design package drawings. This detailed drawing must include pipe support locations and detailed mounting and drilling information.
- A pull box shall be installed above the stilling wells and shall be shown on the detail drawings
- The transducer shall be provided in a waterproof housing made of stainless steel and the cable shall be polyurethane material of Kevlar strength.
- The transducer shall be provided with a vent filter to terminate the vent tube that prevents moisture and insects from entering in to the vent tube. The vent filter shall be installed away from the wet well, preferably inside a temperature controlled building.
- The transducer shall be loop powered from the PLC with a 2-wire 4-20 mA output. The range shall be selected as per the depth of the wet well.
- Provide an intrinsically safe barrier where the transducer cable enters the non-classified building area.
- The transducer shall be rated for the area classification

#### 210.02.02. Water Storage Tank Level Measurement

Level in all elevated water storage tanks shall be measured using two pressure type (level) transmitters. The level signal from the transmitters shall be wired to PLC system for continuous monitoring.

The following are the minimum guidelines and requirements for the level instrument selection and installation. The PDE shall coordinate with the civil and structural engineers and PWW to select the appropriate installation location and the electrical engineer for the signal wiring.

- The pressure transmitters shall be tapped to the tank outlet pipe upstream of any isolation valve in the outlet pipe to allow level monitoring. Each pressure transmitter tap shall include an isolation ball valve between the outlet pipe and transmitter. Another isolation valve shall be provided to vent each transmitter to atmosphere to check the zero, and shall also be provided with the attachment to check the pressure calibration in the field.
- New tank installations shall include a spare "hot tap" for future level/pressure monitoring.
- In unconditioned spaces, the connection from the pressure transmitter to the tank outlet pipe shall be heat traced on an independent circuit (if required and shall be determined on a caseby-case basis in consultation with PWW).
- Pressure transmitters shall be loop powered from the PLC with a 2-wire 4-20 mA output. The range shall be selected as per the height of the tank top from the elevation of intended location of pressure transmitter tapping.
- Pressure transmitter diaphragm shall be rated for potable water application.
- Pressure transmitters with displays shall not be mounted more 6 feet from the floor and shall be mounted in a way that the display can be viewed easily and directly.

#### 210.02.03. Level Switch

High-High level in the wet well or dry well shall be detected by using a float switch.

The following are the minimum guidelines and requirements for the float switch selection and installation. The PDE shall coordinate with the civil and structural engineers to select the appropriate installation location and the electrical engineer for the signal wiring.

- The float shall be put in to the wet well supported on a steel pipe attached to the wet well wall and will be installed to keep it away from the direct inflow and outflow in the wet well.
- The float shall be rugged 5 ½" ball type, 316 SS construction with non-stick coating.
- The float switch shall be mercury free, SPDT NO & NC contact.
- Provide an intrinsic safe relay where the float cable enter the non-classified building area.
- The float shall be rated for the area classification.

# 210.03 Differential Pressure

Water booster sites centrifugal pumps shall be equipped with a differential pressure transmitter to allow continuous monitoring of differential pressure across the pump.

The following are the minimum guidelines and requirements for the differential pressure transmitter selection and installation. The PDE shall coordinate with the civil and structural engineers to select the appropriate installation location and the electrical engineer for the signal wiring.

 Differential pressure transmitter high side shall be tapped to the discharge side of the pump and low side be tapped to the suction side of the pump. The pressure transmitter taps shall include a 3-way isolation valve. The location and configuration of the taps shall be approved by PWW.

- In unconditioned spaces, the connection from the differential pressure transmitter taps to the pipe shall be heat traced on an independent circuit (if required and shall be determined on a case-by-case basis in consultation with PWW).
- Differential pressure transmitter shall be loop powered from the PLC with a 2-wire 4-20 mA output. The range shall be selected as per the discharge and suction pressure difference of the pump.
- Pressure transmitter diaphragm shall be rated for potable water application.
- Differential Pressure transmitters with displays shall not be mounted more 6 feet from the floor and shall be mounted in a way that the display can be viewed easily and directly.

# 210.04 Flow

In-line magnetic-type flowmeters shall be used for all water and wastewater flow metering except where the designer, with PWW's concurrence, does not find the magnetic flowmeter suitable for the application or water custody transfer flow metering application.

The following are the minimum guidelines and requirements for the meter selection and installation. The PDE shall coordinate with the civil and structural engineers to select the appropriate installation location and the electrical engineer for the signal wiring.

- Wherever possible, meter shall be installed on a vertical pipe with isolation valve before and after the meter. Piping and flowmeter placement shall be designed to maintain a full pipe under all operating conditions.
- Flowmeter shall be placed on a pipe with a minimum of 5 upstream and 3 downstream pipe diameters straight pipe length, or as recommended by the meter manufacturer, whichever is greater.
- A bypass piping with isolation valve shall be provided around the flowmeter to allow the maintenance of the meter without shutting down of process.
- Flowmeter piping shall be provided with a 1" flushing connection upstream and downstream of the meter.
- Size the flowmeter to maintain a minimum velocity of 2 ft. /sec on wastewater and sludge lines. Provide reducers as needed.
- Select the liner and electrodes materials and type per manufacturer recommendation compatible with the fluid being measured.
- Provide grounding rings with strap and ground wires.
- Flowmeter shall be powered with 120VAC power, 4-20 mA output to PLC, include a remote mounted transmitter with display.
- All flowmeter components shall be rated for the area classification per Electrical designer.
- Flow Meters with displays or analog readouts/counters shall not be mounted more 6 feet from the floor and shall be mounted in a way that the display can be viewed easily and directly.

For water custody transfer applications, flowmeter selection and installation details shall be recommended by the Designer for approval by PWW.

# 210.05 Miscellaneous

### 210.05.01. Ambient Temperature

Continuous ambient temperature inside pump station and water tank buildings shall be monitored by the PLC. The following are the minimum guidelines and requirements for the sensor selection and installation. The PDE shall coordinate the location of the power and signal wiring with PWW.

- Temperature transmitter for ambient temperature shall be wall mounted in a location approved by PWW.
- Temperature transmitter shall include a LCD display.
- The transmitter shall provide 4-20 mA output and shall be loop powered from the PLC.
- All Ambient Temperature Sensors shall be mounted no more than 5.5 feet or less than 4.5 feet from the horizontal centerline of the display to the floor.

#### 210.05.02. Smoke Detection

Smoke detectors shall be installed inside the pump station and water tank buildings and the status shall be monitored by the PLC. The following are the minimum guidelines and requirements for the sensor selection and installation. The Designer shall coordinate the location of the power and signal wiring with PWW.

- Smoke detector shall be industrial grade ceiling mounted at a well-ventilated location, not in the vicinity of air ducts.
- The smoke detector shall be photoelectric type, 120VAC powered and provide NO & NC relay dry contacts which shall be wired to PLC system.

# 220 Access Control, Operational Video, and Lighting Controls

## 220.01 Introduction

This section addresses the access control and operational video remote system design requirements. Access control and operational video shall be designed and incorporated at all remote D&C sites.

## 220.02 Access Control

The access control system shall be used to record authorized entries and exits at each remote site. The system will notify PWW when authorized access has been recorded and when an unauthorized card or no card has been presented to the reader prior to the door opening.

The access control system at each site shall consist of a card reader controller at the designated primary entrance, intrusion switches at each door or hatch used for maintenance access or personnel entry, door exit controls, and a local audible horn, all of which are linked to the PLC. Site security will be enabled (armed) when all of the building doors and vault hatches are secured. When the card reader validates a user, a signal is sent to the PLC from the card reader instructing the PLC to disarm security. Security shall automatically re-enable when all building doors and vault hatches are completely closed again. An operator-adjustable PLC timer notifies operations when a site has been disarmed for an extended period of time.

A Request to Exit (REX) push button must be used to exit the facility.

The Access Control System design requirements are as follows:

- A minimum of one card reader is required per site. For buildings, the card reader shall be located at the primary entrance. For remote sites with no buildings, the card reader shall be located on or near the PLC panel.
- Each card reader shall be powered via PoE technology and networked within the Communication Panel.
- Each card reader has a cable extending from its back plate that is referred to as "the pigtail". The pigtail is used to connect to the various components at the door location. For each card reader, provide a junction box with terminal blocks to facilitate system wiring.
- For all new buildings, door strikes shall be provided to lock and unlock doors based on authorized access. The door strikes shall be wired to and controlled by the card reader. The PLC shall not be used to control the doors.
- For existing buildings, coordinate with PWW if new door strikes are required in the existing door frames.
- All doors, whether provided with or without door strikes, shall be provided with mechanical key overrides. The mechanical keys will be keyed to PWW's standards.
- A dry relay output from the card reader shall be wired to the PLC as a separate input for authorized entry.
- Intrusion detection switches shall be installed on all building doors, vault hatches, and PLC and communication panels. Each building entrance door shall be wired separately to discrete PLC

inputs. All hatch intrusion switches shall be wired in series to the PLC system (normally closed) for alarming. Panel switches shall be separate inputs to the PLC system.

- Door contacts shall be magnetic wide gap (up to 3-inch) type, high strength aluminum housing with prewired, armored cable rated for heavy-duty industrial service. Contacts shall be furnished with adjustable mounting brackets.
- Hatch style doors shall be provided with industrial rated limit switches with roller arm attachment. Switches shall be oil and water tight with a NEMA 4X rating. Switches shall include 1 NO and 1 NC contact.
- Rolling doors shall be provided with magnetic door contacts enclosed in an epoxy sealed aluminum housing. Factory connected armored cable shall be provided for electrical terminations. Actuating magnet shall be mounted on the rolling door using an adjustable Lbracket.
- An audible horn shall be installed on the PLC panel to sound when an unauthorized intrusion has been detected. Silence functionality shall be available from the OIT. Site process alarms shall not be connected to the audible horn.
- A REX push button shall be provided for personnel exiting the building or site and shall be wired directly to the card reader.

# 220.03 Operational Video

The use of cameras are primarily intended to reduce the need for an operator to initially visit the site when a process alarm is received. The video is used to allow the operator to quickly diagnose issues, and then plan the proper response thus reducing travel to and from the sites. Cameras are NOT intended for security surveillance; however, camera feeds shall be recorded and may be used to support future security initiatives.

The Operational Video design requirements are as follows:

- Indoor and outdoor cameras and accessories shall be as listed in Appendix A Standard Components. There is no "or equal" for the required brand and model of camera.
- Cameras are powered by PoE communications.
- Outdoor cameras shall have a built-in heater, blower, and sun shield for increased protection in extreme temperature conditions. A separate power circuit may be required for the camera/enclosure heater.
- A minimum of two cameras shall be installed at each site. Where there are multiple rooms with process or control equipment, or an exterior door, a minimum of one camera will be required for each room.
- The installation locations for cameras should provide unimpeded viewing of all electrical gear, access door(s), and major equipment control panels. If required by PWW, provide additional cameras for full coverage of the process areas. Camera locations and the need for additional cameras shall be determined on a case-by-case basis in consultation with PWW during design.
- For all water storage tanks with enclosed storage areas and unobstructed views, a single camera may be used to capture all entry doors and the PLC control panel. An exterior camera shall be positioned to provide a view of the ladder cage.
- For outdoor only sites, sufficient cameras shall be provided to capture all vault hatches, and outdoor control panels. For water storage tanks, the camera view shall include a view of the ladder cage.

• Hardwired Motion Detected DOs shall be installed from the PLC to each camera(s) based on the number of doors that the camera is monitoring. PWW will identify the number of connections and cameras required based on the preliminary design.

# 220.04 Lighting Requirements

To support operational video cameras, in addition to general illumination for each facility, always-on LED lighting is required to illuminate the remote sites to allow clear visibility for the video cameras while the facilities are unattended. One or more LED light(s) may be required to be installed, depending on the facility floor plan.

The circuit powering the LED light(s) shall be solely controlled by the circuit breaker, and shall not have a separate control switch.

The LED light(s) shall be positioned to illuminate all areas visible to the operational video camera(s).

For areas observed by the operational video cameras, the quantity and location of LED light(s) shall be selected to provide a minimum of 10 Lux of illumination per 100 square feet of the facility.

# 230 Telemetry, Networking, and Cyber Security

## 230.01 Introduction

This section includes the requirements for networking, telemetry, and cyber security. It is the responsibility of the PDE to incorporate the following requirements into their contract documents.

# 230.02 Telemetry

Each D&C remote SCADA site will communicate with PWW's Operations Control Center using a redundant communications backbone provided and configured by PWW. Communications requirements and media may vary by site. The communications media will be determined by PWW based on the available services, with the design for the installation being developed by the facility designer.

One of the communications media will be cellular, and the facility designer shall include the following:

- The cellular system provided shall consist of a cellular router, two antennas, interconnecting cabling, and connectors. The cellular router will provide the WAN failover, routing, and security required by PWW.
- The cellular router shall be installed in the Communications Panel and provided with a kit for mounting on DIN Rail.
- All cables and connectors shall be compatible with the cellular router and recommended for the installed location.
- Each cellular router shall be provided with two outdoor Omni-directional antennas for maximum bandwidth. The antennas shall be mounted on the outside face of the building (or pole-mounted at sites without buildings). The antennas shall be outdoor rated and compatible with the router and service. The base of building-mounted antennas shall be mounted a minimum of 12 inches above the highest point on the building. The base of pole-mounted antennas shall be a minimum of 12 inches above any obstacle within 25 feet of the pole in any direction.
- Each antenna shall be supplied with an individual surge protector to protect against to direct lightning strikes and induced surges.
- The Cellular Router must be properly grounded per Cisco recommendations.
- Equipment programming configuration and cellular service will be ordered and coordinated by PWW.
- The cellular router, power supply, antenna, surge protector, and accessories shall be as listed
  in Appendix A Standard Components. No "or equal" or substitutions are permitted. Prior to
  ordering, the PCSS shall contact PWW's SCADA Program Manager to discuss ordering
  and option part number specifics to ensure new service and technology requirements
  are met and coordinated.

Site developers shall provide easements and clearly identified crossings from the facility to the closest point of connection to the Comcast cable network. Handholes shall be installed on either end of crossings and at an approved location outside the facility, and shall be marked as property of PWW. A 2-inch conduit, suitable for the installation of Comcast cables, shall be provided from the facility entrance handhole to the communications cabinet. Coordinate with Comcast on the location of the network connection point and characteristics of the handholes and conduit installation, and indicate

the location on all relevant drawings. PWW shall make all arrangements for service utilizing the developer-provided path.

# 230.03 Networking

Each D&C SCADA site has the following two physical networks for local and remote communications:

- WAN
- VLAN

The WAN provides the system-wide communications across the D&C system. The WAN is designed to support communications to the following four sub-networks:

- 1. PLC
- 2. Access Control
- 3. Operational Video
- 4. System Management

Each of these networks are connected through a managed Ethernet Switch located within the Communications Panel. The following are the minimum requirements for the managed Ethernet Switch:

- The managed Ethernet Switch shall be a 19" rack mount style switch, 1U size with metal enclosure. The managed Ethernet Switch shall be an industrial grade switch.
- The switch shall be provided with twenty-four (24) 10/100/1000 PoE Ports, and four (4) Gigabit Ethernet Uplink Ports.
- The switch shall be provided with two (2) Rugged Type 10/100/1000 Copper SFP Modules
- The Ethernet Switch must be properly grounded per Cisco recommendations.
- Redundant power supplies
- The operating voltage shall be 100 240 VAC, derived from the UPS.
- Equipment programming configuration shall be performed by PWW.
- The Ethernet Switch and any accessories shall be as listed in Appendix A Standard Components. No "or equal" or substitutions are permitted. Prior to ordering, the PCSS shall contact PWW's SCADA Program Manager to discuss ordering and option part number specifics to ensure new service and technology requirements are met and coordinated.

A separate **virtual** PLC VLAN shall be configured by PWW to connect the PLC to other SCADA devices located at each site. These devices may include pump soft starts and VFDs, power monitors, and other components. Because they are only on the PLC VLAN, their traffic cannot directly pass through the WAN. Their data must be packaged and transmitted through the PLC.

Communications shall be via Modbus TCP protocol only. The PLC Ethernet VLAN shall be networked using the managed Ethernet switch and/or the Router's Ethernet Switch NIM. PWW shall perform all switch and router programming configurations and provide IP address information to the PCSS for any devices accessing the VLAN or WAN.

PWW shall provide all IP addresses for all networked equipment and communications devices. The Contractor shall submit a Request for Information at an appropriate time during the network configuration.

# 230.04 Cyber Security

The D&C SCADA has been designed around numerous cyber security references, standards, and guidelines including ANSI, ISA, AWWA, DHS, IEC, NIST, and NERC. The design includes firewalls, DMZs, intrusion detection systems, and other security provisions as recommended by these various organizations. PWW cyber security design has been validated by an independent 3rd party expert cyber security firm.

PWW will perform all configurations of communication network routers, switches, and modems. The installation contractor is responsible for configuring all VFD, Soft Starts, PQMs, ATS, or similar VLAN devices in compliance with Prince William Water requirements.

For purposes of design, the PDE is not required to include any additional security appliances and components other than what has already noted within this document. The Designer shall follow the physical network configuration requirements described in Appendix H – Remote Site Network Configuration Requirements

Apart from the cellular interface card in the site router, Wireless Technologies shall not be used in the design of the SCADA control systems for any purposes without prior written requests and approval of the Senior SCADA Program Manager.

Wired/Wireless Technologies that provide any remote access to SCADA devices or networks by anyone other than Prince William Water staff are strictly forbidden without prior written requests and approval of the Senior SCADA Program Manager.

# Appendix A

Standard Components


	2027 (17524				
ATE	GORY / ITEM	Manufacturer	Model / Part Number	Comments	Substitution Allowed?
/IISCI	 ELLANEOUS				
iisci	Enclosure	Hoffman			With Approved Submittal
	Thermostats	Hoffman			With Approved Submittal
	Heaters	Hoffman	-		With Approved Submittal
	Fans	Hoffman			With Approved Submittal
	Alarm Horn				• • • • • • • • • • • • • • • • • • • •
		Edwards Signaling			With Approved Submittal
	Power Supplies	Phoenix Contact			With Approved Submittal
	Signal Isolators	Phoenix Contact	-		With Approved Submittal
	Isolated / Safety Switches	Phoenix Contact			With Approved Submittal
	Intrinsic Safety Barriers	Phoenix Contact			With Approved Submittal
	Relays	Phoenix Contact			With Approved Submittal
	Receptacle	Phoenix Contact			With Approved Submittal
	Terminal Blocks - 120VAC	Phoenix Contact.		120VAC blocks shall be beige	With Approved Submittal
	Terminal Blocks - 24VDC	Phoenix Contact.		24VDC blocks shall be blue	With Approved Submittal
	Fuse Terminals	Phoenix Contact		With blown fuse indicator	With Approved Submittal
	Circuit Breakers	Square D			With Approved Submittal
	Surge Arrestors	Square D			With Approved Submittal
	Surge Protectors	Square D			With Approved Submittal
	Fuses	Bussman			With Approved Submittal
	Uninterminately Device C. J. (1953)	Felson LIPC		Rackmount, rated for load	No, however, selected model
	Uninterruptable Power Supply (UPS)	Falcon UPS		requirements and environment	submittal and approval require
	UPS Network & Modbus Card	Falcon	MEGA-BA506-4-2022	This is the new internal version.	No
	Folding Shelf/Desktop			Installed in PLC Panel	With Approved Submittal
	1U Vented Shelf			Installed in Comm Panel	With Approved Submittal
ISTR	UMENTS				
	PQM	PC&S	DKM-411	with Modbus TCP	With Approved Submittal
	PMR	ATC Diversified Electronics	SLU-100-ASA or -ASD series	With Mode as Yel	With Approved Submittal
	Level Transducer	Mercoid Bird	PBLT2-20-60		With Approved Submittal
	Tank level w/display	Rosemount	SMART 1151	Primary level sensor	With Approved Submittal
	Tank level w/o display	Dwyer	Model 626	Backup level sensor	With Approved Submittal
			FS 202	backup level sellsol	
	Float Switch Dry Well	Contegra	FS 90		With Approved Submittal
	Float Switch Wet Well	Contegra			With Approved Submittal
	Differential Pressure	Siemens	Sitrans P250		With Approved Submittal
	Flowmeter	ABB	ProcessMaster		With Approved Submittal
	Ambient Temperature	Dwyer	RHP Series RHP-2N44-LCD		With Approved Submittal
	Smoke Detection	Gentex Corporation	8000 Series		With Approved Submittal
	Chlorine Monitor	Hach	CL17		With Approved Submittal
	Fuel Level Transmitter	Flowline	LU80-84 Series	Generator Belly Tanks	With Approved Submittal
		Flowline	LG10 Series	All Other Day Tanks	With Approved Submittal
ROG	RAMMABLE LOGIC CONTROLLER				
	Modicon M340	Modicon	M340		No
	CPU / Processor	Modicon	BMXP341000		No
			SCADA Contractor to evaluate t	he capabilities of the standard	
	Upgraded CPU / Processor	Modicon	processor against the design, a	nd recommend an upgraded	No
			processor if necessary.		
	Memory Cards	Modicon	BMXRMS008MP		No
	Power Supply	Modicon	BMXCPSxx00		No
	Chassis	Modicon	BMXXBPxx00		No
	Digital Input Module	Modicon	BMXDAI1604		No
	Digital Output Module	Modicon	BMXDRA0815		No
	Analog Input Module	Modicon	BMXAMI0x10		No
	Analog Output Module	Modicon	BMXAMO0410		No
	LAN Communication Module	Modicon	BMXNOE0100		No
	WAN Communication Module	Modicon	BMXNOR0200H		No
	High Speed Counter Module	Modicon	BMXEHC0800		No
CCES	SS CONTROL				
	Access Card Reader	Isonas	RC-04-PRX-M	w/o key pad and enabled for HID formatted cards	No
	DEV	Cubmit hardwara rasan	dation	iormatteu carus	Submit for Annescal
	REX	Submit hardware recommen			Submit for Approval
	Electric Door Strike	Submit hardware recommen	dation		Submit for Approval


EGORY / ITEM	Manufacturer	Model / Part Number	Comments	Substitution Allowed?
WORK				
Cellular Router	Cisco	Cisco IR1101-K9 Industrial Integrated Services Router Rugged		No
Industrial Integrated Services Router Rugged	Cisco	IR1101-K9		No
SNTC-8X5XNBD Industrial ISR 1101	Cisco	CON-SNT-IR101K9K		No
Network Essentials License for Cisco IR1101 Industrial ISR	Cisco	SL-IR1101-NE		No
Utilities Industry Solutions; For tracking only	Cisco	IOT-UTILITIES		No
Not related to an IoT Utilities Solution; For tracking only.	Cisco	IOT-UTIL-OTHER		No
UNIVERSAL (NETWORK ESSENTIALS)	Cisco	SIR1101UK9-1612		No
CAT4 LTE Pluggable Verizon	Cisco	P-LTE-VZ		No
Cisco OEM PRI for WP7601	Cisco	OEM-PRI-WP7601		No
FW for WP7601 Verizon	Cisco	FW-WP7601-VZ		No
LTE SMA dipole antenna 698- 960,1448-1511,1710-2690	Cisco	LTE-ANTM-SMA-D		No
Din Rail kit for the IR1101	Cisco	IR1101-DINRAIL		No
Multiband Omni-Directional Stick Outdoor 4G Antenna	Cisco	ANT-4G-OMNI-OUT-N=	2 Required, Main/Diversity	No
4G Outdoor Antenna Lightning Arrestor	Cisco	4G-ACC-OUT-LA	2 Required	No
50W AC to DC power supply	Cisco	PWR-IE50W-AC-L		No
*This model of router is DIN-RAIL mo	ountable and not directly 19	" rack mounted and therefore mus	t be mounted to a plate/panel wit	hin the Communications Panel.
Additionally, the power input is 12-4	8VDC so the specified powe	r supply above must be provided a	nd DIN-RAIL mounted on the same	e panel.
NAGED ETHERNET SWITCH				
Cisco IE 9320 Series*	Cisco			No
with 4 GE Uplinks (385W)	Cisco	IE-9320-24P4S-E		No
SNTC-8X5XNBD 24 Port PoE Downlinks with 4 GE Uplinks PoE, PSU for IE9320, 100-240VAC/100	Cisco	CON-SNT-IE93224E		No
	Cisco	PWR-RGD-AC-DC-H	< 11 PoE devies: 2 Required	No
1100-240VAC/100-250VDC	Cisco	PWR-RGD-AC-DC-250	> 10 PoE devies: 2 Required	No
Cisco Copper SFP Module, 10/100/1000Base-TX RJ45, -40 to +85 ( deg C.	Cisco	GLC-T-RGD=	2 Required, generics are not acceptable.	No
series	Cisco	IE9300_SW		No
tracking only	Cisco	IOT-OTHER		No
Not related to an IoT Solution; For tracking only.	Cisco	NO-IOT-SOLUTION		No

CATEGORY / ITEM	Manufacturer	Model / Part Number	Comments	Substitution Allowed?
NON-CONTROLLED SITE OIT				
Advanced Touchscreen Panel	Schneider Electric	Harmony HMIGTO1310	320 x 240 pixels QVGA - 3.5" TFT	No
CONTROLLED SITE OIT				
Advanced Touchscreen Panel	Schneider Electric	Harmony HMIGTO6310	800 x 600 pixels SVGA - 12.1" - TF	No
Accessories - SD Memory Card	Schneider Electric		SD Card 32GB per manf specs	No
BACKUP OIT CONTROLLER				
Small touch HMI Controller	Schneider Electric	Harmony HMISCU8B5	320x240 pixels QVGA - 5.7"	No
OIT includes: Touchscreen capabilitie	es. Color LCD screen.			
Supports these Protocols, at minimu	im:			
a) Modbus				
b) Modbus TCP/IP				
c) CANopen				
Required Accessories:				
Provide one of the following remote assembly shall be provided with all e				
rail mountable in the PLC cabinet's b	ack plate rather than runnir	ng the I/O wiring to the door for a c	leaner and safer installation.	
	oack plate rather than runnii	ng the I/O wiring to the door for a c	leaner and safer installation.	
rail mountable in the PLC cabinet's b	pack plate rather than runnii	ng the I/O wiring to the door for a c	leaner and safer installation.	
rail mountable in the PLC cabinet's b  a) HMIZSURDP (3m) b) HMIZSURDP5 (5m)	oack plate rather than runnii	ng the I/O wiring to the door for a c	leaner and safer installation.	
rail mountable in the PLC cabinet's b a) HMIZSURDP (3m) b) HMIZSURDP5 (5m) VIDEO			leaner and safer installation.	
rail mountable in the PLC cabinet's b  a) HMIZSURDP (3m) b) HMIZSURDP5 (5m) VIDEO Outdoor Camera	iPro	WV-S65340-Z4N1	leaner and safer installation.	No
rail mountable in the PLC cabinet's b a) HMIZSURDP (3m) b) HMIZSURDP5 (5m) VIDEO Outdoor Camera			leaner and safer installation.	No No

# Appendix B


Example P&IDs








# Appendix C


**Example General and Design Drawings** 


































































120VAC UPS Draw Calculation

L64-Comm	VA	Qty	Scaling	Watts
24VDC PS	165	1	0.33	54.45
PLC	119.6	1	0.25	29.9
IR 1101	20	1	1	20
Switch 4010	100	1	1	100
Power Monitor	5	1	1	5
Smoke Detector	8.4	1	1	8.4

217.75

### **SSG1.5K-XT UPS Battery Runtimes**



Heat Calculation

L64-PLC	Watts	Qty	Scaling	Watts
PLC	23	1	1	23
PS1 and PS2	19.9	1	1	19.9
OIT	10	1	1	10
Backup Control	15	1	1	15
				0
				0
				67.9

BTU/Hr 231.82



### **Product selection result**

### **Project**

- Title: PWCSA - L64
- Create date: Oct 14, 2020
- Amend date: Dec 14, 2020

### User

Company:Name:

- Address:

- City:

Enclosure Wall Location

Type Material Mild Steel for Indoor environments / NEMA Type 12

Height 72 inch k 5.5 W/m²K Single housing for wall mount

Width 36 inch Insulation R0 = 0 inch Surface according to VDE 0660 part 600 48ft²

Depth 18 inch

Temperature Rated connection value

Min. ambient temperature 32 °F Rated voltage: 115 V Max. ambient temperature 125 °F Frequency 60 Hz

Min. admissible temperature 32 °F Max. admissible temperature 131 °F

Dissipation based on manual input 232 BTU/h

### Switch cabinet acclimatisation

Total dissipation in enclosure 68 W
Heat Dissipation from environment 0 BTU/h
Heat Dissipation to environment 272 BTU/h
Required cooling capacity 0 BTU/h
Required heating capacity 0 BTU/h

### Product selection result

### Warning

Ensure there is sufficient clearance for air flow around the cooling unit to prevent a so-called air short-circuit. There should be a minimum distance of approximately 200 mm (7.9 inches) to the next component in the housing and 400 mm (15.7 inches) outside the housing

Heat Ca	lcula	tion
---------	-------	------

L64-Comm	Watts	Qty	Scaling	Watts
UPS - Falcon	157	1	1	157
IR1101	30	1	1	30
Switch 4010	112	1	1	112
		1	1	0
				0
		1	1	0
				200

299.0

BTU/Hr 1020.8



### **Product selection result**

### **Project**

- Title: PWCSA - L64 - Comm

- Create date: Oct 15, 2020 - Amend date: Jan 5, 2021

### User

Company:Name:Address:

- City:

Enclosure Wall Location

Type Material Mild Steel for Indoor environments / NEMA Type 12

Height 40 inch k 5.5 W/m²K Single housing for wall mount

Width 24 inch Insulation R0 = 0 inch Surface according to VDE 0660 part 600 31ft<sup>2</sup>

Depth 30 inch

Temperature Rated connection value

Min. ambient temperature 32 °F Rated voltage: 115 V Max. ambient temperature 127 °F Frequency 60 Hz

Min. admissible temperature 32 °F Max. admissible temperature 131 °F

Dissipation based on manual input 1,020 BTU/h

### Switch cabinet acclimatisation

Total dissipation in enclosure 299 W
Heat Dissipation from environment 0 BTU/h
Heat Dissipation to environment 119 BTU/h
Required cooling capacity 901 BTU/h
Required heating capacity 0 BTU/h
Required air flow 217 CFM

### **Product selection result**

### A fan type PF 65000 with filter PFA 60000 and an air flow rate of 230 CFM \*

Caution delta is less than 10 K.

### Warning


Ensure there is sufficient clearance for air flow around the cooling unit to prevent a so-called air short-circuit. There should be a minimum distance of approximately 200 mm (7.9 inches) to the next component in the housing and 400 mm (15.7 inches) outside the housing

<sup>\*</sup> Capacity at above specified conditions.



### PROTEK DOUBLE-HINGED FAN PACKAGES





### INDUSTRY STANDARDS

UL 508A Listed: File Number E61997 cUL Listed per CSA C22.2 No. 94; File Number E61997 Solid Door: Type 3R Window Door: Type 1

NEMA / EEMAC: Type 1 or 3R IEC 60529, IP30 or IP 32, IK 10

### **APPLICATION**

PROTEK Double-Hinged Fan Package cabinets are an excellent, offthe-shelf choice for mounting 19-in. rack, panel-mounted devices or other electronic equipment. An integral top solar/drip shield and thermostatically-controlled fans provide airflow to cool internal equipment. Cabinets are available in UL Type 3R for outdoor use. A UL Type 1 window version is available for indoor applications. The cabinets are designed to provide both front and rear access to 19-in. rack-mounted equipment, while ensuring protection against water, dirt and other contaminants. PROTEK is an excellent choice for applications where space is at a premium and the only option is wall mounting. PROTEK comes in a broad range of sizes, materials and configurations to meet many demanding applications.

- Front and rear access to 19-in, rack equipment provided by threepart design: door, center section and wall section
- Solid door provides complete physical and visual protection
- Integral top solar/drip shield
- Two thermostatically controlled, long-life, high-performance fans mounted into top
- Window door, made of .25-in. scratch-resistant safety glass and mechanically fastened, provides visual monitoring of internal equipment while maintaining equipment protection
- All seams are fully welded and ground smooth
- Perforated, vented base with internal, expanded metal, serviceable filter
- Door, center section and wall section are provided with ground studs to facilitate proper bonding and grounding of the cabinet
- Premium seamless, foam-in-place gasket prevents contaminants from entering the cabinet
- Keylocking wing knob provides access control to the cabinet; two keys are included with each cabinet
- One set of plated, self-grounding, tapped 10-32 rack angles per EIA universal spacing standards, adjustable front-to-back within the center section of the cabinet
- Additional rack angles in tapped- or square-hole versions can be added to the cabinet
- Wall section welded panel studs which accommodate standard panels (steel and wood available), can be ordered separately

### **SPECIFICATIONS**

- Doors made of 16 gauge; wall and center sections made of 14 gauge steel
- Integral top with two 6-in. fans powered by 120 VAC via cord with standard NEMA plug, provide 230 CFM of airflow
- Window made of .25-in. safety glass
- Rack angles with 10-32 tapped holes per EIA universal standards are made of 12 gauge plated steel
- Incoming air filter made of expanded aluminum
- M6 door and body ground studs are masked from paint Twenty 10–32 rack angle equipment mounting screws included with cabinet
- Foam-in-place gasket made of durable polyurethane
- Inline thermostat turns fans on when temperature exceeds 85 F/30 C

Pretreated steel coated with light-gray, low-gloss, lightly textured RAL 7035 polyester powder

### **LOAD RATING**

Height	Rating
0/:-	25015 /

250 lb./113.4 kg 300 lb./136.0 kg 24 in. 36 in. 48 in. 350 lb./158.7 kg

### **ACCESSORIES**

Locks and handles Panels (steel and wood) Grounding kits Power Distribution Units (PDUs) Rack angles

Performance data based on:

- Effective measured airflow provided by integral fans is 272 CFM
- Delta T or ΔT (Ambient Temperature Maximum in-cabinet Temperature)
  - Ambient air must be cooler than maximum in-cabinet temperature
  - For applications that have less than a  $\Delta T$  of 5 F, use PROTEK with AC unit
- Total Cooling = (Air cooling + Cabinet cooling)
   Air Cooling [Watts = .316 x CFM x ΔT] Cabinet cooling [Watts = (.22 x Area) / ΔT]

**Example:** Cabinet height 24 in. x 24 in. deep with ambient temperature 110 F, with a maximum internal cabinet temperature 120 F ( $\Delta T = 10$  F). The cabinet and fans will provide a total cooling capability of 762 Watts or 1300 BTU.

(See Performance Chart)

**BULLETIN: DWDH2** 

# PRINCE WILLIAM COUNTY SERVICE AUTHORITY



### SA-

# **PWCSA SCADA**


### % DESIGN SUBMITTAL DRAWING INDEX


GENERAL


DRAVING DESCRIPTION

DIVINITION INCIDENT	DATE THE MODIFIES DISTRICT DESCRIPTION		ארות איזען איזען
GEN-1-0	DRAWING INDEX	∢	03/21
GEN-I-1	INSTRUMENTATION LEGEND I	∢	03/21
GEN-I-2	INSTRUMENTATION LEGEND II	∢	03/21
GEN-I-3	INSTRUMENTATION LEGEND III	∢	03/21
GEN-E-1	ELECTRICAL LEGENDS AND ABBREVIATIONS	4	03/21
SITE			
DRAWING NUMBER	DRAWING DESCRIPTION	REV	REV REV DATE
	NW T I I I I I I I I I I I I I I I I I I		
	- SYSTEM ARCHITECTURE		
	- PRDCESS & INSTRUMENTATION DIAGRAM 1		
	- PROCESS & INSTRUMENTATION DIAGRAM 2		
	- PLC RISER DIAGRAM		
	- MOTOR PROTECTION CIRCUIT		

1	VIGNT CIVITY AND	DRAWING INDEX		DWG NO. SHT 1 OF 1		□ UEN-I-U	
DATE					DO NOT SCALE		
<b>6</b>					OT SCA	NE NE	
	DRAWN	CHECKED	νьь	REF.	DO NC	SCALE NI	
PROJECT INFORMATION	PRINCE VILLIAM CHINTY SERVICE	ALTERNATION OF VIOL	ACADA ACIDATII, PEN IFOT				
DATE	ш		ĺ				
МР							
СНЕСКЕВ							
DRAWN							
REVISION DESCRIPTION							
REV							







# SAMPLE LTE Outdoor Antenna Mounting Details


GREEAL NOTES.
ANTENNA SUPPORTING LIAST AND CLAMP, ALONG WITH THE RF CABLE,
WAST RE GROUNGED AND BENEARD TO THE BUILDING GROUNGING SYSTEM.


DETAIL.


ANTENNA
DETAIL
A
INTS


REV	REVISION DESCRIPTION	DRAWN CHECKED APP DATE	DRAIN CHECKED APP DATE PROJECT INFORMATION	М	DATE	1	
∢	DRIGINAL ISSUE		PRINCE WILLIAM CHINTY SERVICE	DRAWN		III GIALU INDITATIANI GESINI	
			ALTHORITY OF VICE	CHECKED		INSTRUMENTALIUN LEGEND III	1
			PDD IFCT	APP			
				REF.	.0	DWG NO. SHT 1 OF 1	
				DO NOT SCALE	MG. N		- ΔΞ8Ι
				SCALE NONE	ма	UEN-1-3	


E-4 DETAIL IS DRAWN	SYMBOL WHERE THERE IS A DETAIL	DETAIL A SHET NO.	1/4" = 1'-0" (E-3) WHERE THERE IS A DETAIL	SYMBOL WHERE DETAIL IS DRAWN		S Laws	SYMBOL WHERE THERE IS A SECTION		SECTION (1)		SYMBOL WHERE SECTION IS DRAWN	ا و	ON OTHER DRAWINGS OF SHOWN IN A SHOWN IN A CHANN IN A C	-	NEW WORK			FUTURE ITEMS ARE SHOWN IN A PHANTOM INF	_	<		A AC	ATS AUTOMATIC TRANSFER SWITCH AUTO AUTOMATIC	П	П	888		ទី៩៩		CWS	DMU DN	2		E 88	e e	1		1	ICAL LEGENDS AND ABBREVIATIONS		SH 1 0F 1	- - -
DESCRIPTION	LIGHTNING ARRESTER	GROUND OR GROUND ROD		FUSE, AMPERE RATING AS NOTED	STRIP HEATER OR HEATING ELEMENT		INDUCTOR	TACHOMETER GENERATOR	ON ABOVIEW NOBLAND	ממושמרו מבדו (מס)	CONTACT, NORMALLY CLOSED (NC)	OVERLOAD RELAY HEATER		MOTOR OPERATED VALVE OR GATE	INDICATES LIMITS OF ELECTRICAL EQUIPMENT OR WIRING ENCLOSURE		AUTOMATIC OR MANUAL TRANSFER SWITCI NO.1 (ATS-1), (MTS-1) "N" INDICATES	NORMAL OR PREFERRED SOURCE "S" INDICATES STANDBY OR ALTERNATE SOURCE 100A INDICATES CONTINUOUS CURRENT RATING		SPECIAL CAPACITOR  * SC - SURGE CAPACITOR  PF - POWER FACTOR CORRECTION CAPACITOR	TUNED POWER FACTOR CORRECTION CAPACITOR		MOTOR, NUMERAL INDICATES HORSEPOWER		LOW VOLTAGE AIR OR MOLDED CASE CIRCUIT BREAKER, 3 POLE	UNLESS OTHERMSE NOTED.  COMBINATION MOTOR CIRCUIT PROTECTOR AND	MAGNETIC MOTOR STARTER, FULL VOLTAGE NON-REVERSING UNLESS OTHERWISE NOTED: * F.M FULL VOLTAGE REVERSING * AND PREVIOUS NOT TAKE NOT THE PROPERTY OF THE PRO	RVAT – REDUCED VOLLAGE NON-REVERSING RVAT – REDUCED VOLTAGE AUTOTRANSFORMER RVSS – REDUCED VOLTAGE RVSS – REDUCED VOLTAGE SQUID STATE	2SIW - TWO SPEED, ONE WANDING RS2W - TWO SPEED, TWO WINDING (DIAGRAMATICALLY SHOWN, CONTRACTOR SHALL	FIELD LOCATE)  NON-FISIBLE DISCONNECT SWICH	600 VOLT, 3 POLE * AMPERE RATING NOTED IF OTHER THAN 30A (DIAGRAMATICALLY SHOWN, CONTRACTOR SHALL	FIELD LOCATE)	FOSEILE DISCUNNECT SMITCH, 600 VOLT, 3 POLE.  * AMPERE RATING AND FUSE SIZE AS NOTED  * AMPERE RATING NOTED IF OTHER THAN 30A	FUSE RATING (DIAGRAMATICALLY SHOWN, CONTRACTOR SHALL FIELD LOCATE)		1.00	GENERAL NOTE  SOME SYMBODE LICEND.  SOME SYMBOLS MAY NOT  APPEAR ON THE DRAWINGS.	BY DATE	ELECTRICAL	WED .		NOT SCALE
CONTROL DIAGRAM	 	•	+	 	41174 IIII			(P)		1	 	         					<u>t</u>	-	7	*+			(2) (6)		FRAME			à —			占 -:-			5			THIS IS A SOME S		DRAWN	OHEC	P.G.	]2
DESCRIPTION O	PILOT LIGHT, COLOR AS NOTED * R - RED 6 - GREN	B - BLUE W - WHITE A - ANHTR	A - AMBER A - AM	CONTROL RELAT COIL, NOMBER AS INDICATED	PILOT LIGHT, PUSH-TO-TEST TYPE, COLOR			NORMALLY OPEN NORMALLY OPEN — HELD CLOSED		NORMALLY CLOSED - HELD OPEN	PUSHBUTTON, MOMENTARY CONTACT, CAPRING PETRIPM MOMENTARY PLOSED	Annual Control of the	SPRING RETURN, NORMALLY OPEN	EMERGENCY STOP PUSHBUTTON WITH ES RED MUSHROOM HEAD OPERATOR	START-STOP PUSHBUTTON CONTROL STATION (MOMENTARY CONTACT) WITH LOCKOUT		PBM START CONTACT WITH LOCKOUT DEVICE ON STOP		LOCAL/REMOTE SELECTOR SWITCH 100A	3 POSITION SELECTOR SWITCH,	POSTION TOP MIDDLE BOTTOM		NAMEDIATE (A/B/C)	HOR – HAND/OFF/REMOTE HOR – HAND/OFF/REMOTE	LOR – LOCAL/OFF/REMOTE RSL – RASE/STOP/LOWER TOA – TEST/OFF/AUTO	TIME DELAY RELAY RANGE AS NOTED SETPONT AS NOTED	# NUMBÉR AS INDICATED * TDE - TIME DELAY AFTER ENERGIZATION ON DELAY	TDD - TIME DELAY AFTER DE-ENERGIZATION OFF DELAY NOTC- NORMALLY OPEN, TIMED CLOSING	WHEN ENERGIZED NOTO- NORMALTY CLOSED, TIMED OPENING MARY ENERGYZED, TIMED OPENING	MHIN ENERGIZED NOTO— NOMALLY OPEN, TIMED OPENING MHEN DE-ENERGIZED	NCTC- NORMALY CLOSED, TIMED CLOSING WHEN DE-ENERGIZED	(* - #) FIELD INSTRUMENT, TAG NO, AS INDICATED INDICATES INSTRUMENT TYPE DEPINED ON	LOOP SHET'S OR P & ID  ## INDICATES LOOP NO.  TS] DR (T) OR IN TEMPERATURE SWITCH OR THERMOSTAT		NORMALLY OPEN, CLOSES ON DROPPING TEMPERATURE	NORMALLY CLOSED, OPENS ON RISING TEMPERATURE NORMALLY CLOSED, OPENS ON DROPPING	TEMPERATURE		/ SERVICE		PRUJECI	_
CONTROL DIAGRAM		' — €	€	<u> </u>	*	<u> </u>		 	;	1	9 9		000	ه آه	STOP START	5	<u></u>	۲ ا	( <u>\$</u>	(%)		* 0 (xx)		(x00)_		RANGE	SE IPOIN	*	N NOTC	- × - NCTO	O CONCIDE O		- E		n <del> </del>	P	, and	MATION	WILLIAM COUNTY	AUTHORITY,		
	GROUND SYSTEM GRID OR LOOP, 36" BELOW FINISHED GRADE UNLESS OTHERWISE NOTED.	EXOTHERMIC WELD CONNECTION	3/4" x 10"-0" GROUND ROD. UNLESS SPECIFIED OTHERWISE.	GROUND ROD TEST WELL STATION (SEE DETAIL SHEET FOR	PUSH BUTTON STATION	LICHTING PANELBOARD $(P-\#)$ SHOWN ON PLAN PER ACTUAL PANEL DIMENSIONS	POWER PANELBOARD (PP-#) OR DISTRIBUTION PANELBOARD (PD-A) SHOWN ON BLAN DEP ACTUAL DAMES INTERSECTIVE	LIGHTING CONTACTOR PANELBOARD (LCP-#)	SHOWN ON PLAN PER ACTUAL PANEL DIMENSIONS	JUNCTION BOX	TERMINAL CABINET	INDICATED EQUIPMENT AND MATERIALS TO BE DEMOLISHED	INSTALLED WITHIN THE ROOM OR AREA IN WHICH THIS NOTATION APPEARS SHALL BE OF NEMA 12 CONSTRUCTION (OR GASKETED AND	SOLIMBLE FOR USES OTHERWISE NOTED.  NOT APPLY) UNLESS OTHERWISE NOTED.  INDICATE THAT ALL ELECTRICAL FOILIBRENT AND MATERIALS.	INSTALLED WITHIN THE ROOM OR AREA IN WHICH THIS NOTATION APPEARS SHALL BE OF NEMA AX CONSTRUCTION (OR CASCETED AND SUITABLE FOR USE IN A WET LOCATION WHERE YEAM	STANDARDS DO NOT APPLY) UNLESS OTHERWISE NOTED.  INDICATES THAT ALL ELECTRICAL EQUIPMENT AND MATERIALS INSTALLE!	WTHIN THE ROOM OR AREA IN WHICH THIS NOTATION APPEARS SHALL BE OF NEMA 4X CONSTRUCTION (OR CORROSION RESISTANT CONSTRUCTION SUITABLE FOR USE IN A WET LOCATION WHERE NEMA		APPEARS SHALL HAZARDOUS ARE	TRANSFORMER, RATINGS AND CONNECTIONS AS NOTED UNITED UNITEDS OF THE SINGLE LINE DIAGRAMS, ALL DRY TYPE	-			PAN, TILT, ZOOM CAMERA LENS CONTROLS	REQUEST TO EXIT		$\rightarrow$	PS] OR  PRESSURE OR VACUUM SWTCH NORMALLY OPEN, CLOSES ON RISING PRESSURE	NORMALLY OPEN, CLOSES ON DROPPING PRESSURE	NORMALY CLOSED, OPENS ON RISING PRESSURE	NORMALLY CLOSED, OPENS ON DROPPING PRESSURE	ES OR ■ FLOW SWITCH (AIR, WATER, ETC.)	NORMALLY OPEN, CLOSES ON INCREASED FLOW	NORMALLY CLOSED, OPENS ON INCREASED FLOW	(CONT):	8. CONTRACTOR SHALL MAINTAIN 12" MINIMUM SEPARATION BETTREEN POWER AND SIGNAL CONDUT.	CONTRACTOR SHALL SELL-OFF ACROSION STRENG OF LONG RECARDS LOCATION AREA FRE REC.	DRAWN CHECKED APP DATE PROJECT INFORMATION	PRINCE WI		SCADA	
		1	•	0						□			DUST	[	S S	Ē	CORROSIVE	CLASS I, DIV. 1	GROUP D	∆XX_KWA	38/4K	* TO 5	- [	22	X) EX	<b>%</b>	<b> </b> -	ı	4 ×	'		E	\ \ \ \		GENERAL NOTES (CONT):	8. CONTRACTOR MINIMUM SEP POWER AND	9. CONTRACTO CONDUITS EN HAZARDOUS I NEC.	CRIPTION				
SIMBUL.	HAME RUN TO DESIGNATED EQUIPMENT. BRANCH GRCUIT CONDUIT WITH 2 NO. 12 AND BRANCH CREAIT CONDUCTORS AND 1 NO. 12 ANG GROUND CONDUCTOR UNLESS OTHERWISE NOTED. NUMBER OF	ARROWS INDICATE NUMBER OF CIRCUITS, FOR MINIMUM SIZE CONDUIT PERMITTED REFER TO THE SPECIFICATIONS CARRIED TO SPECIFICATION OF SPECIFICATIONS CARRIED TO SECURITY OF SPECIFICATION OF SPECIFICATIONS CARRIED TO SECURITY OF SPECIFICATION OF SPECIFICATIONS CARRIED TO SECURITY OF SECURITY OF SPECIFICATION OF SPECIFICATION OF SECURITY	OR ABOVE CELLING.	CONDUIT CONCEALED IN OR BELOW FLOOR OR UNDERGROUND.	CONDUIT RUN EXPOSED. RUN PARALLEL OR PERPENDICULAR TO STRUCTURE OR WALL.	X INDICATES EXPLOSION PROOF CONDUIT SEAL FITTING	CONCRETE ENCASED DUCTBANK, MDTH VARIES, SEE DUCTBANK SECTION/DETAILS FOR REQUIREMENTS AND WIDTH	GONDUIT STUBBED OUT AND CAPPED	DENOTES A QUANTITY OF TWO (2) 3-INCH CONDUITS EACH CONTAINING THREE NO. 3/O AWG CONDUCTORS AND 1 NO. 2	JEV.V. 1849 ANG GROUND CONDUCTOR.  DENOTES A QUANTITY OF TWO INSTRUMENT CABLES. EACH CABLE	2-2/c#16 STP AND THE AND TANNING CONDUCTORS TWISTED TOGETHER PROFESS TO THE SPECIFICATIONS FOR THE PROFESSIVE JACKET, REFER TO THE SPECIFICATIONS FOR THE	EXACT CABLE TO BE PROVIDED.	2-3/C#16 STP AWG CONDUCTORS TWISTED, SHIELDED AND COVERED WITH AN OVERALL PROTECTIVE JACKET, REFER TO THE SPECIFICATIONS	(3) 4"C. THREE 4-INCH CONDUITS	PEXBLE METAL CONDUIT "MHP" (3/4"Cs, 2#12, 1#120 UNIESS OTHERWISE NOTED) FOR LIQUID TIGHT MOTOR CONNECTIONS	Y INDICATES COMPILE SEAL EXTRAC IN OTHER THAN CODE	REQUIRED LOCATIONS.    RECUIRED LOCATIONS.		\$2 DOUBLE POLE SWITCH "a" INDICATES FIXTURES CONTROLLED.	THREE WAY SWITCH "C" INDICATES FIXTURES CONTROLLED.	\$4 FOUR WAY SWITCH "d" INDICATES FIXTURES CONTROLLED.	ETM ELAPSED TIME METER FIRE FIRE FIRE FIRE FIRE FIRE FIRE FI	П	WP - WEATHER PROOF ENCLOSURE.	RECTIVI CLOSED CIRCUIT TV CAMERA	DEMOLITION GENERAL NOTES. (CONT): 1. CONTRACTOR SALL DOCOMECT AL. 7. DUCTS, WHICH ARE ONTO BE RELISED LECTRICAL POWER CONNECTIONS FOR	ALL EQUIPMENT TO BE REMOVED IN ENTER BUILDINGS AND MADE WATER CARDET TO ALLOW SAFE AND COMPLETE TIGHT.	FRANCKI, UT ALL ASSOLATED COUPWINT IN THIS AREA. ITEMS SHOWN HATCHED ARE IDENTIFIED GENERA <u>L NOTES.</u>	FOR DEMOLITION UNLESS OTHERWISE 1. CONTRACTOR SHALL COORDINATE NEW STATED IN THE DRAWING. ELECTRICAL WORK WITH ALL OTHER ASSOCIATED DISCIPLINES.		REVIEW OF POSSIBLE RE-USE. AND GROSSWAS WITH ALL OTHER 3. WOINT THE SERVICE AUTHORITY PRIOR HEW AND EXISTING ULITIES TO THE PRIOR THE PRIOR HEW AND EXISTING		SYSTEMS AND EQUIPMENT DENTIFIED AND COMPINE STACE PROVIDED IS SYSTEMS AND EQUIPMENT DENTIFIED SYSTEMS AND COMPINE SYSTEMS AND COMPINE SYSTEMS AND COMPINE SYSTEMS AND COMPINE ON SYSTEM	TRADES PRIOR TO PERFORMING ANY 4. MANTAIN AT LEAST 3" —6" IN FRONT DEMOLITION WORK.  OF ELECTRICAL EQUIPMENT PER NEC	REMOVE EXPOSED CONDUITS, OUTLET BOXES, PULLBOXES AND HANGERS MADE GBSOLETE BY THE ALTERATIONS, SYSTEM IN ACCORDANCE WITH	UNIESS DESIGNATED TO REMAIN. PATCH ARTICLE 250 OF THE INTONAL UNIESS DESIGNATED TO RECERT CODE.  COVERS FOR ABANDONED OUTLETS.	6. ARANDOR DOCUMENTS OF ALL BOUNDARD.  NALLS SAULE BC IT LISTS WITH 7. SAULDORD.  THE SLA OR WILL AT THE PORT TO STITUS WITH 7. SMITOBLOADS.  SE DITURANCE THE COMPULITS SHALL	SMOOTH AND AFFROVED MANNER.  REV. REVISION DESCRIPTION	A DRIGINAL ISSUE			




















SECTION 1 SCALE: NTS

CONTRACTOR SHALL AVOID EXISTING GROUT FILLET (SEE NOTE 3) -

TWO (2) 5/8" SS BOLTS (SEE NOTE 13)

(TYP OF TWO) EXISTING RISER PIPE

SHALL BE LOCATED AS HIGH AS POSSIBLE AND WITHIN 36" OF THE TOP OF THE STILLING WELL

TOP PIPE SUPPORT

5" CORE DRILLED HOLE

MIDDLE SUPPORT EVENLY SPACED BETWEEN OTHER SUPPORTS

SUBMERSIBLE LEVEL TRANSDUCER LOCATED 12" ABOVE INVERT OF

SHALL BE LOCATED AS LOW AS POSSIBLE AND WITHIN 96" OF THE BOTTOM OF THE

BOTTOM PIPE SUPPORT

STILLING WELL


WET WELL (TYP OF TWO)

12"x12"x6" SS NEMA 4X PULL BOX (SEE BOX MOUNTING

DETAIL)

BETWEEN BOX AND CONCRETE WETWELL TOP

**NEOPRENE GASKET** 



### Appendix D

**Example Equipment & Instrument and I/O Lists** 

## Instrumentation List

Site ID	DWG QTY	TY TAGID	Description	Function	Make	Model	Part Number	Range / Output	Units	Power	Notes
	1	1 LT-101A	Pressure (Level) Transducer	Wet Well Level	ISdX	120	750S14D4B013.002000.000B10050B	0-30	Feet	24 VDC Loop	Lightning Protection
	1	1 LT-101B	Pressure (Level) Transducer	Wet Well Level	ISdX	220	750S14D4B013.002000.000B10050B	0-30	Feet	24 VDC Loop	Lightning Protection
	1	1 PQM-400	Power Quality Monitor	Power Data	PC&S		DKM-411	Modbus TCP		120VAC from UPS	Self Enclosed Assembly
	1	1 JSL-402B	Phase Monitor Relay - Load Side	Site Loss-of-Power	ATC Diversified Electronics	SLU-100 series	SLU-100-ASA	SPDT		Integral	
	1	1 LIT-404	Ultrasonic Level Transmitter	Fuel Tank Level	EchoSpan (Flowline)	LU81	LU81-5101	0.75 18	Feet	24 VDC Loop	
	1	1 XS-701	Smoke Detector	Building Smoke Alarm	System Sensor	100 Series	2151	SPDT		120 VAC	
	1	1 TT-700	Temperature Transmitter	Building Temperature	Dwyer	RHP-E/N Series	RHP2N44LCD	20 140	Ⅎ。	24 VDC Loop	
	1	1 ACR-801	Card Reader	Card Access	Isonas	RC-04 Series	RC-04 PRX-M	SPDT		Power over Ethernet	Include Pigtail Cable
	1	1 HS-801	Request to Exit Push Button	Request to Exit	SDC	440 Series	446U	DPST			
	1	1 ZS-801	Magnetic Contact	Door Opened	Edward Signaling	2500 Series	2507A-L	SPDT			Main Door
	1	1 ZS-802A	Magnetic Contact	Door Opened	GE Security	2800 Series	2844TW-M	SPDT			Grinder Vault Hatch
	1	1 ZS-802B	Magnetic Contact	Door Opened	GE Security	2800 Series	2844TW-M	SPDT			Wet Well Vault Hatch
	1	1 ZS-802C	Magnetic Contact	Door Opened	GE Security	2800 Series	2844TW-M	SPDT			Meter Vault Hatch 1
	1	1 ZS-802D	Magnetic Contact	Door Opened	GE Security	2800 Series	2844TW-M	SPDT			Meter Vault Hatch 2
	_	1 CAM-830	PTZ Network Camera (indoor)	Operational Video	Panasonic		WV-S6130	Ethernet		Power over Ethernet	
	_		LED Lighting	Building Illumination	Metalux	WNLED Series	4WNLED-LD4-50SL-F-UNV-L850-CD-1-U				
	2		Multiband Omni-Directional Stick Outdoor 4G Antenna	Outdoor Antenna	Cisco		ANT-4G-OMNI-OUT-N				

XX         1         JSL-402A         Phase Monitor Rey-Utility         SSAC         RLM611         SPDT         Poste ATS           XX         1         LSH-Ho10         Med Well High Level Switch         RM	Existing Devices	ses								
1 LSHH-101   Wer Well High Level Switch   Level S	XX	1	JSL 402A		SSAC		RLM611	SPDT		Inside ATS
1 LSH3-100 Influent Channel High Level Switch   E131-010 On Endmet Channel High Level Switch   E131-010 On Endmet Channel High Level Switch   E131-010 On Endmet Pleu Meder   E11-300 Flow Presenting Flow Transmitter   E131-010 Rev Trans	XX	1	LSHH-101	Wet Well High Level Switch						
1         FE.300         Discharge Flow Meter         ABB         MAG.XM         0-500           1         FIT-300         Flow Transmitter         0-500         0-500           2         CV-2016 & 202         Check Valves         0-500           1         G-100         Grinder         0-500	XX	1	LSH-100	Influent Channel High Level Switch						
1         FIT-300         Flow Transmitter         ABB         MAG-XM         0-500           2         CV-2016 & 200         Chick Valves         0-500         Critical Control         0-500           1         G-100         Grinder         Critical Control         Critical Control         Critical Control         Critical Control	XX	1	FE-300	Discharge Flow Meter						
2 CV-201 & 202 (	XX	1	FIT 300		ABB	MAG-XM		005-0	GPM	
1 G-100	XX	2	CV 201 & 202	_						
	XX	1	G-100	Grinder						

-

# I/O List

				_							
ISA Tag	Description	Туре	Rack	Slot	Point	Alarms	Range	Units	Power	Backup OIT	Notes
LT-101A	Wet Well Lvl 1 (Submersible) Raw	AI	0	3	0	-	0 - 30	FT	24VDC Loop powered	Yes	w/ ISB
FIT-300	Discharge Flow Meter Raw	ΙΑ	0	8	2	ı	009 - 0	GPM	120 VAC (External)	ı	
		A	0	က	2	1	ı	ı	ı	ı	
		A	0	3	3	-	-	1	-	1	
LT-101B	Wet Well Lvl 2 (Submersible) Raw	A	0	4	0	ı	0 - 30	F	24VDC Loop powered	Yes	w/ ISB
LT-404	Generator Fuel Tank Level Raw	₹	0	4	-	ı	0.75 - 18	ᇤ	24VDC Loop powered	1	
TT-700	Building Temperature Raw	A	0	4	2	ı	-20 - 140	ĥ	24VDC Loop powered	1	
		A	0	4	က	ı	ı	ı	ı	ı	
YL-201	Pump No. 1 Remote Raw		0	7	0	ı	,	1	1	1	
MN-201	Pump No. 1 Running Raw		0	2	-	ı	ı	1	ı	1	
XA-201	Pump No. 1 Failed Raw	П	0	2	2	1	ı	1	1	ı	Normally Closed
ZSO-201	Pump No. 1 Check Valve Opened Raw	Ю	0	2	3	-	-	1	1	-	
MAH-201	Pump No. 1 Seal Leak Raw	Ю	0	2	4	-	-	ı	1	1	Normally Closed
TAH-201	Pump No. 1 Over Temperature Raw	Ю	0	2	5	ı	ı	1	ı	ı	Normally Closed
		IO	0	2	9	-	-	1		-	
		П	0	2	7	-	1	1	-	ı	
		IO	0	2	8	1	-	1	-	ı	
ZS-802	Vault Intrusion Raw	IO	0	2	6	-	-	1		-	Normally Closed (w/ ISB)
		П	0	2	10	-	1	1	-	ı	
		П	0	7	11	-	ı	ı	-	ı	
		DI	0	7	12	-	ı	1	-	ı	
LSH-100	Influent Channel High Level Switch Raw	Б	0	2	13	ı	Î	ı	•	1	w/ ISB
MN-100	Grinder Running Raw	Ю	0	2	14	-	-	1	-	1	
XA-100	Grinder Fault Raw	Ю	0	2	15	-	-	1		-	
YL-202	Pump No. 2 Remote Raw	Ю	0	8	0	1	-	1	-	ı	
MN-202	Pump No. 2 Running Raw		0	80	-	ı	ı	1	ı	1	
XA-202	Pump No. 2 Failed Raw	IO	0	8	2	1	1	1	-	-	Normally Closed
ZSO-202	Pump No. 2 Check Valve Opened Raw	Ю	0	8	3	-	-	1	-	ı	
MAH-202	Pump No. 2 Seal Leak Raw	Ю	0	8	4	-	-	1	-	-	Normally Closed
TAH-202	Pump No. 2 Over Temperature Raw	П	0	8	5	ı	-	-	•	1	Normally Closed

	۵	0	ω	9	1	1	•	•	1	
	IO	0	8	7	1	1	'		1	
	П	0	8	ω	ı	1	'	ı	ı	
	IO	0	80	6	ı	1	'	1	1	
Utility Phase Failed Raw	DI	0	8	10	ı	1	-	-		Normally Closed
Wet Well Hi Level Switch Raw	П	0	ω	1	ı	1	'	1	Yes	w/ ISB
ATS Utility Connected Raw	П	0	∞	12	ı	1	'	ı	1	
ATS Utility Available Raw	П	0	8	13	ı	1	1	ı	ı	
ATS Generator Connected Raw	۵	0	80	41	ı	1	'	ı	1	
ATS Generator Available Raw	Ia	0	8	15	ı	1	'	ı	1	
	IO	0	6	0	ı	,	'	,	1	
	IO	0	6	-	ı	1	'	1	1	
	DI	0	6	2	1	1	-	1	-	
	IO	0	6	3	-	-	-	-	-	
	IO	0	6	4	Ī	-	'	ı	ı	
Generator Running Raw	IO	0	6	5	I	-	-	1	-	
Generator Fault Raw	DI	0	6	9	-	-	-	-	-	
PLC AC Power Fail Raw	IO	0	6	7	ı	1	-	-	1	Normally Closed
Load Phase Failed Raw	IO	0	6	8	I	-	-	-	-	Normally Closed
MCC Room Smoke Alarm Raw	DI	0	6	6	Ī	1	1	1	1	Normally Closed
Card Reader Access Granted Raw	DI	0	6	10	Ī	1	1	-	-	
Main Door Intrusion Raw	IO	0	6	11	1	-	-	-	-	Normally Closed
PLC Panel Door Intrusion Raw	IO	0	6	12	Ī	1	1	-	1	Normally Closed
Communication Panel Door Intrusion Raw	IO	0	6	13	I	-	-	-	-	Normally Closed
Surge Arrestor Fault Raw	IO	0	6	14	I	-	1	ı	ı	Normally Closed
24VDC Power Supply Redundancy OK Raw	IO	0	6	15	ı	-	-	1	-	Normally Closed
Pump No.1 Start/Stop Raw	DO	0	10	0	ı	ı	1	ı	Yes	
	OO	0	10	-	ı	1	'	1	1	
	ОО	0	10	2	ı	-	-		-	
	DO	0	10	3	1	1	1	-	-	
	DO	0	10	4	I	1		1		

		00	0	10	5	1	ı	ı	•	1	
		DO	0	10	9	1	ı	-	1	-	
xxx-xx	Remote Backup Control Request	DO	0	10	7	1	-	1		SəY	DI in Backup OIT
MC-202	MC-202 Pump No.2 Start/Stop Raw	DO	0	11	0	•	1	1	-	Yes	
		DO	0	11	1	1	1	1		-	
		DO	0	11	2	•	ı	1	-	-	
		DO	0	11	3	-	1	1	-	-	
		DO	0	11	4	1	ı	1	-	-	
JC-403	Generator Remote Test Raw	DO	0	11	5	•	1	1	-	1	
CAC-830	Camera Event Raw	DO	0	11	9	-	1	1	-	-	
YAC-801	YAC-801 PLC Alarm Horn Raw	DO	0	11	7	•	1	1	-	-	

# Appendix E

Alarms, Alerts, and Logging Configuration

## Appendix E - Alarm Identification and Prioritization

The primary function of the alarm system is to alert the operator to deviations from normal operating conditions, i.e. abnormal operating situations. The ultimate objective is to prevent, or at least minimize, physical and economic loss through operator intervention in response to the condition that was alarmed. The secondary function of the alarm system is to serve as an alarm and event log so operations staff can analyze the events that have led to current or past incidents. The log can also be used for analysis to optimize D&C system operations.

The facility design shall include all necessary PLC I/O and equipment and instrumentation to support and enable alarms for all process variables and monitored equipment. The Designer shall submit the recommended and proposed alarm configuration for review and acceptance (or acceptance as modified) by PWW.

#### **Alarm Identification**

For each design package, the PDE shall ensure that the alarms to be generated by the SCADA system meets PWW's requirements. PWW has defined what conditions are to be configured as alarms, and what conditions are alerts or log entries.

The Designer shall submit for approval a completed I/O list with the configuration of all alarms, alerts, or logging settings clearly identified. The design shall include hardware and software provisions to monitor and alarm all process variables and equipment condition and status, unless specifically excluded by PWW. Each alarm shall meet the definition as stated by ISA 18.2:

An alarm is an audible and/or visible means of indicating to the operator an equipment malfunction, process deviation, or abnormal condition requiring a response.

Alarms generated by the D&C SCADA system shall meet the above definition and specific criteria defined below:

"An alarm is an audible and/or visible means of indicating" - There must be an indication of the alarm. An alarm limit can be configured to generate control actions or log data but if this limit is not audibly or visually indicated it should not be considered analarm.

**"to the operator" -** The indication must be targeted to the operator to be an alarm, not to provide information to an engineer, maintenance technician, or manager.

"an equipment malfunction, process deviation, or abnormal condition" - The alarm must indicate a problem, not a normal process condition or normal operational event (e.g., pump stopped, valve closed). The SCADA system should be configured to determine if any events have occurred unexpectedly (i.e., are "abnormal"). If an unexpected or abnormal event has occurred and operator action is required, this notification should be classified as an alarm.

"requiring a response." - There must be a defined operator response to correct the condition and bring the process back to a desired (safe and/or productive) state. If the operator does not need to respond, then the condition should not be an alarm. A notification that has no associated operator action should be defined as an alert or message. Acknowledging the alarm or logging a measurement is not considered an operator response (does not correct the abnormal situation). Typical operator responses to alarm include:

- Change the desired setpoint of an operating sequence
- Close a valve or gate
- Start a backup pump
- Issue a corrective work order

Conditions that **do NOT** meet the above criteria shall not be designated as an alarm.

#### Alarm Identification

For each alarm identified and/or designed by the PDE, an associated alarm priority shall be assigned. PWW utilizes three alarm priorities which are presented in Table 1 to convey the seriousness of the specific process condition:

Table 1 - Alarm Priorities

Alarm Priority	Severity	Percentage of Total Alarms
Emergency	Severe	3 – 7% (5%)
High	Major	15 – 25% (20%)
Low	Minor	70 – 80% (75%)

To assist in the assignment of alarm priorities, the following tables will help determine the most appropriate priority for the alarm. The first and most important of these tables is for the "Areas of Impact and Severity of Consequences" (Table2). To use the table, each Impact Category should be considered separately for the alarm. The PDE should focus on "How severe are the consequences, if the alarm occurs and no operator action is taken in response?" Note that any single scenario may have different severities in the different impact categories which are normal and expected. Industry best practices recommend assigning the overall severity for the event to be whichever one is worst.

Table 2 - Areas of Impact and Severity of Consequences

Impact Category	Severity: NONE	Severity: MINOR	Severity: MAJOR	Severity: SEVERE
Personnel Safety	No injury or health effect	<ul><li>Slight injury or health effect</li><li>No disability</li><li>No lost time or recordable</li></ul>	Injury affects work performance max of one week Reversible health effects	Lost time injury > 1 week Severe injuries Life threatening situation
Public or Environme ntal	No effect	<ul> <li>Local</li> <li>environmental effect</li> <li>Little, if any clean-up</li> <li>Negligible financial consequence</li> <li>Internal or routine reporting</li> </ul>	Spill causes some non-permanent damage Single complaint Single exceedance of prescribed limit Reporting required at the local agency level	Impacts community Repeated exceedances Major environmental impact Extensive cleanup or financial consequences State or EPA reporting required
Production Loss / Downtime	No loss	■Staff level reporting required	Departmental level reporting required	Senior management level reporting required

The second table, "Maximum Time to Respond" (Table 3), helps determine the time an operator needs to take action in order to prevent or mitigate the undesired consequence caused by an abnormal condition. The response time is how much time is available to take the effective action from when the alarm sounds to when the consequence becomes unavoidable, regardless of the action.

**Table 3 - Maximum Time to Respond** 

Category	Maximum	Meaning
No Alarm	> 30 Minutes	May not qualify as an alarm.
Promptly	15 to 30 Minutes	This alarm must be dealt with, but you can first make a quick phone call or complete a new task.
Rapidly	5 to 15 Minutes	Quickly wrap up the phone call. Finish an ongoing short task. Don't start anything new - this alarm has to be dealt with.
Immediately	< 5 Minutes	Drop what you are doing and respond to this alarm right now. Hang up the phone. Interrupt a conversation.

Table 4 combines the results of the two tables together to help determine the most appropriate priority for the alarm. For all "Emergency" alarms, industry best practices recommended that pre- alarms be created and set to a "High" priority (if practical), so the operator to take effective action in response to the pre-alarm. On parameters such as toxic and flammable gas detectors, this is usually not practical to have a pre-alarm condition.

**Table 4 - Priority Determination Grid** 

Maximum Time to Call-Out > 30 Minutes	Consequ ences No Alarm	Consequences Severity: MAJOR No Alarm	Consequences Severity: No Alarm
15 to 30 Minutes	Low	Low	High
5 to 15 Minutes	Low	High	High
< 5 Minutes	High	Emergency	Emergency

# Appendix F

PCSS/AESS Qualification Requirements

## PCSS QUALIFICATION REQUIREMENTS

- A. The PCSS shall be a "systems integrator" regularly engaged in the design and the installation of instrumentation systems and their associated subsystems as they are applied to the municipal water and wastewater industry. PWW defines a "systems integrator" as an organization that complies with all of the following criteria:
  - 1. Employs personnel who have successfully completed ISA or manufacturers training courses on general process instrumentation and configuration and implementation of the specific programmable controllers, computers, and software proposed for this project. Key personnel shall hold ISA Certified Control Systems Technician (CCST) Level 1 certification or have a minimum of 10 years of verifiable system startup experience. Key personnel shall include, as a minimum, the lead field technician.
  - 2. Has successfully completed work of similar or greater complexity on at least three previous projects within the last five years. Successful completion shall be defined as a finished project completed on time, without any outstanding claims or litigation involving the PCSS. Potential references shall be for projects where the PCSS's contract was of similar size to the designed project.
  - 3. Has been actively engaged in the type of work specified in this Section for a minimum of five years.
- B. The PCSS shall maintain a permanent, fully staffed and equipped service facility within 200 miles of PWW's main office at 4 County Complex Court, Woodbridge, VA 22192, with full time employees capable of designing, fabricating, installing, calibrating, and testing the systems specified herein. At a minimum, the PCSS shall be capable of responding to on-site problems within 12 hours of notice. Provide an on-site response within 4 hours of notification starting at two months before scheduled start up to two months after startup completion.
- C. PCSS shall hold a valid UL-508 certification for their panel fabrication facility.
- D. Actual installation of the instrumentation system need not be performed by the PCSS's employees; however, the PCSS as a minimum shall be responsible for the technical supervision of the installation by providing on site supervision to the installers of the various components.

## **AESS QUALIFICATION REQUIREMENTS**

- E. Because the AESS is a Critical Sub Contractor PWW requires that the AESS shall be a "systems integrator" regularly engaged in the design, installation, and programming of Graphical SCADA systems and Programmable Logic Control systems, OITs and their associated subsystems as they are applied to the municipal water and wastewater industry. PWW defines a "systems integrator" as an organization that complies with all of the following criteria:
  - 4. Employs personnel who have successfully completed ISA or manufacturers training courses on general process instrumentation and configuration and implementation of the specific programmable controllers, computers, and software proposed for this project. Key personnel shall have a minimum of 10 years of verifiable SCADA, PLC, and OIT systems programming and startup experience. Key personnel shall include, as a minimum, the lead programmer.
  - 5. Has successfully completed work of similar or greater complexity on at least three previous projects within the last five years. Successful completion shall be defined as a finished project completed on time, without any outstanding claims or litigation involving the AESS. Potential references shall be for projects where the AESS's contract was of similar size to the designed project.
  - 6. Has been actively engaged in the type of work specified in this Section for a minimum of five years.
- F. The AESS shall maintain a permanent, fully staffed and equipped service facility within 200 miles of PWW's main office at 4 County Complex Court, Woodbridge, VA 22192, with full time employees capable of designing, fabricating, installing, calibrating, and testing the systems specified herein. At a minimum, the AESS shall be capable of responding to on-site problems within 12 hours of notice. Provide an on-site response within 4 hours of notification starting at two months before scheduled start up to two months after startup completion.
- G. An AESS not directly contracted by PWW shall submit a qualifications package to PWW for review and approval prior to being selected for the work.

# Appendix G

**Acceptance Testing** 

## SYSTEM TESTING

#### A. General

- 1. Testing of each panel and/or system shall be scheduled, performed in an orderly sequence, and conducted in the presence of, and to the satisfaction of the Engineer. Testing shall be conducted for each component and system in accordance with the PCSS's submitted plan that has been reviewed by the Engineer.
- 2. UPS and Network Switches are installed in the Communications Panel. Because the PLC Panel functionality is largely dependent on this equipment, all PLC Panel and Communications Panel testing shall be performed with both panels interconnected to demonstrate all required functionality.
- 3. Testing shall include the operation of all hardware, AESS logic, and custom control features.
- 4. The following Factory Testing shall be provided for the PCS PLC Control Panel and Communications Panel:
  - a. Unwitnessed Factory Test (UFT)
  - b. Witnessed Factory Test (WFT) (Optional if requested)
  - c. System Integration Test (SIT) (Optional if requested)
- 5. The following Field Testing shall be provided for the PCS PLC Control Panel and Communications Panel:
  - a. Operational Readiness Test (ORT)
  - b. Site Acceptance Test (SAT)
- **B.** Factory Testing Requirements
  - 1. Unwitnessed Factory Test (UFT)
    - a. The purpose of the UFT is for the PCSS to check the hardware portion of the system prior to the WFT. This type of testing should be part of any quality firm's internal Quality Assurance / Quality Control (QA/QC) procedures.
    - b. Tests to be performed shall include, but not be limited to, the following:
      - 1) Panels and enclosure inspection to verify integrity of cabinet enclosures, frame structures, paint work and finish.
      - 2) System audit to verify all components have been staged for the test and have been documented properly with correct model numbers, serial numbers, etc.
      - 3) Panel wire pull tests to ensure all wiring has been connected with the appropriate torque to prevent wires from coming loose.
      - 4) UPS test to verify all UPS backed loads are kept online when in operations.
      - 5) Network test to verify all communications are functional. Network tests shall include demonstrating that all Ethernet and Serial links are able to communicate between devices as required and proper data is received. Tests shall include but are not limited to:
        - a) UPS to PLC communications

- b) PLC to [Main] OIT communications
- c) PLC to Managed Switch (network ping test)
- d) OIT to Managed Switch (network ping test)
- e) Backup OIT to Managed Switch (network ping test)
- f) UPS to Managed Switch (network ping test)
- g) Camera to Managed Switch (network ping test)
- h) Access Badge/Card Reader (network ping test)
- 6) PLC I/O point checkout to verify proper control panel wiring and I/O module setup.
- c. Upon successful completion of UFT, the PCSS shall submit a record copy of test results to PWW and request scheduling of the WFT.
- 2. Witnessed Factory Test (WFT) (Optional if requested)
  - a. The purpose of WFT is to allow PWW to witness the functionality, performance, and stability of entire hardware system prior to the AESS testing the software portion. This test shall be a repeat of the UFT.
  - b. Upon successful completion of WFT, the PCSS shall submit a record copy of test results to PWW and notify the AESS in writing that the system is ready for SIT. The AESS shall schedule and complete the SIT within 30 days of receipt of the submittal.
- 3. System Integration Test (SIT) (Optional if requested)
  - a. The purpose of SIT is to allow the AESS to test entire hardware and software system as a complete integrated system prior to installation in the field. During the SIT, the AESS shall have unrestricted access to the entire PLC system to verify the functionality of the PLC program and OIT application.
  - b. The SIT shall be run by the AESS, with assistance from PCSS as needed. The test shall be conducted at PCSS's facility. Normal access to the system shall be from 7:30 am to 4:00 pm Monday through Friday.

### C. Field Testing Requirements

- 1. Operational Readiness Test (ORT)
  - a. The purpose of the ORT is to check that the process equipment, instrument installation, instrument calibration, instrument configuration, field wiring, control panels, and all other related system components are ready to monitor and control the processes. This test determines if the equipment is ready for operation.
  - b. The ORT shall take place prior to startup. Prior to starting this test, relevant process equipment shall be installed and mechanically tested, instruments installed, control panels installed, and field wiring complete.
  - c. The following steps shall be performed as part of the ORT:
    - 1) Instrument calibration, configuration, and set-up. Calibrate, configure, and set-up all components and instruments to perform the specified functions.
    - 2) PCSS hardware and I/O testing. The purpose of the PCSS hardware and I/O signal testing is to check that the process equipment, instrument installation, calibration, configuration, field wiring, and the control panels are set-up correctly to monitor

- and control the processes. This test is commonly referred to as a "loop test" or an I/O checkout.
- 3) I/O Testing to the HMI and OITs with AESS. The purpose of the I/O testing to the HMI and OITs with AESS is to check that the instruments and field equipment are connected properly and work from the end device, through the PLC, to the HMI and OITs.
- 4) Testing of Automatic Control Strategies with AESS.
- 5) Testing and demonstration of the backup control system and strategies.
- 6) Network Tests that include demonstrating that all Ethernet and Serial links are able to communicate between devices as required and proper data is received. Tests shall include but are not limited to:
  - a) UPS to PLC communications
  - b) PLC to [Main] OIT communications
  - c) PQM to PLC communications
  - d) PLC to Managed Switch (network ping test)
  - e) OIT to Managed Switch (network ping test)
  - f) Backup OIT to Managed Switch (network ping test)
  - g) UPS to Managed Switch (network ping test)
  - h) Camera to Managed Switch (Video Check)
  - i) Access Badge/Card Reader (network ping test)

Specific control strategies shall be verified using actual process equipment and instruments, or other means, to verify the logic performs as expected. Testing shall verify faults and logical failure scenarios for control strategies such as instrument failures, equipment failures, loss of communications, out-of-range testing for analog inputs, loss of power, and all other strategies specified in the control strategies. This test shall be run by the AESS, with assistance from the PCSS as necessary.

#### 2. Site Acceptance Test (SAT)


- a. After system is started-up and running the process in automatic control to extent possible, system shall undergo a Site Acceptance Test. While this test is proceeding, PWW shall have full use of system. Only operating personnel shall be allowed to operate equipment associated with live processes. Operations shall remain responsibility of PWW and decision of the operators shall be final.
- b. During this test, PCSS personnel shall be present as required to address any potential issues that would impact system operation. PCSS is expected to provide personnel for this test who have an intimate knowledge of equipment supplied as part of this system. When PCSS personnel are not on-site, PCSS shall provide cell phone/pager numbers that Owner personnel can use to ensure that support is available by phone and/or on-site within four hours of a request by operations staff.
- c. Any malfunction during test shall be analyzed and corrections made by PCSS. Throughout duration of SAT, no modifications shall be made to system without prior approval from PWW.

## D. Additional Field Testing Requirements

- 1. Demonstrate the control features of each panel and associated field mounted instrumentation and control equipment, to verify that each panel performs the required control functions and logic as shown on the Contract Drawings or as specified. Control features shall include relay energization, initiation of alarm conditions, resets, interlocks, set point activation, and other functions of the control panels.
- 2. Equipment shall be field demonstrated to operate satisfactorily in the presence of the Owner, and shall be conducted in accordance with the PCSS's testing and demonstration plan that has been reviewed by the Engineer. Field demonstrations shall be performed after successful installation, calibration and testing of each control panel.
- 3. In addition to demonstrating the operation of standard control features, special control panel functions shall be demonstrated as specified for each panel as specified below.
- 4. The Contractor shall provide the necessary test equipment, process media, materials, supplies, and qualified test personnel to perform the field demonstrations as specified herein.
- 5. Field instrumentation control signals that are required to demonstrate the operation of associated control panels may be simulated upon approval of the Engineer.
- 6. In the event of failure of the field demonstration, the Contractor shall perform the necessary corrections and re-demonstrate, at his own cost and expense, the equipment as directed by the Engineer.
- E. The PCSS shall provide competent personnel to participate in all testing.
- F. The PCSS shall provide competent personnel to participate in the testing and startup of the facility as scheduled below and as specified in Section 01660, Testing and Startup.
- G. Time Durations
  - 1. Contractor and PCSS shall allot for and allow the following minimum time duration for each specified item.
    - a. Completion of AESS's Programming A minimum of ninety (90) calendar days are required for the AESS to complete the programming necessary prior to the System Integration Test. The allotted time period shall not start until panel layout drawings have been submitted and approved, but may also start as late as 90 days prior to anticipated panel delivery date.
    - b. Completion of AESS's Optional Software Integration Test at PCSS's facility Twenty-one (21) calendar days after successful completion and acceptance of the Witnessed Factory Test.
    - c. Completion of AESS's Application Software Operational Readiness Tests Twenty-one (21) calendar days after successful completion and acceptance of the PCSS's Operational Readiness Testing.

# Appendix H

Remote Site Network Configuration Requirements



# Appendix I

Sample Schedule

	Activity ID	Activity Name	Orig Start Finish	Total   Qtr 4, 2016   Qtr 1, 2017	GW 2, 2017 GW 3, 2017 GW 4, 2017 GW 1, 2018 GW 2, 2018 GW 3, 2018 GW 4, 2018 GW 1, 2019 GW 2, 2019 GW 3, 2019	Qtr 4, 2019   Qtr 1, 2020   Qtr 2, 2020   Qtr 3, 2020	20 Otr 4, 2020
March   Marc				Oct Nov Dec Jan	Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep	Nov Dec Jan Feb Mar Apr May Jun Jul Aug	Oct
March House, and the control of th	PWCSA SCADA Bas	eline DD3Jan17	03-Jan-17				
Control Cont	MILESTONES		Octobil 1	2			
Control of the Part	MS1000	Notice to Proceed		<b>•</b> †	ice lo Proceed		
Continued and Continued	MS1020 MS1030	Nick-Orff Meeting MILESTONE #1:(Completion of Sewer Group 1 & Water Groups D	10-Jan-17	31d	WILEST	fler NTP 22Jun18)	
The contraction of the contract of the contr		&C) (535 caldays after NTP 22Jun18)					
The file Company of the Court of Market (17) and with the Court of Market	MS1040	MILESTONE #2:Miestone 2 (Completion of Sewer Group 2 and Water Groups A&B, E, F) (841 days after NTP 23Apr19)			→ MILESTONE #2/Mestone 2 (Comple	<del></del>	(84) days after
Control of Control o	MS1050	MILESTONE #3: Completion of Sewer Group 3 & Water Groups G, H) (1110 days after NTP 17Jan20)				■ MILESTONE #3; Completion of Sewer Glou	up 3,8 Water Gn
Contact   Cont	MS1060	MILESTONE #4: Substantial Completion (1313 days after NTP 07Aug20)		_		MILESTO	NE #4: Substan
Section Control Engineering   Sect	MS1070	Final Completion (1415 days after NTP 17Nov20)					
State   Country   Countr	MILESTONE 1 PROJE	ECTS	345d 03-Jan-17 09-May-18	8 31d			
Review Esting Documentation   143   Charlet Y Charlet	SEWER GROUP 1		345d 03-Jan-17 09-May-18	8 31d			
Profess the Land Block Surveys   Processing Surve	DESIGN SG1-D4030	Davisu Evietics Decimontation	03-Jan-17	244 SG1-D1030	ion: Exterior Drouwandilion		
Proper Feature Signature Summares   34   24-Line 17   244	SG1-D1040	Perform Site Surveys	04-Jan-17	24d SG1-D1040	Perform Site 9		
Source Feelware Precisions   Source Feelwa	SG1-D1050	Prepare Field Investigation Summaries	24-Jan-17	24d SG1-D1050	Prepare Field Investigation Summaries		
Summer Bore Protection   Control Protection   Con	SG1-D1080	Submit Field Investigation Summaries	1 10	<b>₹</b> 13	Submit Fiel		
Convert February   Convert Feb	SG1-D1030	Submit 50% Design Package	/	240 36 -010	t		
Solution   President   Solution   Solution	SG1-D1070	Owner Review Period	10-Apr-17	24d SC	-D107d— Owner Review Period		
Submit Design Review Meeting Minutes	SG1-D1080	50% Design Review Meeting	01-May-17	24d	330 t-Drβ30 <sup>™</sup> 50% Design Review Meeting		
Develop Petral Design Peckage   155 Okmber 17 22-Meyr 17 22-Meyr 17 22-Meyr 17 22-Meyr 17 22-Meyr 18 24-Meyr	SG1-D1090	Submit Design Review Meeting Minutes		24d	■ Submit besign Review Meeting Minutes		
Submit Persere & Acquire DP-Submesteb Lift Station   42d 2-4Map-17 2-4Jul-17 33d   SG-D1100-4	SG1-D1010	Develop Pre-Final Design Package	03-May-17	24d	SG1-D1(110+TT Devjetop Pte-Final Design Package		
PERMINI Prepare & Acquire ID-Schmersbell III Station   422 24-May-17 24-Laf17 107d   359   17104   100   1	SG1-D1100	Submit Pre-Final Design Package		400	Submit Pre-Final Design Package		
Overline Percent Routine Rou	SG1-D1104	PERMIT: Prepare & Acquire DP-Submersible Lift Station	24-May-17	-	j.		
Pre-Fired Design Review Meeting   14   08-Jun-17   24-Jun-17   2	SG1-D1110	Owner Review Period	24-May-17		D1110 - Owner		
Submit Design Package   3d 09-Lun-17   32-d   3d 09-Lun-17   3d	SG1-D1120	Pre-Final Design Review Meeting	08-Jun-17	-	SET-D1120 Pre-linal Design/Reylew Meeting		
Dovelop Field Design Package   Control Field Design Package	SG1-D1130	Submit Design Review Meeting Minutes		_	Submit Dosign Revide Meeting Minutes		
School For Color Procure - Instrumentation   Grand Obstacles   School For Color Procure - Instrumentation   Grand Obstacles   School For Color Procure - Instrumentation   Grand Obstacles   G	SG1-D1140	Develop Final Design Package		-	1140 1140		
Exercise P.O. For Coll De Poceire - Instrumentation   Coll Devices   Exercise P.O. For Coll De Poceire - Instrumentation   Coll Devices   Exercise P.O. For Coll De Poceire - Instrumentation   Coll Devices   Coll De	SG1-D1150	Submit Final Design Package	F) W		STODING THE FIRST PRICE TO SEE THE SECOND TO SECOND THE		
Februation & Deliver for - Instrumentation   450 (C-May-17)   C-May-17   128d   SG-1-P275   Februation & Deliver for 1 Instrumentation   Februation & Deliver for 1 Instrumentation   Februation & Deliver for 1 Instrumentation   February for 1 Instrumentation   Fe	SG1-P2030	Execute P.O for CCI to Procure - Instrumentation		128d	Elecute P.O. for CO. to Precure		
Fabrication & Deliver for Sterwood-Logan - Panel LO4	SG1-P2025	Fabrication & Deliver for - Instrumentation		128d	32		
Release for Fathcackin for Shewood, Logan - Panels   04   03-Jup-17   24d   07-Jup-17   24d   27-Jup-17   24d   27-Jup	SG1-P2050	Fabrication & Deliver for Sherwood-Logan - Panel L04		24d	1-P2050		
Submit Control Panel LPT Results Panel LO4	SG1-P2040	Release for Fabrication for Sherwood- Logan - Panels	09-Jun-17	-	for Fabrication for Sherwood-Logan - Pan		
Submit Control Pland LTP Results Panel Load   1740   174	SG1-P2060	Unwitnessed Factory Testing (UFT) Panel L04		-	bassaumun TO9		
Programming Stamilial Package	SG1-P2070	Submit Control Panel UFT Results Panel L04		_	ŭ		
gamming Submitted Package  Od 07-List 7  Table Rough Condition of Old Devices  22 07-Aug+77 22-Aug+77 22-	CONSTRUCTION	ر ا	07-10-17				
nation of Ob Daviese  22	SG1-CN0110	Programming Submittal Package	07-Jul-17		Page Productor (Skhrijiza Page Kana		
circal Rough—in Conduit and Wree         100         Ob-Aug-17         22-Aug-17         35-3         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-On 13 Fig. Selected to began in the conduit and wree         SS C-ON 13 Fig. Selected to be a selected to be a selected to be a selected to selected	SG1-CN0120	Demolition of Old Devices	07-Aug-17	-	20 Dempittor of Did		
all New Jezumentation         22         22-Aug-17         24-Aug-17         34-Aug-17	SG1-C0N130	Electircal Rough-in / Conduit and Wire	09-Aug-17	-	-cdN 30 - Electrica Relighin / Conduit and W		
Half New Communication & PLC Painels  56 12-Aug-17 33-4 ag 1-14 ag 1-	SG1-CN0140	Install New Instrumentation		-	S1-CN07401 Install New		
Communication   Communicatio	SG1-CN0150	Install New Communication & PLC Panels		_	National Property of the Prope		
Control Cycle and the Control Penetral National National Penetral National National Penetral National National Penetral National Nationa	SG1-CN0160	Perform Loop Checks  Barform Operational Bardinger Test (OBT)		_	-CN0180 FILE Perform Loop Checks		
Communication & Public Parking   Sept.   Sept.   Communication & Public Parking   Sept.   Se	961-000170	Perform Operational Regulates Less (ORL)	11-3eb-17	-	The state of the s		
gramming Submitted Package  do 2 2-12-14 7 8-40  for Exchange 10 4 2-12-14 7 8-40  for Exchange 20 4 14-40-17 8-17 8-40  for Exchange 20 4 14-40-17  for Exchange 20	14 - Occours Plan	Perform Site Acceptance Testing (SAL)	71-Sep-17	-	- CNOT SCHOOL STEWARD CONTROL		
Complexation / UFT & Definery of Penel L14         5d         08-Aug-17         14-Aug-17         53d         SSO-LOW/2007         Complex countries and countries	SG1-CN0210	Programming Submittal Package	-	-	E		
Submit Control Panel UFT Results Panel L14   0d   14-Aug-17   33d   84-10-17   33d   84-10-17   33d   84-10-17   34d   84-10-17   84-17   84-1	SG1-CN0220	Cmpl Fabrication / UFT & Delivery of Panel L14	08-Aug-17	-	CN0220 - Cmol Rabridation		
Demonstration of Dol Devices   2d   18-Aug-17   21-Aug-17   24-Aug-17   24-A	SG1-CN0230	Submit Control Panel UFT Results Panel L14		-	Submit Control Panel UFT Results Panel L14		
Electrical Rough-In Conduit and Wire   10d   22Aug-17   05.Sep-17   24d   Sep-17   24d   24	SG1-CN0240	Demolition of Old Devices			1-CN0240 T Demotribu of		
Instal New Instrumentation   2d   08-Sep-17   07-Sep-17   38d   SSC1-NVICEO   19-Sep 17   18-Sep-17	SG1-CN0250	Electircal Rough-in / Conduit and Wire			31-CN0250 THE ENDINGS		
Install New Communication & PLC Panels   5d   09-Sup-17   14-Sep-17   36d   SGF-07474   1845 New Communication & PLC Panels   5d   15-Sep-17   21-Sep-17   21-Se	SG1-CN0260	Install New Instrumentation		_	CNGGGG Trestal New Instrumentation		
Perform Loop Checks	SG1-CN0270	Install New Communication & PLC Panels			0270 - El Install New Communication & PLC		
	SG1-CN0280	Perform Loop Checks			etto		

Project Start: 03-Jan-17
Project Finish: 10-Sep-20
Data Date: 03-Jan-17
Run Date: 15-Nov-16
Page 1 of 21

Actual Work
Remaining Work
Critical Remaining Work

Wilestone

PRINCE WILLIAM COUNTY SERVICE AUTHORITY
Distribution & Collection SCADA System Replacement
Proposed Baseline Project Schedule
( All Activities Sort )

N 1 996 N 1 99	2	75-58-9717 28-58-9717 38-6 70-0-0-0-17 38-6 70-0-0-17 38-6 70-0-0-17 38-6 70-0-0-17 21-40-971 57-6 71-40-971 21-40-971 57-6 71-40-971 21-40-971 58-6 71-40-971 21-59-971 38-6 72-58-971 21-59-971 38-6 72-58-971 72-60-971 38-6 72-58-971 72-60-971 38-6 72-58-971 72-60-971 38-6 72-58-971 18-58-971 57-6 72-58-971 18-58-971 57-6 72-58-971 18-58-971 57-6 72-58-971 18-58-971 58-6 72-58-971 18-58-971 38-6 72-58-971 18-58-97	
SG1-CN0330  Demdition of Old Devices  SG1-CN0330  SG1-CN0330  Fred Trans Rever bestimmentation  SG1-CN0330  Fred Trans Rever bestimmentation  SG1-CN0330  Fred Trans Rever bestimmentation  SG1-CN0330  Fred Trans Submit George Trans Rever Brand L17  SG1-CN0340  Fred Trans Submit George Trans Rever Brand Resolutes Test (ORT)  SG1-CN0440  SG1-CN0440  SG1-CN0440  SG1-CN0440  SG1-CN0440  SG1-CN0440  Fred Trans Submit Brackage  SG1-CN0450  Fred Trans Submit George Trans Rever Brand L17  SG1-CN0440  SG1-CN0440  Fred Trans Submit George Trans Rever Brand L17  SG1-CN0440  SG1-CN0450  Fred Trans Submit George Trans Rever Brand L17  SG1-CN0450  Fred Trans Submit George Trans Rever Submit George Tr		06-06-17 21-Aug-17 22-Aug-17 22-Aug-	
Sel - CAND310   Programming Submitted Peckage   Sel - CAND310   Chapter Submitted Peckage   Sel - CAND310   Chapter Submitted Month Peckage   Sel - CAND310   Chapter Submitted Month Peckage   Sel - CAND340   Denderfield of Denderfield Peckage   Sel - CAND340   Denderfield Office Peace   Sel - CAND350   Install New Communication & PLC Peace   Sel - CAND350   Perform Loop Checks   Sel - CAND350   Perform Loop Checks   Sel - CAND360   Perform Loop Checks   Sel - CAND360   Perform Cloop Checks   Sel - CAND40   Sel - CAND40   Perform Cloop Checks   Sel - CAND50		21-Aug-17 21-Aug-17 21-Aug-17 21-Sep-17 22-Sep-17 22-Sep-17 17-Oct-17 18-Sep-17 18-Sep-17 18-Oct-17 18-Oct	
SG1-CN0330   Programming Submitted Protecting Brand Life SG1-CN0330   Chrol Fathcristor / UTT & District Special Schild Schild Protection Schild Protection Schild Protection Schild Protection Schild Protection Schild		21-Aug-17 21-Aug-17 21-Sep-17 22-Sep-17 22-Sep-17 22-Sep-17 22-Sep-17 22-Sep-17 23-Sep-17 23-Sep-17 24-Oct-17 25-Sep-17 26-Oct-17 26-Oct-17 26-Oct-17 27-Oct-17 28-Aug-17 28-Aug	
SGI-CN0310 Completication / UFT Results Panel L16 SGI-CN0320 Completication / UFT Results Panel L16 SGI-CN0320 Demoficion of Old Devices SGI-CN0320 Demoficion of Old Devices SGI-CN0320 Perform Operational Peachers SGI-CN0320 Perform Operational Peachers SGI-CN0320 Perform Operational Peachers SGI-CN0440 Perform Operational Peachers SGI-CN0440 Demoficion of Old Devices SGI-CN0440 SGI-CN0440 Demoficion of Old Devices SGI-CN0440 Demoficion of Old Devices SGI-CN0450 SGI-CN0450 Perform Operational Peachers Test (ORT) SGI-CN0440 Demoficion of Old Devices SGI-CN0450 Perform Operational Peachers SGI-CN0450 Perform Completication / UFT & Detvery of Penel L17 SGI-CN0450 Perform Completication / UFT & Detvery of Penel L17 SGI-CN0450 Perform Completication / UFT & Detvery of Penel L14 SGI-CN0450 Perform Completication / UFT & Detvery of Penel L14 SGI-CN0550 Perform Side Acceptance Testing (SAT) L08 - Powels SGI-CN0550 Perform Side Acceptance Testing (SAT) L08 - Powels SGI-CN0550 Perform Side Acceptance Testing (SAT) SGI-CN0550 SGI-CN0550 Perform Side Acceptance Testing (SAT) SGI-CN0550 Perform Loop Checks SGI-CN0550 Perform Completional Reductions Testing Sate (ORT) SGI-CN0550 Perform Completional Reduction of URT Results SGI-CN0550 Perform Completional Reductions Testing Sate (ORT) SGI-CN0550 Perform Completional Reduction of URT Results SGI-CN0550 Perform Completional Reduction Set Completion S		21-Aug-77 21-Sep-77 21-Sep-77 22-Sep-77 22-Sep-77 22-Sep-77 22-Sep-77 24-Oct-17 24-Oct-17 24-Oct-17 24-Oct-17 24-Oct-17 24-Oct-17 24-Oct-17 24-Oct-17 25-Oct-17 25-Oct	
SG1-CN0320   Submit Counted Panel Util Results Panel Life   SG1-CN0320   Submit Counted Panel Util Results Panel Life   SG1-CN0320   Electrical Rough-in / Conduit and Wire   SG1-CN0320   Install Wew Communication & PLC Penels   SG1-CN0320   Perform Clop Checks   SG1-CN0320   Perform Clop Checks   SG1-CN0320   Perform Clop Checks   SG1-CN0420   Perform Clop Checks   SG1-CN0420   SG1-CN0420   Perform Clop Checks   SG1-CN0420   SG1		21-Aug-17 21-Sep-17 22-Sep-17 22-Sep-17 22-Sep-17 10-Oct-17 11-Oct-17 22-Aug-17 11-Oct-17 22-Aug-17 11-Oct-17 22-Aug-17 11-Oct-17 22-Aug-17 11-Oct-17 22-Aug-17 11-Oct-17 23-Oct-17 11-Oct-17 11-Oct	
Sel - 1-200390   Benferred Rough-In/ Conduit and Wire Sel - 1-200390   Benferred Rough-In/ Conduit and Wire Sel - 1-200390   Benferred Rough-In/ Conduit and Wire Sel - 1-200390   Perform Loop Checks   Sel - 1-200390   Perform Loop Checks   Sel - 1-200390   Perform Loop Checks   Sel - 1-200430   Perform Loop Checks   Sel - 1-2004410   Canpl Fatherister / UTT & Detector of Sel - 1-2004410   Canpl Fatherister / UTT & Detector of Sel - 1-2004410   Canpl Fatherister / UTT & Detector of Sel - 1-2004410   Perform Loop Checks   Sel - 1-2004410   Sel - 1-2004410   Perform Loop Checks   Sel - 1-2004510   Sel - 1-2004510   Perform Loop Checks   Sel - 1-2004510   Sel - 1-2004510   Perform Loop Checks   Sel - 1-2004510   Sel - 1-2004510   Perform Loop Checks   Sel - 1-2004510   Sel - 1-2004510   Perform Loop Checks   Sel - 1-2004510   Sel - 1-2004510   Perform Loop Checks		21-58p-17 25-58p-17 10-0ct-17 11-0ct-17 17-0ct-17 17-0ct-17 18-58p-17 18-58p	
10   10   10   10   10   10   10   10		25-58-PT   11-00-LT	
SG1-CN0330   Install New Communication & PLC Panels   SG1-CN0399   Perform Operational Readmens Treat (ORT)   SG1-CN0399   Perform Operational Readmens Treat (ORT)   SG1-CN0430   Perform Operational Readmens Treat (ORT)   SG1-CN0440   Submit Coincid Panel UFT & Delevery of Panel L17   SG1-CN0440   Submit Coincid Panel UFT Reads Panel L17   SG1-CN0440   Submit Coincid Panel UFT & Delevery of Panel L17   SG1-CN0440   Install New Instrumentation & PLC Panels   SG1-CN0450   Install New Instrumentation & PLC Panels   SG1-CN0460   Perform Coincid Panel UFT Reads Panel L17   SG1-CN0460   Perform Coincid Panel UFT Reads Panel L17   SG1-CN0460   Perform Coincid Panel UFT Reads Panel L14   SG1-CN0460   Perform Coincid Panel UFT & Delevery of Panel L14   SG1-CN0460   Perform Coincid Panel UFT & Delevery of Panel L14   SG1-CN0460   Perform Coincid Panel UFT & Delevery of Panel L14   SG1-CN0650   Submit Coincid Panel UFT & Delevery of Panel L14   SG1-CN0650   Submit Coincid Panel UFT Reads Panel L14   SG1-CN0650   Submit Coincid Panel UFT Reads Panel L14   SG1-CN0650   Install New Communication & PLC Panels   SG1-CN0650   Install New Communication & PLC Panels   SG1-CN0650   Install New Communication & PLC Panels   SG1-CN0650   Perform Bio Acceptance Testing (SAT)   SG1-CN0650   Perform Bio Acceptance Testing (SAT)   SG1-CN0650   Perform Bio Acceptance Testing (SAT)   SG1-CN0650   Perform Site Acceptance Testing (SAT)   SG1-CN0650   Perform Bio Acceptan		02-00-017 10-00-017 24-00-17 24-00-17 28-Aug-17 28-Aug-17 28-Aug-17 29-00-017 19-00-	
SG1-CN00309   Perform Loop Checks		10-00e177 24-00e177 24-00e177 28-Aug-177 28-	
961-CN0399 Perform Operational Readeness Test (ORT) 961-CN0395 Perform Site Acceptance Testing (SAT)  L17 - Berinott S 671-CN0410 961-CN0410 961-CN0410 961-CN0420 96		17-00-17 07-00-17 07-00-17 07-00-17 07-00-17 18-28-01-17 18-00-17	1
11		28-01-17 28-419-17 28-419-17 29-419-17 19-01-17	
SG1-CN0430 SG1-CN0440		28-Aug-17 28-Aug-17 18-Sep-17 10-Coc-17 12-Coc-17 12-Coc-17 13-Coc-17 13-Coc	
SG1-CN0430  SG1-CN0420  SG1-CN0420  SG1-CN0420  SG1-CN0420  SG1-CN0420  SG1-CN0420  SG1-CN0430  Experiment Control Peand UFT Results Panel L17  SG1-CN0430  Experiment Control Peand UFT Results Panel L17  SG1-CN0430  Install New Detrumentation  SG1-CN0430  Perform Loop Checks  SG1-CN0430  Perform Loop Checks  SG1-CN0430  Perform Doop Checks  SG1-CN0430  Perform Site Acceptance Testing (SAT)  L04 -Forwalts Greek I.  SG1-CN0500  Perform Site Acceptance Testing (SAT)  COMP Examination UFT Results Panel L14  SG1-CN0500  SG1-CN0500  SG1-CN0500  Experiment Submitted Package  SG1-CN0500  Demofation Odd Devices  SG1-CN0500  Perform Loop Checks  SG1-CN0500  Perform Loop Checks  SG1-CN0500  Perform Code Devices  SG1-CN0500  Perform Code Devices  SG1-CN0500  Perform Loop Checks  SG1-CN0600  Perform Checks  Perform Checks  Perform Checks  Perform Checks  SG1-CN0600  Perform Checks  SG1-CN0600  Perform Checks  Perform Checks  Perform Checks  Perform Checks  SG1-CN0600  Perform Checks  SG1-CN0600  Perform Checks  SG1-CN0600  Perform Checks  Perform Checks  Perform Checks  Perform Checks  SG1-CN0600  Perform Checks  SG1-CN0600  Perform Checks  Perform Checks  Perform Checks  Perform Checks  Perform Checks  Perform Che		28-Aug-17 29-Aug-17 16-Sep-17 02-Oct-17 19-Oct-17 19-Oct-17 19-Oct-17 19-Oct-17 07-Nov-17 05-Sep-17	1   1   1   1   1   1   1   1   1   1
SG1-CN0400  SG1-CN0400  SG1-CN0400  SG1-CN0400  SG1-CN0400  Submir Control Panel LIT Results Panel LIT SG1-CN0400  SG1-CN0400  SG1-CN0400  Install New Instrumentation  SG1-CN0400  Perform Operational Readness Test (ORT)  SG1-CN0400  Perform Operational Readness Test (ORT)  SG1-CN0400  Perform Operational Readness Test (ORT)  SG1-CN0500  Perform Operational Readness Test (ORT)  SG1-CN0500  Perform Operational Readness Test (ORT)  SG1-CN0500  Perform Loop Checks  SG1-CN0500  SG1-CN05			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
SG1-CN0440			
SG1-CN04590 Install flow between the control and Wireless SG1-CN04690 Install flow formunication & PLC Planets SG1-CN04690 Install flow formunication & PLC Planets SG1-CN04690 Perform Loop Checks SG1-CN04690 Perform Loop Checks SG1-CN04690 Perform Site Acceptance Testing (SAT) LOB + Power Site Acceptance Testing (SAT) Control and Control Planets SG1-CN0560 Perform Site Acceptance Testing (SAT) Control and Control Planets SG1-CN0560 Perform Site Acceptance Testing (SAT) Decided to Control and Control Planets UFT Results Planets SG1-CN0560 Perform Control Planets UFT Results Planets SG1-CN0560 Install Now Communication & PLC Planets SG1-CN0560 Perform Loop Checks SG1-CN0560 Perform Site Acceptance Testing (SAT) SG1-CN0560 Perform Loop Checks SG1-CN0560 SG1-CN0560 Perform Site Acceptance Testing (SAT) SG1-CN0560 Perform Loop Checks SG1-CN0660 Perform Loop Checks SG1-CN0660 Perform Checks SG1-CN0660 Perform Loop Checks SG1-CN0660 Perform Checks SG1-CN0660 Perform Loop Checks SG1-CN0660 Perform Loop Checks SG1-CN0660 Perform Loop Ch			
SS 1-CN0480   Instal New Instrumentation   SS 1-CN0480   SS 1-CN0510   SS 1-CN0510   SS 1-CN0510   SS 1-CN0510   SS 1-CN0510   SS 1-CN0510   Submit Control Penal Life Readeness Test (DRT)   L08 -Powells Creek Life Readeness Test (DRT)   L08 -Powells Creek Life Readeness Test (DRT)   SS 1-CN0510   Submit Control Penal Life Readeness Penal Life SS 1-CN0540   Submit Control Penal Life Readeness Penal Life SS 1-CN0540   Instal New Instrumentation & PLC Panels SS 1-CN0570   Instal New Instrumentation & PLC Panels SS 1-CN0570   Penform Operational Readiness Test (ORT)   SS 1-CN0520   Penform Control Penal LIFT Results Panel Life SS 1-CN0520   Submit Control Penal LIFT Results Panel LIG SS 1-CN0630   Penform Control Penal LIFT Results Panel LIG SS 1-CN0630   Submit Control Penal LIFT Results Panel LIG SS 1-CN0630   Penform Control Penal LIFT Results Panel LIG SS 1-CN0630   Demultion of Demultion Results Panel LIG SS 1-CN0630   Penform Loop Checks SS 1-CN0630			
SG 1-CN0470   Install New Communication & PLC Panels   SG 1-CN0499   Perform Operational Readmess Test (ORT)   SG 1-CN0499   Perform Operational Readmess Test (ORT)   SG 1-CN0499   Perform Operational Readmess Test (ORT)   SG 1-CN0530   Complete Acceptance Testing (SAT)   SG 1-CN0530   Complete Acceptance Testing (SAT)   SG 1-CN0530   Submit Control Panel UFT Results Panel L14   SG 1-CN0540   Dendition of Dendition of Old Devises SG 1-CN0550   Install New Communication of PLC Reads SG 1-CN0550   Install New Communication & PLC Reads SG 1-CN0550   Install New Communication & PLC Reads SG 1-CN0550   Perform Clope Checks SG 1-CN0550   Perform Clope Checks SG 1-CN0550   Perform Size Acceptance Testing (SAT)   SG 1-CN0550   Dendition of Old Devises SG 1-CN0550   Dendition of Old Devises SG 1-CN0550   Dendition of Old Devises SG 1-CN0550   Perform Loop Checks SG 1-CN0550   Perform Checks SG 1-CN0550   Perform Loop Checks SG 1-CN0550   Perform Checks SG 1-CN0550   Perform Loop Checks SG 1-CN0550   Perform Checks SG 1-CN0550   Perform Loop Checks SG 1-CN0550   Perform Checks SG 1-CN		12-0ct-17 19-0ct-17 31-0ct-17 07-Nov-17 05-Sep-17 06-Sep-17 19-0ct-17	2
SG1-CN04989 Perform Loop Checks SG1-CN04989 Perform Dopenbroal Readness Test (ORT) SG1-CN0498 Perform Dopenbroal Readness Test (ORT) SG1-CN0498 Perform Readness Test (ORT) SG1-CN0530 Perform Complication (UFT & Debtwy of Panel L14 SG1-CN0530 Submit Control Panel UFT Results Panel L14 SG1-CN0530 Submit Control Panel UFT Results Panel L14 SG1-CN0550 Install New Instrumentation SG1-CN0550 Install New Instrumentation SG1-CN0550 Install New Instrumentation SG1-CN0550 Perform Loop Checks SG1-CN0550 Perform Size Accorption of SG1-CN0550 SG1-CN0550 Perform Size Accorption Readness Test (ORT) SG1-CN0550 Perform Size Accorption of SG1-CN0550 SG1-CN0550 Perform Size Accorption Readness Test (ORT) SG1-CN0550 Perform Size Accorption Readness Size (ORT) SG1-CN0550 Perform Loop Checks		19-0ct-17 31-0ct-17 07-Nov-17 22-Nov-17 05-Sep-17 05-Sep-17 04-0ct-17 19-0ct-17	Corpus de la company de la com
SG 1–200496  SG 1–200496  Perform Site Acceptance Testing (SAT)  L04 –5rowits Compt.  SG 1–200406  SG 1–200405  Programming Submitted Package SG 1–200520  Submit Control Panel UFT Results Panel L14 SG 1–200520  Submit Control Panel UFT Results Panel L14 SG 1–200520  Submit Control Panel UFT Results Panel L14 SG 1–200520  Install New Instrumentation SG 1–200530  Perform Loop Cheevis SG 1–200530  Perform L00 Cheevis SG 1–200530  Perform Loop Cheevis SG 1–200630  Perform Loop Cheevis SG 1–200630  Perform Coperational Readeness Testing (SAT) SG 1–200630  Perform Coperational Readenes SG 1–200630  Perform Loop Cheevis		31-0ct-17 07-Nov-17 05-Sep-17 05-Sep-17 04-0ct-17 19-0ct-17	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
SG 1–20065 (See Perform Siles Acceptance) Testing (SAT)  L08 +Powalis Creek LS  SG 1–200510 (Cmpl Fathication / UFT & Dathvery of Parnel L14  SG 1–200500 (Short Corrido Parel L14  SG 1–200540 (Short Corrido Parel L14  SG 1–200540 (Short Corrido Parel L14  SG 1–200550 (Testine Parel Parel Parel L14  SG 1–200550 (Testine Parel Parel Parel L14  SG 1–200550 (Perform Corrido Parel L16  SG 1–200550 (Perform Corrido Parel L17  SG 1–200550 (Cmpl Fathication Parel Parel L19  SG 1–200650 (Cmpl Fathication Parel Parel L19  SG 1–200650 (Cmpl Fathication Parel L19  SG 1–200650 (Cmpl Fathication Parel Parel L19  SG 1–200650 (Cmp		05-Sep-17 05-Sep-17 05-Sep-17 06-Oct-17 19-Oct-17	Perform Ste Acceptance     Chora selection ( UFT & Defivery of     Perform Stemular Processor     Perform Stemular Processor     Stemular Stemular Processor     Stemular Stemular Processor     Stemular Stemular Processor     Stemular Stemula
SG1-CN0630  SG1-CN0630  SG1-CN0630  SG1-CN0630  SG1-CN0630  Submit Countrol Panel LIT Results Panel LIT4 SG1-CN0630  SG1-CN063		05-Sep-17 05-Sep-17 04-Oct-17 19-Oct-17	
SG1-CANDGSO Submid Control Panel UFT Results Panel L14 SG1-CANDGSO Submid Control Panel UFT Results Panel L14 SG1-CANDGSO Submid Control Panel UFT Results Panel L14 SG1-CANDGSO Install New Instrumentation SG1-CANDGSO Install New Instrumentation SG1-CANDGSO Perform Loop Checks SG1-CANDGSO Perform Loop Checks SG1-CANDGSO Perform Size Acceptance Testing (SAT) L09 - Dewys Greek LS SG1-CANDGSO Perform Size Acceptance Testing (SAT) SG1-CANDGSO SG1-CANDGSO SG1-CANDGSO SG1-CANDGSO SG1-CANDGSO Perform Control Panel UFT Results Panel LUG SG1-CANDGSO SG1-CANDGSO SG1-CANDGSO SG1-CANDGSO SG1-CANDGSO Perform Control Panel UFT Results Panel LUG SG1-CANDGSO SG1-CANDGSO Perform Control Panel UFT Results Panel LUG SG1-CANDGSO Perform Loop Checks		05-Sep-17 04-Oct-17 19-Oct-17 23-Oct-17	
SG1-CN0520 Submit Control Panel LIFT Results Panel L14 SG1-CN0540 Submit Control Panel LIFT Results Panel L14 SG1-CN0540 Demultion of Old Devices SG1-CN0550 Install New Yorgammination SG1-CN0550 Install New Communication & PLC Panels SG1-CN0550 Perform Operational Readness Test (ORT) SG1-CN0550 Perform Site Accorption of Testiles Panel L09 SG1-CN0550 Perform Site Accorption of Testiles Panel L09 SG1-CN0550 Perform Control Panel UFT Results Panel L09 SG1-CN0550 Perform Control Panel UFT Results Panel L09 SG1-CN0550 Perform Control Panel Wre SG1-CN0550 Install New Venturmentation SG1-CN0550 Perform Loop Checks SG1-CN0550 Perform Loop Checks SG1-CN0550 Perform Loop Checks		05-Sep-17 04-Oct-17 19-Oct-17 23-Oct-17	0.00
SG1-CN0550 Electrical Rough-In Control and Wire SG1-CN0550 Electrical Rough-In Control and Wire SG1-CN0550 Electrical Rough-In Control and SG1-CN0550 Electrical Rough-In Control Peacles SG1-CN0550 Perform Loop Checks SG1-CN0550 Perform Coop Checks SG1-CN0550 Perform Control Peacle ID F7 Results Pend L09 SG1-CN0550 Perform Control Peacle ID F7 Results Pend L09 SG1-CN0550 Perform Control Pend ID F7 Results Pend L09 SG1-CN0550 Perform Control Pend ID F7 Results Pend L09 SG1-CN0550 Electrical Rough-In Control Pend IN Results Pend L09 SG1-CN0550 Electrical Rough-In Control Pend ID SG1-CN0550 SG1-CN0550 Pend Pend Pend Pend Pend Pend Pend SG1-CN0550 Pend Pend Pend Pend Pend Pend Pend SG1-CN0550 Pend Pend Pend Pend Pend Pend Pend Pend		04-0ct-17 19-0ct-17 23-0ct-17	
SG1-CN05500 Exerticated Rough-Information Whee SG1-CN05500 Install whew instrumentation & PC Panels SG1-CN05500 Install whew instrumentation & PC Panels SG1-CN05500 Perform Loop Checks and SG1-CN05500 Perform Loop Checks SG1-CN05500 Perform Site Acceptance Testing (SAT) CL09 - Daways Creek LS Perform Site Acceptance Testing (SAT) CL09 - Daways Creek LS Checks SG1-CN05500 Cmyl Exertication (LHT Reals Panel LO9 SG1-CN05500 Perform Control Panel LU9 SG1-CN05500 Exerticated Rough-Information Conduction Control Panel LU9 SG1-CN05500 Exerticated Rough-Information SG1-CN05500 Install New Instrumentation SG1-CN05500 Install New Instrumentation SG1-CN05500 Perform Loop Checks SG1-CN05500 Perform Dop Checks S		19-Oct-17 23-Oct-17	1000
SG1-CN0500   Institut New Instrumentation   SG1-CN0500   Institut New Instrumentation   SG1-CN0500   Institut New Instrumentation   SG1-CN0500   Perform Loop Checks   SG1-CN0500   Perform Cope carbonal Readeness Test (DRT)   SG1-CN0500   Perform Operational Readeness Test (DRT)   SG1-CN0500   Perform Operational Readeness Test (DRT)   SG1-CN0500   Cmp1 Education / UFT Results Panel L09   SG1-CN0600   Perform Side Control Panel UFT Results Panel L09   SG1-CN0600   Perform Readeness SG1-CN0600   Institut New Institutinentation   SG1-CN0600   Institution New Institution   SG1-CN0600   Institution New Institution   SG1-CN0600   Perform Loop Checks   SG1-CN0600   Perform Coperational Readmess Test (ORT)   SG1-CN0600   Perform Coperational Readmess Test (ORT)   SG1-CN0600   Perform Coperational Readmess Test (ORT)   SG1-CN0600		23 Oct 17	0
SG1-CN0570   Instal New Communication & PLC Panels   SG1-CN0550   Perform Operational Readness Test (P(T))   SG1-CN0560   Perform Operational Readness Test (P(T))   SG1-CN0560   Perform Operational Readness Test (P(T))   SG1-CN0620   Perform Site Acceptance Testing (SAT)   SG1-CN0620   Submit Control Panel UTP Results Panel L09   SG1-CN0620   Submit Control Panel UTP Results Panel L09   SG1-CN0630   Perform Operational Package   SG1-CN0630   Demidlion of Old Devices   SG1-CN0630   Instal Mew Centrumetation   SG1-CN0630   Instal Mew Centrumetation   SG1-CN0630   Instal Mew Centrumetation   SG1-CN0630   Perform Loop Checks   SG1-CN0630   Perform Deperational Readness Test (ORT)		200	10950N
SG1-CN0580 Perform Loop Checks SG1-CN0586 Perform followerbrand Readness Test (ORT) SG1-CN0586 Perform followerbrand Readness Test (ORT) SG1-CN0600 SG1-CN0600 SG1-CN0600 SG1-CN0600 Demofation of Odd Devices SG1-CN0600 Electrical Rough-In / Control and Wre SG1-CN0600 Install New Instrumentation SG1-CN0600 Install New Instrumentation SG1-CN0600 Install New Ormanization & PLC Paines SG1-CN0600 Install New Ormanization & PLC Paines SG1-CN0600 Perform Loop Checks SG1-CN0600 Perform Loop Checks		30-Oct-17	CN057
SG1-CN0550   Perform Operational Readeness Test (ORT)		06-Nov-17	CN058041 Perform Loop Checks
SG1-CN0556   Perform Site Acceptance Testing (SAT)		08-Nov-17 15-Nov-17 34d	\$GT+CN/glag4** Perform Operational/Readiness Test (ORT)
109 - Downys Creek I.S   Charlet Section   UPT & Detroit LD9   SG 1-AV0600   Sumpl Fabrication / UPT & Detroit LD9   SG 1-AV0600   Summir Control Panel UPT Results Panel LD9   SG 1-AV0600   Programming Submitted Package   SG 1-AV0600   Demidlion of Old Devices   SG 1-AV0600   Electrical Rough-Inf Control and Wire   SG 1-AV0600   Instal New Instrumentation   SG 1-AV0600   Instal New Communication & PLC Panels   SG 1-AV0600   Perform Loop Cheeks   SG 1-AV0600   Perform Loop Cheeks   SG 1-AV0600   Perform Loop Cheeks   SG 1-AV0600   Perform Departition & Rough Perform Control and Panels   SG 1-AV0600   Perform Departition & Rough Perform Control and Panels   SG 1-AV0600   Perform Operational Readiness Test (ORT)			SS + Chillaga + Taylor Sie Acceptange Testing (\$AT)
		11-Dec-17	
	90 PS	-	-0-
		12-Sep-17	- Storing Control Prince of Prince Control Prince C
		20 Oct 17 23 Oct 17 334	COS CHECK THE TOTAL COST COST COST COST COST COST COST COST
	10d 24-C	-	- CN0650
		08-Nov-17	CN0860 Instal New Instrumentation
	1-60 PS	-	\$C CANGITY III Issai New Communication & PLC Panels
		17-Nov-17 27-Nov-17 33d	SQL-C\Quad Quad Paricom Loop Checks
		-	- - - - - - - - - - - - - - - - - - -
		11-Dec-17	SOS-CONDINGED Perform Site Acceptance Tosifing (SAT)
L42 - Ridgeleigh LS#1 - Submersible PS	72d 13-5	29 Dec-17	
SC1-CN0710 Cmpl Fabrication / UF 1 & Delivery or Panel L42		14-Vep-17 14-Vep-17 78d	SCHOOL OF A CONTROL OF A CONTRO
		_	A Committee of the Comm
		08-Nov-17	Soci-ty/Wyd-E Dimpagino Old Devices
		27-Nov-17	CN0756
SG1-CN0760 Install New Instrumentation	2d 28-h	28-Nov-17 29-Nov-17 31d	Sport Autority   Install New Instrumentation
			SST-CANTO TO THE INSIGN New Communication & PLIC Panels
		$\rightarrow$	CN0780
		-	08-18-18-18-18-18-18-18-18-18-18-18-18-18
SG1-CN0/95 Perform Site Acceptance Testing (SAT)	1-17 B8	21-Dec-17 29-Dec-17 31d	SCH-COCKING Mile Acceptance (esting (SAL)
SG1_CN0810 Complete Substitute T& Delivery of Panel 1.43			SQL-Dillard Parish Anna Parish and Parish and 143
	$^{+}$	-	Ī
		-	Programming Submittal Packs
	11		: 1

Project Start: 03-Jan-17 Project Finish: 10-Sep-20 Data Date: 03-Jan-17 Run Date: 15-Nov-16 Page 2 of 21

PRINCE WILLIAM COUNTY SERVICE AUTHORITY
Distribution & Collection SCADA System Replacement
Proposed Baseline Project Schedule
( All Activities Sort )

Actual Work

Remaining Work

Critical Remaining Work

The control of the co	ivity D		Activity Name		Orig Dur	Start	usuu.	Float Oct Nov Dec Jan Feb Mar Apr May	Jun Jul Aug Sep	Oct Nov Dee Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dee Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dee Jan Feb Mar Apr May Jun	9
Record Section 1   1   1   1   1   1   1   1   1   1		SG1-CN0840	Demolition of Old Devices		i			-		Demolition of Old Devices	
Section   Sect		SG1-CN0850	Electircal Rough-in / Conduit.	and Wire		Nov-17 11-L	-	77	SG1-GN	Electircal Rough-in /	
Particular Colored State   Particular Colored		SG1-CN0860	Instal New Instrumentation			Dec-17 13-L		7	30.1	Instal New Instrume	
According to the control of		SG1-CN0870	Instal New Communication &	& PLC Panels		Jec-17 20-L	-	77	\$G\$+	Ŧ	
Particular Schoolstoon Street (P. O.)   March 10 April		SG1-CN0880	Perform Loop Checks				-		- <del>S</del>	O-10 Perform Loop Che	
Activity 1989   Control Stationaries   Part   P		SG1-CN0890	Perform Operational Readine.	ess Test (ORT)		lan-18 08-	-	7		890 📶 Perform Operal	
Confidencial Life Schemering   Section 19		SG1-CN0895	Perform Site Acceptance Tes.			lan-18 16-			<u> </u>	10895 Perform Site A	
Section of posterior between 19   20 Section 19 Section 19   20 Section 19 Sect		L56 - Belmont To	own Center LS - Submersible PS					70			
Programmer Schoolman Products and Wiley Control (1992)   Product Cont		SG1-CN0910	Cmpl Fabrication / UFT & Del	slivery of Panel L56					SG1-CN0910	abrication / UFT & Delive	
Committee Standing Reading   Contact and Wiles   Contact and Wil		SG1-CN0920	Submit Control Panel UFT Re	esults Panel L56	P0	93	_	T	<b>f</b> i	Submit Control Panel UFT Results Panel Life	
Previous of the Content and Wise   24   20-20-77   24-40   2		SG1-CN0930	Programming Submittal Pack	(age		Nov-17	$\vdash$	D		Programming Submittal Package	
Percent Books   Control and Vive   101 October 7 20cm		SG1-CN0940	Demolition of Old Devices			Jec-17 06-1	-	T	8017	molition of Old De	
February 1992   February 199		SG1-CN0950	Electircal Rough-in / Conduit of	and Wire		Jec-17 20-t	-		SG14C	Electircal Rough-in	
Perfect to produce it is a Control of the Control		SG1-CN0960	Instal New Instrumentation				-	35		distal New Instru	
Perform Logg Control Processes   Feb. Charges   State   Stat		SG1-CN0970	Instal New Communication &	& PLC Panels		Dec 17 03.	_			nstal New Com	
Author to Demonstrate of Render)   Section 19   Section		SG1-CN0980	Perform Loop Checks			lan-18 10-		35	<u>м.</u>	80 FI	
15.5. Selected Review (St. 67)   55.0   2-4.0-0.0   5.0   2-4.0-		SG1-CN0990	Perform Operational Readine	ess Test (ORT)			_	-		Deed Perform Ope	
Control of the Cont		SG1-CN0995	Perform Site Acceptance Tes		-1	Jan-18 30-				109895 Perform Site	
Section   Control broad bro		L59 - Powells Lan	inding LS - Submersible PS			Oct-1/ 13-		70			
Pacific Control and Vive Products 2004   1.00		SG1-CN1110	Cmpl Fabrication / UF1 & De.	elivery of Panel L59		-	-		SC1-CN1110	abrication / UFT & Deliv	
Order for the control and where some and control a		SG1-CN1120	Submit Control Panel UF I Re	esuits Panel L59		-	-		F1.	Panel UF 1 Kes	
Description of the Extension of the Communication & R. C. Pender I (160 - 200 - 17 - 160 - 17 - 17 - 17 - 17 - 17 - 17 - 17 - 1		SG1-CN1130	Programming Submittal Pack.	kage	$\top$	Nov-17	-			Programming Submittal	
Perform Record		SG1-CN1140	Demonition of Old Devices			71-090	-			TI-TI-TI-TI-TI-TI-TI-TI-TI-TI-TI-TI-TI-T	
Perform Logo Diversisher   2 California   2 Calif		961-011130	Elecurical Rough III / Conduin.	and wife	+		-		9	Decilical York	
Perform to personal process   State		961-CN1180	Install New Instrumentation			Jan 18 12-	-			Install New Ins	
Perform Coordinational Reachiness Test (ORT)   562 - 12   15 - 16   15   15   15   15   15   15   15		SG1-CN11/0	Install New Communication &	& PLC Panels			-			CIVIL DO LESS NEW C	
Description of the control Period of Tool Period Signature Testing (SM)         Seq. (Ordinal Period Signature Testing (SM		SG1-CN1180	Perform Loop Checks	(Bod O)	$^{+}$		-			renorm Loop Checks	
Conversion   Co		SC1 CN1190	Perform Operational Readine	ess lest (ORI)		Jan 16 Ub				Perorin Operational Readiness Test	
Complexity of Panel 174         Seq 1-County (Panel 1744)         Seq		CELLVO-100			-1	-60-10 13-					
Supprisonment   Submit   Package		L/4 - Neabsco Ls	- AB			John 17 18-0	_		CN123		
Programming Submittal Pockage  Declared Submittal Declared Submittal Pockage  Declared Submittal Declared Submitt		SG1-CN1220	Submit Control Dated HET Bo	series Danel 74	+	_	-	,		ontrol Panel 15 T Per	
Demonstrate of Ott Devices   2		SG1-CN1220	Submit Control Panel OF 1 Re	esuis Panel L/4	т		-				
Electrical Rough in Conduit and Wive   10d   Classifier   2		SG1-CN1230	Demolition of Old Desiron	yage yage			-			SAMPLE DEPORTION OF O	
Perform Operations Readness Test (ORT)   Sci 12-tain-18   35d		SG1-CN1250	Electional Douglain / Conduits	and Mira	T		-	,   -	<u></u>	٠, [	
Perform Loop Concentration of PLC Panels   3-2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2		SG1-CN1260	Inetal New Instrumentation	all will a		an 18 24	_			L	
Perform Loco Checks Perform Control Pancients (SAT) Perform Loco Checks Perform Control Pancients (SAT) Perform Control Panci		SG1-CN1270	Inotal New Communication &	O Donog	T	an-18 31-	_	,   -		Deta New	
Perform Control Readmess Test (ORT) 55 (14-Eeb-18 21-Ee-18 31d Perform Control Readmess Test (ORT) 55 (14-Ee-18 31d Perform Control Perform Control Readmess Test (ORT) 55 (14-Ee-18 31d Perform Control Perform Control Pere Lit 1 56 (14-Ee-18 31d Perform Control Perform Control Pere Lit 1 56 (14-Ee-18 31d Perform Control Pere Lit		SG1-CN1280	Parform Loop Chacks	X LC Lallets			-			Berform	
Perform Stockers   Secreptions   Secreption   Secrepti		SG1-CN1290	Perform Operational Reading	see Tast (OBT)		ob-18 21-6		,   -		200 Parform	
Complete britation (LPT & Delevery of Panel L11		SG1-CN1200	Perform Site Acceptance Tee	stro (SAT)		-12 OF-02		,  -		1300 Perform	
Complication / UPT & Delivery of Panel LTT         Set         19-Oct-17         103d         SO -CN1310-1         Figure Incidence of Panel LTT         Programming Summaria Package         Programming Package         Progra		L11 - "B" Station L	1		-	Oct-17 14-8	_	, ,			
Submit Control Panel UFT Results Panel UFT Res		SG1-CN1310	П		-				CN1310	Cmd Fabrication 2 UFT & Delivery of Panel L11	
Programming Submittad Package   Od 21-Dec-17   Std		SG1-CN1320	Submit Control Panel UFT Re	esults Panel L11			-			Submit Control Planel UPT Results Panel L11	
Demottion of Old Devices   22-Jan-18   24-Jan-18		SG1-CN1330	Programming Submittal Packa	(age		Jec-17	áo	-		Progretiming Submittal Package	
Ebertreat Rough-H / Conduit and Wire   Conduit and Wire   Conduit and Wire   Conduit and Wire   Soci-Originary   Soci-Origi		SG1-CN1340	Demolition of Old Devices			an-18 24.		-		Demplition of	
Install New Instrumentation   2d 08-Feb-18 334   Septembries   Septemb		SG1-CN1350	Electircal Rough-in / Conduit a	and Wire				-			
Install Nav Communication & PLC Panels   56   12-Feb-18   334   Septembre		SG1-CN1360	Instal New Instrumentation								
Perform Loop Cheecks   Secretaria   Secre		SG1-CN1370	Install New Communication &	% PLC Panels		eb-18 16-				<u>7</u> 1	
Perform Operational Readiness Test (ORT)   561 (01-Mail-18) 31d   SG1-CN1894*   Parform Size Accordance Testing (SAT)   562 (01-Mail-18) 31d   SG1-CN1894*   Parform Size Accordance Testing (SAT)   563 (01-Mail-18) 31d   SG1-CN1894*   Parform Size Accordance Testing (SAT)   SG1-CN1894*   Parform Operational Readiness Tost (ORT)   SG1-CN1894*   Parform Operational Readines		SG1-CN1380	Perform Loop Checks			-eb-18 26-	$\rightarrow$			Perform	
Perform Star Accorptince Testing (SAT)   102d 26-0cu-18   14 Main-18   31d   55 CM 1339   102d 26-0cu-18   14 Main-18   31d   55 CM 1339   102d 26-0cu-17   106d   52 CM 1349   102d 26-0cu-17   106d   102d 26-0cu-17   106d 26-0cu		SG1-CN1390	Perform Operational Readine	ess Test (ORT)		Mar 18 07.	-	70		Perfo	
Cmpf abrication / UFT & Delivery of Panel L18         Vida 25-00-17 (10ke)         Total Abrillands         SGI-CN1410-17 (10ke)         Programment of Panel UFT Results Panel L18         On On-Lan-18		SG1-CN1395	П		_	Mar-18 14-				- Perto	
Submit Control Panel UT Results Panel List   Ord   Ord-Nort 1   Ord   Ord-Nort 2   Ord   Ord-Nort 2   Ord   Ord-Nort 2		L18 - Dumfries LS				Jot-17 28					
Programming Submitted Peckage of the Control of t		SG1-CN1410	Cmpl Fabrication / UF L& De.	elivery of Panel L18			_	Q T	-CN 14 E	8 L	
Francisco Chiecke   Control and Wire   Control an		SC1 CN1430	Drogramming Schmittel Doors	double Fairer Lio			_	2		5 - 5	
Electrical Rough—I/ Conduit and Wire   Card Control of Card		SC1 CN1440	Domolitics of Old Desiron	0000		00 40 VO.	_	,   -		ijέ	
Carcin Number   Carcin Numbe		SG1-CN1440	Election Double to Conduit	Miro		- SU 01-U9-	_	3 -		7	
Install New Communication   SEC		SC1-CN1460	petal New petrumontation	O NAME OF THE OWNER OWNER OF THE OWNER OF THE OWNER OWNE		20 10 40		,   -			
Perform Loop Checks         5d         09-Mar-18         14-Mar-18         24d         SGI-CN14804-19         Perform Checks           Perform Operational Readiness Test (ORT)         5d         15-Mar-18         21d         SGI-CN14804-19         Perform Checks		SG1-CN1470	Install New Communication &	2 D C Panak	$^{+}$	dar=18 07=6		,   -			
Perform Operational Readiness Test (ORT) 55 of 15-Mar-18 21-Mar-18 21-d		SG1-CN1480	Perform I oon Checks	2010		far 18 14-6	_	,   -			
		SG1-CN1490	Perform Operational Readine:	3SS Test (ORT)		Aar -18 21-1		,		1-CN1490	
					11				-	1	

Project Start: 03-Jan-17 Project Finish: 10-Sep-20 Data Date: 03-Jan-17 Run Date: 15-Nov-16 Page 3 of 21

Actual Work

Remaining Work

Critical Remaining Work

Wilestone

PRINCE WILLIAM COUNTY SERVICE AUTHORITY
Distribution & Collection SCADA System Replacement
Proposed Baseline Project Schedule
( All Activities Sort )

## Appendix J

Design Review Approximate Sequence and Duration

