

Galt Court Water Main Replacement and Upgrade WAT-162
Project Summary
Project Commencement: Anticipated construction date, Spring of 2019

Project Description: Replacement of approximately 885 feet of 4-inch cast iron pipe and service lines constructed in 1971. The Galt Court project is a water main replacement and upgrade project.

Scope of Work: The project will consist of replacing the existing 4-inch cast iron pipe with new 4-inch, 6-inch and 8-inch ductile iron pipe along with new water service lines. The water main replacement will improve the fire flow and system reliability to the 38 dwelling units in the community.

Project timeline (all dates are approximate):

Design and permitting	Spring 2017- Summer 2018
Community Outreach	Winter 2018-19 (approximately one month before construction commences)
Replacement of current meters	Meters have been replaced
Project Commencement	Spring 2019
Anticipated project duration	Estimate 3-4 months

Project benefits:

- Increased water supply
- Improved fire flows to the Georgetown Village Community
- Enhanced overall system reliability

Project impact on residents/customers:

- Approximately 38 single-attached units will be impacted in the Georgetown Village Community due to construction. The impacted residents will receive a minimum of 24-hour notice in the event of a service interruption.
- Other potential impacts on the residents/customers are:
 - Traffic
 - Road construction
 - Dirt (there will be daily cleanup during construction to control dirt and dust)
 - Noise associated with construction
 - Parking accessibility (resident parking may be limited during construction hours)

Project Manager:

M. Elena Herrera, Prince William County Service Authority
E: galtcourt@pwcsa.org
P: 703-335-8927

Design Engineer:

Mark Liberati, P.E.;
Pennoni Inc.