

PWCSA CAPITAL IMPROVEMENT PROJECT DATA SHEET

PROJECT INFORMATION

Project Name: Poplar Lane Water Main
CIP Number: WAT-125
JDE Number(s): Not Assigned
Location: Poplar Ln., Riverview Ln. and Devils Reach Rd.
Pressure Zone: WL – Woodbridge
Sewershed: OP – Occoquan Plant
Magisterial District: OC – Occoquan
Criteria: 1, 2, 3, 4, 5
Project Estimate: Order of Magnitude
Estimate By: Engineering and Planning Division

PROJECT DESCRIPTION

Project Description: Construction of a parallel water main along Poplar Lane to supplement the existing 16-inch main along Occoquan Road in case of a water main break on Washington Street near Center Lane. This project will construct approximately 7,500 feet of 16-inch and 500 feet of 8-inch waterlines along Poplar Lane, Riverview Lane and Devils Reach Road.

Project Benefit: This project will improve fire flow, reliability, and service to customers in the area by supplementing the existing 16-inch main along Occoquan Road and providing an alternate flow path in case of a water main break on Washington Street near Center Lane.

Source Derivation: Engineering and Planning, and Operations and Maintenance Divisions

PROJECT PICTURE



This CIP is marked as a future project.

Proposed Funding Sources	
Exp. Fund (02) – Availability Fees	-
Commit. Fund (03) – Availability Fees	-
Repl. Fund (04) – User Rates	100%
Other Contrib. – Development Contributions	-
PROJECT TOTAL	100%