

PWCSA CAPITAL IMPROVEMENT PROJECT DATA SHEET

PROJECT INFORMATION

Project Name: "G" Street Replacement and Upgrade
CIP Number: WAT-147
JDE Number(s): 24WWLM3001
Location: Occoquan Rd. to Baxter St.
Pressure Zone: WL – Woodbridge
Sewershed: BM – Belmont Lift Station
Magisterial District: WB – Woodbridge
Criteria: 1, 4, 5
Project Estimate: Order of Magnitude
Estimate By: Engineering and Planning Division

PROJECT DESCRIPTION

Project Description: Construction of approximately 2,800 feet of 12-inch water main along "G" Street from Baxter Street to Occoquan Road to replace the existing 6-inch cast iron main. The main will connect the 16-inch transmission main along Baxter Street to the new 16-inch water main in Occoquan Road.

Project Benefit: This project will upgrade a major water line loop in the northern end of the Woodbridge Pressure Zone. This project will improve the water supply and fire flows in the northern commercial section of the pressure zone and improve system reliability and flexibility.

Source Derivation: Engineering and Planning Division; Managed By Engineering and Planning

PROJECT PICTURE



This CIP is marked as a future project.

Proposed Funding Sources	
Exp. Fund (02) – Availability Fees	-
Commit. Fund (03) – Availability Fees	-
Repl. Fund (04) – User Rates	100%
Other Contrib. – Development Contributions	-
PROJECT TOTAL	100%